

**Reconstruction of the terminal
building of “Eugen Doga”
International Airport - Chisinau
(cadastral no. 0100120.236.01),
including partial replanning of
internal spaces and building
extension**

(name of the facility)

WinEstimate

**Cost Estimate-Offer No. 2-1-3
BLOCK 1A Phase 2
Structural Steelwork Structures (ST section)**
(name of works)

Coefficient for basic wages = 1,150

Coefficient for cost of machine operation = 1,150

No.	Norm symbol and resource code	Description of works	Unit of measure (U.M.)	Quantity according to the design data
1	2	3	4	5
		1. Structural Steelwork Structures		
1	CL08A	Factory-fabricated metal elements (columns, beams, trusses), delivered fully assembled, mounted on site, in lightweight structural framework	tonne	15,47
	7214210026800	Metal structure installer	man-hours	622,668
	9310060019920	Worker servicing ST	man-hours	88,953
	2811106301200	Metal elements	kg	15 779,40
	2775276309886	Metal fabrications embedded in concrete	kg	30,94
	2873155901340	Welding electrode for low-alloy steel S 1125/2 E 50B 4	kg	6,962
	2874115842700	Hexagonal nut M20	pieces	100,555
	2874115802500	Hexagonal head bolt M20	pieces	100,555
	2874115883700	Washer M20	pieces	100,555
	2413547308164	Technical calcium carbide (carbide) S102	kg	1,006
	2411115904512	Technical gaseous oxygen S2031	m ³	1,547
	4011106202741	Electrical energy	kw	6,962
	3410520006728	Pneumatic crane up to 9.9 ton-force (TF) with lattice boom	machine-hours	2,669
2	IzD10A	Anticorrosion painting by brush of metal products and structures with one coat of anticorrosive primer based on red lead and two coats of chlorinated rubber	tonne	15,47

1	2	3	4	5
		enamel.		
	7141020013400	Industrial painter	man-hours	114,571
	2430116100000	Chlorinated rubber enamel	kg	120,666
	2430226100814	Red lead primer G 355-6	kg	60,333
	2430226109420	Thinner for anticorrosive varnishes D.006-1 NI 1708-61 A1	kg	8,509
	2320166200676	White spirit	kg	30,166
	1711317306661	Cleaning cotton	kg	15,083
3	CL31A	Protection of metal structures with intumescent fire-retardant coating "Pirex-Metal Plus"	m ²	418,00
	7134050013250	Insulator	man-hours	697,015
	9310060019920	Worker servicing ST	man-hours	96,14
	2430126104976	Fire-retardant paint "Pirex-Metal Plus" R90*	kg	794,20
	2430226101026	Anticorrosive primer GF 021	kg	56,43
	1711317306661	Cleaning cotton	kg	21,318
	2320166200676	White spirit	kg	62,70
	2681126001472	Dry sandpaper 23 × 30 cm, grit 6	pieces	209,00
Total Structural Steelwork Structures				
Total				
Social fund				
Total				
Transportation of materials				
Storage expenses				
Direct expenses				
Overhead expenses				
Total				
Estimated profit				

**Total estimate:
Including wages**

Subsemnata, Poleacova Ana, traducător autorizat, (limba Engleză), certific exactitatea traducerii cu textul înscrisului, care a fost vizată de mine și port răspundere personală pentru corectitudinea traducerii actului.

Undersigned, Poleacova Ana, sworn translator, (English language), certify the authenticity of the translation which corresponds to the text of the authentic document, which was confirmed by me and I do take personal responsibility for the truthfulness of the translation.

26.02.2026

*Semnătura
Signature*

*Translator's stamp: /Republic of Moldova,
Authorization AT No. 461 of 10.02.2014, AT No. 500 of 21.07.2014,
English, French, Romanian, Russian, Translator*