

Beneficiar "FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924

Antreprenor "Alpro-Construct" SRL, IDNO 1009600009470

Obiect *Ремонт бетонного пола склада форм и рамы*

Contract Nr. 14891

DEVIZ LOCAL № 14891-3

Устройство бетонного пола склада форм

Valoarea de deviz 119 782.26 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	RpCE09B	Instalare pelicula	m2	150.000	9.26	1 389.63
					3.26	489.56
2	RpCD08C	Instalare plasa din armatura (150m2)	kg	489.600	24.97	12 227.58
					3.92	1 917.49
3	CG22A2	Pardoseli din beton M300, cu strat consolidat (H=120mm, k=1.2 mater.)	m2	150.000	421.96	63 294.01
					135.99	20 398.13
Total			Lei			76 911.22
Asigurarea sociala			24.00 %			5 473.24
Transportarea materialelor			5.00 %			2 495.27
Total						84 879.72
Cheltuieli de regie			12.00 %			10 185.57
Total						95 065.29
Beneficiu de deviz			5.00 %			4 753.26
Total						99 818.55
TVA			20.00 %			19 963.71

Total deviz:**Lei****119 782.26**

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **"FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Ремонт бетонного пола склада форм и рамы**Contract Nr. **14891**

Anexa Nr. 1

Catalog de preturi unitare

Устройство бетонного пола склада форм

(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	RpCE09B	Instalare pelicula	m2			9.26
						3.26
	7134030012200	Izolator hidrofug	h-om	0.0600	94.60	3.26
	2682132603	Pelicula PE	m2	1.1200	4.31	4.88
	2922140006702	Macara de fereastr	h-ut	0.0150	75.00	1.13
2	RpCD08C	Instalare plasa din armatura (150m2)	kg			24.97
						3.92
	7123020011140	Fierar beton	h-om	0.0310	94.60	3.37
	9310060019920	Muncitor deservire CM	h-om	0.0050	94.60	0.54
	28731220511	Plase arm. Bp5*100*100	kg	1.0100	20.25	20.45
	2710602000030	Otel beton profil neted OB 37 STAS 438 D = 6 mm	kg	0.0050	12.98	0.06
	2734113803116	Sirma neagra moale d = 1 mm	kg	0.0100	23.33	0.23
	2523156719079	Distantier pt.poz. arm in beton armat tip cupa	buc	0.1500	1.75	0.26
	2922140006702	Macara de fereastr	h-ut	0.0006	75.00	0.05
3	CG22A2	Pardoseli din beton M300, cu strat consolidat (H=120mm, k=1.2 mater.)	m2			421.96
						135.99
	7123010010200	Betonist	h-om	1.1500	94.60	125.11
	9310060019920	Muncitor deservire CM	h-om	0.1000	94.60	10.88
	2663102100350	Beton M350	m3	0.1025	1 684.17	207.15
	265112210012	Sikafloor ProSeal-12	kg	0.1500	79.17	14.25
	1135444004	Cordon de etansare	m	0.66667	7.92	6.34
	11354118	Topping Sintop	kg	3.0000	8.75	31.50
	2952160007200	Utilaj de ridicat pentru lucrari de finisaj	h-ut	0.1000	267.33	26.73

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar "FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924

Antreprenor "Alpro-Construct" SRL, IDNO 1009600009470

Obiect *Ремонт бетонного пола склада форм и рамы*

Contract Nr. 14891

DEVIZ LOCAL № 14891-3

Устройство бетонного пола склада форм

Valoarea de deviz 119 782.26 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7
Manopera:						
1.	7123010010200	Betonist	h-om	198.38	94.60	18 766.28
2.	7123020011140	Fierar beton	h-om	17.45	94.60	1 651.17
3.	7134030012200	Izolator hidrofug	h-om	5.18	94.60	489.56
4.	9310060019920	Muncitor deservire CM	h-om	20.07	94.60	1 898.17
Total manopera						22 805.17
Materiale:						
1.	11354118	Toping Sintop	kg	540.00	8.75	4 725.00
2.	1135444004	Cordon de etansare	m	120.00	7.92	950.40
3.	2523156719079	Distantier pt.poz. arm in beton armat tip cupa	buc	73.44	1.75	128.52
4.	265112210012	Sikafloor ProSeal-12	kg	27.00	79.17	2 137.59
5.	2663102100350	Beton M350	m3	18.45	1 684.17	31 072.94
6.	2682132603	Pellicula PE	m2	169.68	4.31	731.32
7.	2710602000030	Otel beton profil neted OB 37 STAS 438 D = 6 mm	kg	2.45	12.98	31.78
8.	2734113803116	Sirma neagra moale d = 1 mm	kg	4.90	23.33	114.22
9.	28731220511	Plase arm. Bp5*100*100	kg	494.50	20.25	10 013.54
Total materiale de constructii						49 905.31
Utilaje de constructii:						
1.	2922140006702	Macara de fereastră	h-ut	2.54	75.00	190.79
2.	2952160007200	Utilaj de ridicat pentru lucrari de finisaj	h-ut	15.00	267.33	4 009.95
Total utilaje de constructii						4 200.73
Total			Lei	76 911.22		
Asigurarea sociala			24.00 %	5 473.24		
Transportarea materialelor			5.00 %	2 495.27		
Total				84 879.72		
Cheltuieli de regie			12.00 %	10 185.57		
Total				95 065.29		
Beneficiu de deviz			5.00 %	4 753.26		
Total				99 818.55		
TVA			20.00 %	19 963.71		
Total deviz:			Lei	119 782.26		

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)