

**ANTREPRENOR**

"Alpro-Construct" SRL, IDNO  
1009600009470

**BENEFICIAR**

IS "MOLDELECTRICA", IDNO  
1002600004580

**Coordonat:**

\_\_\_\_\_  
\_\_\_\_\_

**Aprobat:**

\_\_\_\_\_  
\_\_\_\_\_

**Lucrari de protectie anticoroziva a  
pilonilor metalici (20 buc.)**

\_\_\_\_\_  
(denumirea obiectivului)

Contract Nr. 14761

**DEVIZ LOCAL № 4**

**LEA-110 kV Floresti # Soldanesti nr. 268 (tip pilon Y110-1+5); nr. 275, 276 (tip pilon Y110-2+9) Total 3 piloni.**

Valoarea de deviz 269 622.49 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2	966.80	5.10	4 932.42
	7141020013400	Vopsitor industrial	h-om	106.348	46.38	4 932.42
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 30 buc.	m2	102.00	6.51	664.27
	7134030012200	Izolator hidrofug	h-om	6.120	46.38	283.85
	2682132602	Пленка п/э	m2	114.240	3.33	380.42
	2922140006702	Macara de fereastră	h-ut	1.530	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2	966.80	171.50	165 806.94
	7141020013300	Zugrav vopsitor	h-om	2 687.704	46.38	124 655.71
	2430116104160	Email (с алюмин. пастой)	kg	232.032	103.93	24 115.09
	2430226100981 f	Grund anticorosiv 2 in 1	kg	154.688	62.50	9 668.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	40.606	53.67	2 179.32
	2320166200676	White spirit	kg	96.680	53.67	5 188.82
Total			Lei			171 403.63
Asigurarea sociala			24.00 %			31 169.28
Transportarea materialelor			6.00 %			2 491.90
Cheltuieli directe						205 064.81
Cheltuieli de regie			7.00 %			14 354.53
Total						219 419.34



Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761**

Anexa Nr. 1

**Catalog de preturi unitare****LEA-110 kV Floresti # Soldanesti nr. 268 (tip pilon Y110-1+5); nr. 275, 276 (tip pilon Y110-2+9) Total 3 piloni.**

(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7</b>
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2			5.10
	7141020013400	Vopsitor industrial	h-om	0.110	46.38	5.10
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 30 buc.	m2			6.51
	7134030012200	Izolator hidrofug	h-om	0.060	46.38	2.78
	2682132602	Пленка п/э	m2	1.120	3.33	3.73
	2922140006702	Macara de fereastră	h-ut	0.015	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2			171.50
	7141020013300	Zugrav vopsitor	h-om	2.780	46.38	128.94
	2430116104160	Email (с алюмин. пастой)	kg	0.240	103.93	24.94
	2430226100981F	Grund anticorosiv 2 in 1	kg	0.160	62.50	10.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	0.042	53.67	2.25
	2320166200676	White spirit	kg	0.100	53.67	5.37

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761****DEVIZ LOCAL № 4****LEA-110 kV Floresti # Soldanesti nr. 268 (tip pilon Y110-1+5); nr. 275, 276 (tip pilon Y110-2+9) Total 3 piloni.****Valoarea de deviz 269 622.49 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7

**Manopera:**

1.	7134030012200	Izolator hidrofug	h-om	6.120	46.38	283.85
2.	7141020013300	Zugrav vopsitor	h-om	2 687.704	46.38	124 655.71
3.	7141020013400	Vopsitor industrial	h-om	106.348	46.38	4 932.42
<b>Total manopera</b>						<b>129 871.98</b>

**Materiale:**

1.	2320166200676	White spirit	kg	96.680	53.67	5 188.82
2.	2430116104160	Email (с алюмин. пастой)	kg	232.032	103.93	24 115.09
3.	2430226100981f	Grund anticorosiv 2 in 1	kg	154.688	62.50	9 668.00
4.	2430226109260	Diluant 509 D.005-1 S 3123	kg	40.606	53.67	2 179.32
5.	2682132602	Пленка п/э	m2	114.240	3.33	380.42
<b>Total materiale de constructii</b>						<b>41 531.65</b>

**Utilaje de constructii:**

1.	2922140006702	Macara de fereastră	h-ut	1.530	0.00	0.00
<b>Total utilaje de constructii</b>						<b>0.00</b>

Total	Lei	171 403.63
Asigurarea sociala	24.00 %	31 169.28
Transportarea materialelor	6.00 %	2 491.90
Cheltuieli directe		205 064.81
Cheltuieli de regie	7.00 %	14 354.53
Total		219 419.34
Beneficiu de deviz	2.40 %	5 266.07
Total		224 685.41
TVA	20.00 %	44 937.08

**Total deviz: Lei 269 622.49**  
**Incluziv salariu 129 871.98**

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)