

DECLARATION

We **İDEAL MAKİNA ENDÜSTRİ ÜRÜNLERİ SAN. VE TİC. A.Ş.**, who are official manufacturer of Oxygen Generator and Filling System & accessories, IDEAL MAKİNA Company having factories at Emek, Ordu Cd. No:16, 34785 Dudullu Osb/Sancaktepe/İstanbul do hereby confirm that the offered **PLUG& PLAY, CONTAINERIZED, IDEAL 20/4-150 OIL-FREE, AIR COOLED HIGH PRESSURE OXYGEN COMPRESSOR SYSTEM** with all of its components, work altogether efficiently.

In addition to this, **İDEAL MAKİNA ENDÜSTRİ ÜRÜNLERİ SAN. VE TİC. A.Ş.**, confirms that the offered system works fully compatible with the **İDEAL IM-GO 300 OXYGEN GENERATOR SYSTEM**.



Alpaslan Tekin
General Manager
Dated on 28.02.2024

idealMakina®
İDEAL MAKİNA END. ÜRÜN. SAN. VE TİC. A.Ş.
Esenkent Mh. Nato Yolu Cd. No:277 34776 Ümraniye-İST.
Sarıgazi V.D 470 097 1328 Tic. Sic. No: 530388
www.idealmakina.com

DECLARATION

İDEAL MAKİNA ENDÜSTRİ ÜRÜNLERİ SAN. VE TİC. A.Ş. confirms that the offered **PLUG & PLAY, CONTAINERIZED, IDEAL 20/4-150 OIL-FREE, AIR COOLED HIGH PRESSURE OXYGEN COMPRESSOR SYSTEM** consists of the equipment in the table below.

High Pressure Oxygen Booster Compressor;

Model	GOW-20/4-150 OIL-FREE, AIR COOLED HIGH PRESSURE OXYGEN COMPRESSOR
Capacity	20 Nm ³ /h
Inlet Pressure	2-4 bar
Outlet Pressure	150 bar
Motor Power	11 kW
Motor Speed	200-400 rpm
Electric	400V/50-60Hz/3 faze
Cooling	Air Cooling

Oxygen Cylinders Filling Ramp;

Model	OXYGEN CYLINDERS FILLING RAMP - V
Quantity	3 pcs of FILLING RAMP FOR 5 CYLINDERS (10 cylinders will be placed on 2 filling ramps) (1 filling ramp will be left for free ports)
** All Safety Valves, Manometers, Flexible Pipes, Chains, Metal Structure and Connections are included.	

Oxygen Cylinders;


Model	OXYGEN CYLINDERS, 40 L, 150 BAR
Volume	40 L
Filling Pressure	150 bar

Container;

Model	HEAVY DUTY, SPECIAL INSULATED, HIGH CUBE 20 ft ISO CONTAINER
<ul style="list-style-type: none">The container is transportable as needed, and allow forklift handlingThermal insulation, two main doors, one emergency exit door, air conditioner, lightning, fire detection, emergency disconnection system, all cabling and piping, outdoor lightning, ventilation fan are included.All equipment will be connected each other and tested at İdeal Makina Factory in İstanbul.The mechanical and electrical connections will be tested before delivery.FAT (Factory Acceptance Test) will be done and reported by İdeal Makina Technical Service Team.No installation on-site, No leakage possibility, Easy commissioning on-site, PLUG & PLAY.	

Alpaslan Tekin - General Manager

Dated on 28.02.2024

**idealMakina®**
İDEAL MAKİNA END. ÜRÜN. SAN. VE TİC. A.Ş.
Esenkent Mh. Nato Yolu Cd. No:277/18 34776 Ümraniye-İST.
Sarıgazi V.D 470 097 1938 Tic. Sic. No: 530388
www.idealmakina.com

İdeal Makina Endüstri Ürünleri San. ve Tic. A.Ş.

Esenkent Mh. Nato Yolu Cd. No:277 34776 Ümraniye - İstanbul - Türkiye/Turkey **T** +90 216 540 88 55 **F** +90 216 540 88 18 **E** info@idealmakina.com

www.idealmakina.com