

1	2	3	4	5	6	7
<b>-Catan</b>						
<b>Incluziv salariu</b>						<b>5 268,80</b>
		<b>6. 1.6.Sectorul 6 Savca Oleg- L=500m,l=4.0m</b>				
13	DH02B	Scarificarea usoara a impietruirii pina la 5 cm adincime cu autogreder, inclusin reprofilarea	100m2	20,00	33,00 0,00	660,00 0,00
14	DI89B	Reparatia drumurilor impetruite:cu adaos de material	100m2	20,00	2 495,41 290,16	49 908,20 5 803,20
<b>Total 1.6.Sectorul 6 Savca Oleg- L=500m,l=4.0m</b>						<b>50 568,20</b>
<b>Incluziv salariu</b>						<b>5 803,20</b>
		<b>7. 1.7.Sectorul 7 Tighineanu Boris-Piata</b>				
15	DH02B	Scarificarea usoara a impietruirii pina la 5 cm adincime cu autogreder, inclusin reprofilarea	100m2	16,10	33,00 0,00	531,30 0,00
16	DI89B	Reparatia drumurilor impetruite:cu adaos de material	100m2	16,10	2 495,41 290,16	40 176,10 4 671,58
<b>Total 1.7.Sectorul 7 Tighineanu Boris-Piata</b>						<b>40 707,40</b>
<b>Incluziv salariu</b>						<b>4 671,58</b>
		<b>8. 1.8.Sectorul 8 Cebotaru iulian- Statia de pompare L=350,0m x4.0m=1400m2,L=125.0m x 3.5m =437.0m2 S tot=1837 m2</b>				
17	DH02B	Scarificarea usoara a impietruirii pina la 5 cm adincime cu autogreder, inclusin reprofilarea	100m2	18,37	33,00 0,00	606,20 0,00
18	DI89B	Reparatia drumurilor impetruite:cu adaos de material	100m2	18,37	2 495,41 290,16	45 840,69 5 330,24
<b>Total 1.8.Sectorul 8 Cebotaru iulian-Statia de pompare L=350,0m x4.0m=1400m2,L=125.0m x 3.5m =437.0m2 S tot=1837 m2</b>						<b>46 446,89</b>

