

Formularul nr. 3

Devizul: Reparatia str.I.Secieru din orasul Cimisia in varianta alba

Devizul local de resurse Nr. 18.1.1

Valoarea de deviz 354 949,627 (Lei)

Nr.	Simbol norme si Cod resurse	Denumire lucrari si cheltuieli	U.M.	Cantitate conform datelor din	Valoarea de deviz (Lei)	
					Pe unitate de masura	Total
1	2	3	4	5	6	7
Manopera						
1	7129020012800	Pavator	h-om	230.4	40	9216
Total manopera					9216	
Materiale						
1	1411122201646	Piatra sparta pentru pt.drumuri r.magmatice 15-25 mm	m3	77.952	300	23385.6
2	1411122201672	Piatra sparta pentru pt.drumuri r.magmatice 40-63 mm	m3	468.096	300	140428.8
3	1421102200525	Savura(moluza)	m3	98.688	220	21711.36
4	4100116202806	Apa industriala in cisterne pt. lucrari drumuri-terasam.	m3	57.6	8	460.8
Total materiale					185986.56	
Utilaj						
1	20003491	Autobasculantă 10 t	h-ut	23.5545	50	1177.725
2	2952220003546	Autogreder pina la 175 cp	h-ut	62.304	450	28036.8
3	2952240004010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	99.072	350	34675.2
4	2952270007403	Incarcator frontal pe senile 0,5 - 0,99 mc	h-ut	18.2784	50	913.92
5	3410540005603	Autocisterna 5-8 t cu dispozitive de stropire	h-ut	5.76	220	1267.2
Total utilaj					66070.845	
Total					261273.405	
Asigurari sociale si medicale			22,5000%		2073.6	
Total					263347.005	
Cheltuieli de regie			8,0000%		21067.76	
Total					284414.765	
Beneficiu de deviz			4,0000%		11376.591	
TOTAL Deviz faraTVA					295791.356	
Total					295791.356	
TVA			20%		59158.271	
TOTAL Deviz					354949.627	

Intocmit: SRL Autoring

(functia, semnatura, numele, prenumele)

Verificat: Primaria or.Cimisia

(functia, semnatura, numele, prenumele)

