

**ANTREPRENOR**

"Alpro-Construct" SRL, IDNO  
1009600009470

**BENEFICIAR**

IS "MOLDELECTRICA", IDNO  
1002600004580

Coordonat:

\_\_\_\_\_

\_\_\_\_\_

Aprobat:

\_\_\_\_\_

\_\_\_\_\_

**Lucrari de protectie anticoroziva a  
pilonilor metalici (20 buc.)**

(denumirea obiectivului)

Contract Nr. 14761

## DEVIZ LOCAL № 1

LEA-110 kV Edinet # Cuconesti nr. 1 (tip pilon Y1M plus); nr. 9, 10 (tip pilon Y1M); Total 3 piloni.

Valoarea de deviz 151 634.63 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2	543.59	5.10	2 773.29
	7141020013400	Vopsitor industrial	h-om	59.795	46.38	2 773.29
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 18 buc.	m2	61.20	6.51	398.56
	7134030012200	Izolator hidrofug	h-om	3.672	46.38	170.31
	2682132602	Пленка п/э	m2	68.544	3.33	228.25
	2922140006702	Macara de fereastră	h-ut	0.918	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2	543.59	171.50	93 226.12
	7141020013300	Zugrav vopsitor	h-om	1 511.180	46.38	70 088.53
	2430116104160	Email (с алюмин. пастой)	kg	130.462	103.93	13 558.92
	2430226100981 f	Grund anticorosiv 2 in 1	kg	86.974	62.50	5 435.88
	2430226109260	Diluant 509 D.005-1 S 3123	kg	22.831	53.67	1 225.34
	2320166200676	White spirit	kg	54.359	53.67	2 917.45
Total			Lei			96 397.97
Asigurarea sociala			24.00 %			17 527.71
Transportarea materialelor			6.00 %			1 401.95
Cheltuieli directe						115 327.63
Cheltuieli de regie			7.00 %			8 072.94
Total						123 400.57



Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761**

Anexa Nr. 1

**Catalog de preturi unitare**

**LEA-110 kV Edinet # Cuconesti nr. 1 (tip pilon Y1M plus); nr. 9, 10 (tip pilon Y1M); Total 3 piloni.**  
(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2			5.10
	7141020013400	Vopsitor industrial	h-om	0.110	46.38	5.10
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 18 buc.	m2			6.51
	7134030012200	Izolator hidrofug	h-om	0.060	46.38	2.78
	2682132602	Пленка п/э	m2	1.120	3.33	3.73
	2922140006702	Macara de fereastr	h-ut	0.015	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2			171.50
	7141020013300	Zugrav vopsitor	h-om	2.780	46.38	128.94
	2430116104160	Email (с алюмин. пастой)	kg	0.240	103.93	24.94
	2430226100981F	Grund anticorosiv 2 in 1	kg	0.160	62.50	10.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	0.042	53.67	2.25
	2320166200676	White spirit	kg	0.100	53.67	5.37

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761****DEVIZ LOCAL № 1****LEA-110 kV Edinet # Cuconesti nr. 1 (tip pilon Y1M plus); nr. 9, 10 (tip pilon Y1M); Total 3 piloni.****Valoarea de deviz 151 634.63 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7
<b>Manopera:</b>						
1.	7134030012200	Izolator hidrofug	h-om	3.672	46.38	170.31
2.	7141020013300	Zugrav vopsitor	h-om	1 511.180	46.38	70 088.53
3.	7141020013400	Vopsitor industrial	h-om	59.795	46.38	2 773.29
<b>Total manopera</b>						<b>73 032.13</b>
<b>Materiale:</b>						
1.	2320166200676	White spirit	kg	54.359	53.67	2 917.45
2.	2430116104160	Email (с алюмин. пастой)	kg	130.462	103.93	13 558.92
3.	2430226100981f	Grund anticorosiv 2 in 1	kg	86.974	62.50	5 435.88
4.	2430226109260	Diluant 509 D.005-1 S 3123	kg	22.831	53.67	1 225.34
5.	2682132602	Пленка п/э	m2	68.544	3.33	228.25
<b>Total materiale de constructii</b>						<b>23 365.84</b>
<b>Utilaje de constructii:</b>						
1.	2922140006702	Macara de fereastră	h-ut	0.918	0.00	0.00
<b>Total utilaje de constructii</b>						<b>0.00</b>
Total			Lei	96 397.97		
Asigurarea sociala			24.00 %	17 527.71		
Transportarea materialelor			6.00 %	1 401.95		
Cheltuieli directe				115 327.63		
Cheltuieli de regie			7.00 %	8 072.94		
Total				123 400.57		
Beneficiu de deviz			2.40 %	2 961.62		
Total				126 362.19		
TVA			20.00 %	25 272.44		
<b>Total deviz:</b>			<b>Lei</b>	<b>151 634.63</b>		
<b>Incluziv salariu</b>				<b>73 032.13</b>		

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)