



RDW

Vehicle Technology Division



THE NETHERLANDS
(N E D E R L A N D)



COMMUNICATION

Concerning ⁽¹⁾ :

- ~~- approval granted~~
- approval extended
- ~~- approval refused~~
- ~~- approval withdrawn~~
- ~~- production definitely discontinued~~

of a type of tyre for motor vehicles pursuant to Regulation number 30.

Approval number: E4-30R-0287153

Extension number: 01

- | | |
|--|--|
| 1. Manufacturer's name and address | : Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover
Germany |
| 2. Tyre type designation ⁽²⁾ | |
| 2.1 Brand-name(s)/trademark(s) | : GISLAVED
<u>CONTINENTAL</u> |
| 2.2 Trade description(s)/Commercial name(s) | : GISLAVED, SOFT*FROST 200
<u>CONTINENTAL, VikingContact 7</u> |
| 3. If applicable, name and address of the manufacturer's representative | : not applicable |
| 4. Summarized description | |
| 4.1 Tyre size designation | : 215/65 R 16 |
| 4.2 Category of use | : normal /snow / special use / temporary use ⁽¹⁾ |
| 4.3 Structure | : diagonal / bias belted / radial/ run-flat tyre ⁽¹⁾ |
| 4.4 Speed category symbol | : T |
| 4.5 Load-capacity index | : 102 |
| 5. Technical Service and, where applicable, test laboratory approved for purposes of approval or of verification of conformity | : Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover
Germany |
| 6. Date of report issued by that service | : 14.03.2016, 15.03.2016 |
| 7. Number of report issued by that service | : 4727005, 4727006 |
| 8. Reason(s) of extension (if applicable) | : Tyre Type Designation added |
| 9. Any remarks | : Reinforced/Extra Load |



Approval number: E4-30R-0287153

Extension number: 01

10. Place : Zoetermeer
11. Date : 11-DEC-2017
12. Signature :



13. The list of documents in the approval file which are deposited at the administrative service having delivered the approval and which can be obtained upon request.

- Application form relating to ECE approval for a pneumatic tyre pursuant to Regulation number 30.

-
- The drawing of the tyre's sidewalls, tread and dimensioned cross-section.
- The test report as mentioned in item 7.

(1) Strike out what does not apply.


(2) A list of Brand name(s)/trademark(s) or Trade description(s)/ Commercial name(s) may be annexed to this communication

Serial Side (SS)

Off Serial Side (OSS)



The drawing may contain more position numbers than required by UNECE type approval.




Position	Description	min height	Tire Side	TSL Content	Position	Description	min height	Tire Side	TSL Content
1/194	Brand Name (Trade mark)		both	CONTINENTAL	116	"Inside"/"Outside" marking		SS	OUTSIDE
2 or 3	Trade description (Commercial name)		both	VikingContact 7	117	"Inside"/"Outside" marking		OSS	INSIDE
4	Tire size designation	>6 (or 9	both	215/65 R 16	134	Date of manufacturing	>4 mm	SS	[WWYY]
6	Structure	>4 mm	both	RADIAL	179	Alpine Symbol		both	#ALPINE SYMBOL#
7 or 8	Service description (LI / SSV)	>6 mm	both	102 T	184	Runflat Symbol		both	-
9 or 10	Additional service description	>6 mm	both		191	"FRT" marking	>4 mm	both	-
13 or 14	"M+S" (or "M.S" or "M&S")		both	M+S	135	UN approval mark	>12 mm	both	E4
15	Tube type / Tubeless		both	TUBELESS	137	UN R30/R54/R75 approval no.		both	0287153
17	Extra Load or Reinforced	>6 mm	both	EXTRA LOAD	If Pos 78 is used				
19	PSI index	>2 mm	both						
27	Regroovability		both						
32	"TEMPORARY USE ONLY"	>12,7 mm	both		If Pos 79 is used				
34	"INFLATE TO 420 kPa (60 PSI)"	>12,7 mm	both						
78	Mark for special use tires	>4 mm	both						
79	"TRACTION"	>4mm	both		Depth of lateral grooves/sipes >=50% of main groove depth?				

Design Dimensions (calculated / Annex-5)			
Overall diameter	A (mm)		886
Section Width	B (mm)		221
Measuring rim	C (Rim Code)		6.5Jx16
Approval No.	E4-30R-0287153		
Extension:	01		
Name:	D. Schoenfelder		
Drawing No.:	1		
Date:	10/27/17 1:25 PM		
Pattern	9999.99		


Continental



Company proprietary
Unauthorized duplication prohibited




APPROVAL MARK




1st Sidewall

APPROVAL MARK



2nd Sidewall

3119.02



6	T	3	215/65 R 16 Reinforced/Extra Load	5	102	TT TL	686	221	6.5Jx16	
SS		Category of use marking (if applicable) M+S		LI		Tyre Type	A mm	B mm	C Rim Code	Remarks
Brand name		1 GISLAVED				Drawing No. / Remarks :		Checked / Date :		
Tyre type Designation		2 SOFT*FROST 200				P - 0287153		20.07.2015 J. Recknagel		

