

1	2	3	4	5	6	7
						57,08
	931006001 9900	Muncitor necalificat	h-om	0,9900	57,66	57,08
	141112220 1752	Piatra sparta	m3	1,1500	200,00	230,00
	410012620 2818	Apa	m3	0,1000	5,00	0,50
	291234000 2506	Compresor mobil motor ardere interna, presiunea pina la 686 kPa (7atm), 2,2 m3/min	h-ut	0,2100	350,00	73,50
	259227000 4021	Compactor pe pneuri sau mecanic 150 - 200 kg	h-ut	0,4200	350,00	147,00
32	PI06A	Montarea elementelor prefabricate din beton armat (tevi de 5m, d=0.5m)sau precomprimat, cu automacara sau macara pe pneuri cu capacitatea de 9.9 tf	buc			340,48 72,08
	712303001 2500	Montator P.B.	h-om	1,2500	57,66	72,08
	201010290 0566	Lemn rotund de stejar virf cu l mai mare 160 dn=10 cm	m3	0,0040	600,00	2,40
	201010290 4545	Dulapi de stejar tiv el C gr=50 mm L=2 m	m3	0,0150	3 000,00	45,00
	287527631 1528	Scoabe din otel	kg	0,3000	25,00	7,50
	341052000 6728	Macara pe pneuri pina la 9,9 TF cu brat cu zabrele	h-ut	0,6100	350,00	213,50
33	PI08A	Elemente prefabricate din beton armat, confectionate in uzina (Tava din beton armat prefabricat d=0.5m, l=5.0m)	buc			2 014,00 0,00
	266612280 0511	Elemente pentru poduri din beton armat	buc	1,0070	2 000,00	2 014,00
34	PF05A	Hidroizolatii la lucrari de arta din bitum filerizat, aplicat la rece, cu peria, in doua staturi succesive (primul diluat cu 50 % apa, iar al doilea cu 20% apa)	m2			12,88 2,88
	713403001 2200	Izolator hidrofug	h-om	0,0500	57,66	2,88
	241331734 6000	Suspensie de bitum filerizat-subif	kg	1,0000	10,00	10,00
35	PB01A	Turnarea betonului simplu in completari, nivelari, umpluturi si panta, executat in straturi cu grosimea de 5-20 cm	m3			1 390,00 179,90
	713203001 2600	Mozaicar	h-om	1,9000	57,66	109,55
	931006001	Muncitor necalificat	h-om	1,2200	57,66	70,35



Handwritten signature: M. B. B.