



THE NETHERLANDS
(N E D E R L A N D)



COMMUNICATION

Concerning ⁽¹⁾ :

- ~~- approval granted~~
- approval extended
- ~~- approval refused~~
- ~~- approval withdrawn~~
- ~~- production definitely discontinued~~

of a type of tyre for motor vehicles pursuant to Regulation number 30.

Approval number: E4-30R-0271511

Extension number: 01

- | | | |
|--|---|--|
| 1. Manufacturer's name and address | : | Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover
Germany |
| 2. Tyre type designation ⁽²⁾ | | |
| 2.1 Brand-name(s)/trademark(s) | : | CONTINENTAL |
| 2.2 Trade description(s)/Commercial name(s) | : | CONTINENTAL, CONTIVIKINGCONTACT 6
<u>CONTINENTAL, VikingContact 7</u> |
| 3. If applicable, name and address of the manufacturer's representative | : | not applicable |
| 4. Summarized description | | |
| 4.1 Tyre size designation | : | 235/65 R 17 |
| 4.2 Category of use | : | normal /snow / special use / temporary use ⁽¹⁾ |
| 4.3 Structure | : | diagonal / bias belted / radial/ run-flat tyre ⁽¹⁾ |
| 4.4 Speed category symbol | : | T |
| 4.5 Load-capacity index | : | 108 |
| 5. Technical Service and, where applicable, test laboratory approved for purposes of approval or of verification of conformity | : | Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover
Germany |
| 6. Date of report issued by that service | : | 28.09.2017 |
| 7. Number of report issued by that service | : | 5228460, 5228461 |
| 8. Reason(s) of extension (if applicable) | : | Tyre Type Designation added |
| 9. Any remarks | : | Reinforced/Extra Load |
| 10. Place | : | Zoetermeer |



Approval number: E4-30R-0271511

Extension number: 01

11. Date : 01-DEC-2017

12. Signature :



T. Ploshchansky

13. The list of documents in the approval file which are deposited at the administrative service having delivered the approval and which can be obtained upon request.

- Application form relating to ECE approval for a pneumatic tyre pursuant to Regulation number 30.

- The drawing of the tyre's sidewalls, tread and dimensioned cross-section.


- The test report as mentioned in item 7.

⁽¹⁾ Strike out what does not apply.

⁽²⁾ A list of Brand name(s)/trademark(s) or Trade description(s)/ Commercial name(s) may be annexed to this communication



The drawing may contain more position numbers than required by UNECE type approval.





Position	Description	min height	Tire Side	TSL Content
1/194	Brand Name (Trade mark)		both	CONTINENTAL
2 or 3	Trade description (Commercial name)		both	VikingContact 7
4	Tire size designation	>6 (or 9)	both	235/65 R 17
6	Structure	>4 mm	both	RADIAL
7 or 8	Service description (LI / SSY)	>6 mm	both	108 T
9 or 10	Additional service description	>6 mm	both	
13 or 14	"M+S" (or "M.S" or "M&S")		both	M+S
15	Tube type / Tubeless		both	TUBELESS
17	Extra Load or Reinforced	>6 mm	both	EXTRA LOAD
19	PSI index	>2 mm	both	-
27	Regroovability		both	-
32	"TEMPORARY USE ONLY"	>12,7 mm	both	-
34	"INFLATE TO 420 kPa (60 PSI)"	>12,7 mm	both	-
78	Mark for special use tires	>4 mm	both	-
79	"TRACTION"	>4mm	both	-


Position	Description	min height	Tire Side	TSL Content
116	"Inside"/"Outside" marking		SS	OUTSIDE
117	"Inside"/"Outside" marking		OSS	INSIDE
134	Date of manufacturing	>4 mm	SS	[WWYY]
179	Alpine Symbol		both	#ALPINE SYMBOL#
184	Runflat Symbol		both	-
191	"FRT" marking	>4 mm	both	-
135	UN approval mark	>12 mm	both	E4
137	UN R30/R54/R75 approval no.		both	0271511
If Pos 78 is used	Tread depth			-
	Surface void/ fill ratio			-
If Pos 79 is used	Number of circumferential ribs			-
	Number of block-like elements			-
	Depth of lateral grooves/sipes >=50%of main groove depth?			-

Design Dimensions (calculated /Annex-5)		
Overall diameter	A (mm)	738
Section Width	B (mm)	240
Measuring rim	C (Rim Code)	7.0Jx17
Approval No.	E4-30R-0271511	
Extension:	01	
Name:	D. Schoenfelder	
Drawing No.:	1	
Date:	11/21/17 4:24 PM	
Pattern	9999.99	





1st Sidewall



2nd Sidewall

3726-02



6	③	5					
T	235/65 R 17 Reinforced/ Extra Load	108	TT TL	738	240	7Jx17	
SS	4 Category of use M & S	LI	Tyre type	A mm	B mm	C Rim-Code	Remarks
Brand name	1	Continental		Drawing No. /Remarks:		Checked / Date :	
Tyre type designation	2	Conti VikingContact 6		P - 0271511		23.09.2013 Fischer	