

1	2	3	4	5	6	7
		mm				
3	CK26A п. К=3=1,000; М=1,000; Ш=1,000	Glafuri montate la ferestre din mase plastice (Подоконники для окон из пластмассы)	m	14,550	94,925 18,925	1 381,161 275,361
	7422010060100	Timplari	h-om	4,074		
	9310060019920	Muncitor deservire CM	h-om	1,164		
	2521106718392	Glafuri din mase plastice pentru ferestre	m	14,550		
	2874115829126	Suruburi cu cap inecat crestas 6 x 30 mm	buc	58,200		
4	CK26B п. К=3=1,000; М=1,000; Ш=1,000	Glafuri montate la ferestre din aluminiu (Подоконники для окон из алюминия)	m	14,550	82,028 21,028	1 193,507 305,957
	7422010060100	Timplari	h-om	4,656		
	9310060019920	Muncitor deservire CM	h-om	1,164		
	2743123549026	Glafuri din aluminiu pentru ferestre	m	14,550		
	2874115829126	Suruburi cu cap inecat crestas 6 x 30 mm	buc	58,200		
5	SC13A п. К=3=1,000; М=1,000; Ш=1,000	Oglinda sanitara din semicristal cu marginile slefuite, avid dimensiunile de 1600 x 1600 mm, montata pe perete din zidarie de caramida sau b.c.a. (Установка зеркала полукристаллического, с шлифованными краями, размером 1600x1600 мм, на кирпичные или блочные стены) Material marunt (dibluri, ipsos etc)=1,020	buc	6,000	683,282 39,428	4 099,690 236,565
	7136020011620	Instalator apa, canal	h-om	4,500		
	2612132506710	Oglinda din semicristal(geam tras, slefuit)	buc	6,181		
<b>Total Capitolul 1.Ferestre</b>						<b>71 279,502</b>
<b>Incluziv salariu</b>						<b>2 667,927</b>
<b>2. Capitolul 2.Usi</b>						
6	CK21D п. К=3=1,000; М=1,000; Ш=1,000	Usi confectionate din profiluri din aluminiu, inclusiv armaturile si accesoriile necesare usilor montate in zidarie de orice natura. la constructii cu inaltimea pina la 35 m inclusiv,	m2	4,990	1 356,720 55,720	6 770,03 248,043

