



1	2	3	4	5	6	7
	4-14	jgheaburi metalice, pe pereti din lemn sau caramida 120x 70mm				
		<b>Capitolul 3. LUCRARI DE MONTARE SISTEM ELECTRIC</b>				
11	08-03-57 3-4	Dulap (pupitru) de comanda suspendat, inaltime, latime si adincime, mm, pina la SPB PM12IP21	buc	1,00		
12		BOXC -12MODELE SPb-Pm-12IP2	buc	1,00		
13		SINAYNS20-3-063	buc	1,00		
14		SINAYNN 10-14-100	buc	1,00		
15	08-03-59 4-3	Corp de iluminare montat aparte pe pivoate cu cantitatea lampilor in corpul de iluminare: pina 4 LED Amstrung	100 buc	0,42		
16	pret firma	Corp Iluminat 4x18	buc	42,00		
17	08-03-59 1-9	Priza de fisa tip neingropat, la instalatie inchisa IP43	100 buc	0,28		
18	pret firma	Priza simpla euro	buc	28,00		
19	08-03-59 1-2	Intreruptor cu o clapa, tip ingropat, la instalatie inchisa IH10A IP20	100 buc	15,00		
20	pret firma	Intrerupator cu oclapa	buc	15,00		
21	08-03-52 6-1	Automat mono-, r, montat pe constructie pe perete sau coloana, la curent, A, pina: 25	buc	20,00		
22	pret firma	INTRERUPATOR AUTOMAT BA47-29/1 10-B	buc	10,00		
23	pret firma	INTRERUPATOR AUTOMAT BA47-29/1 16-B	buc	10,00		
24	08-03-52 6-1	Automat bi-., montat pe constructie pe perete sau coloana, la curent, A, pina: 25	buc	8,00		
25	pret firma	INTRERUPATOR AUTOM DIFERENTIAL CiDPNa 1P	buc	8,00		
26	08-03-52 6-2	Automat mono-, bi-, tripolar, montat pe constructii pe perete sau coloana, curent	buc	4,00		

1	2	3	4	5	6	7
		pina la 100				
27		Intrerupator -3-poli BA47-29/3/32	buc	1,00		
28		CUTIE PENTRU INTRERUPATOR,si Prize	buc	43,00		
29		RASPRED COROBCA	buc	10,00		
30	08-02-47 2-3	Conductor de legare la pamint comuflat in strat de egalizare a pardoselii, din otel fisie, sectiune 100 mm2	100 m	0,30		
31	08-02-47 1-4	Priza de pamint, verticala, din otel rotund, diametru 20 mm	10 buc	0,30		
32	08-02-14 8-1	Cablu pina la 35 kV in tevi, blocuri si cutii pozate, masa 1 m pina la: 1 kg VVG NG 3X1.5	100 m	2,10		
33	pret firma	Cablu VVG ng 3x1.5	m	210,00		
34	08-02-14 8-1	Cablu pina la 35 kV in tevi, blocuri si cutii pozate, masa 1 m pina la: 1 kg VVG NG 3X2.5	100 m	2,40		
35	pret firma	Cablu VVG ng 3x2.5	m	240,00		
36	RpEJ05 A	Incercari, verificari electrice si reglari la cabluri de energie electrica pina la 1 kW	buc	70,00		