



## Play Complex No 6

**Installation requirements:** To ensure safe and reliable operation, all supports are to be immersed in the ground (ground) to 0.70m to increase rigidity, then following the concrete process (concrete BC 300). The installation of the elements must exclude the possibility of disassembling them without the use of special purpose tools.



