

Formularul nr. 3

Obiectivul: rl.TELENESTI

Obiectul: Telenesti

Devizul: Lucrari de reparatie la acoperisul IP Gimnaziul s Scorteni raionul Telenesti

Devizul local de resurse Nr. 18.18.7

Valoarea de deviz 633668,49 (Lei)

Nr.	Simbol norme si Cod resurse	Denumire lucrari si cheltuieli	U.M.	Cantitate conform datelor din	Valoarea de deviz (Lei)	
					Pe unitate de masura	Total
1	2	3	4	5	6	7
Manopera						
1	7124010010700	Dulgher	h-om	11,66	49	571,34
2	7213050013100	Tinichigiu	h-om	2404,35	49	117813,15
3	9310060019920	Muncitor deservire CM	h-om	737,54	49	36139,46
Total manopera					154523,95	
Materiale						
1	2010102908749	Grinzi rasin.cu 4 fete plane gros=10/12-35/35 L=4-6m	m3	0,525	5200	2730
2	2222222222991	MATERIAL MARUNT	%	2	0	296,412
3	2222222222991	MATERIAL MARUNT	%	3	0	1105,508
4	2222222222992	Material marunt (material pt. lipit tabla)	%	5	0	11846
5	2413217300010	Cleme	buc	34	45	1530
6	2420157308151	Carbolineum	kg	0,125	55	6,875
7	2430226103064	Snur profilat din mastic	kg	160	45	7200
8	2666122800555	Element de inchidere	buc	29,7	45	1336,5
9	2710403642000	Tabla zincata ondulata sau cutata de 0.45mm cantitatea zinc minim 225 g/m2	m2	1840	100	184000
10	2710403643220	Tabla zincata plana	kg	960	29	27840
11	2710406311726	Burlan rotund prefabricat tip brass	m	71,4	79	5640,6
12	2710406311800	Jgheaburi semirotonde prefabricate tip brass	m	155,925	79	12318,075
13	2710703434927	Otel lat 30 x 6	kg	520	19	9880

14	2874115830000	Pilnii de curatire	buc	17	81	1377
15	2874115837745	Suruburi	buc	1485	4	5940
16	2874115837746	Suruburi mecanice	buc	8000	0,5	4000
17	2874125886734	Nituri POP	buc	8000	0,5	4000
18	2875274000050	Elemente de legatura	buc	14,85	45	668,25
19	2875274000050	Elemente de legatura	buc	17	81	1377
20	2875274000501	Cot de jgheab	buc	29,7	180	5346
21	2875274000502	Cot burlan	buc	34	81	2754
22	2875274000503	Cot de capat	buc	17	81	1377
23	2875274110001	Piesa de legatura	buc	17	45	765
24	2875274110101	Piesa de racordare jgheab -burlan	buc	29,7	81	2405,7
25	2875276310033	Pene metalice pentru impanare	kg	6	45	270
26	2875276311231	Cirlige din otel zn pentru jgheaburi	buc	207,9	42,5	8835,75
Total materiale						304845,67
Utilaj						
1	2922140006702	Macara de fereastr	h-ut	0,005	150	0,75
2	2922140006703	Macara fereastr de 0,0015 MN (0,15 tf)	h-ut	32	150	4800
3	2940420007679	Fierastrau mecanic	h-ut	0,06	50	3
4	2952160007200	Utilaj de ridicat pentru lucrari de finisaj	h-ut	39,19	5	195,95
Total utilaj						4999,7
Total						464369,32
Asigurari sociale si medicale				24,0000%	37085,748	
Total						501455,068
Cheltuieli de transport				2,0000%	6096,913	
Total						507551,982
Cheltuieli de regie				2,0000%	10151,04	
Total						517703,021
Beneficiu de deviz				2,0000%	10354,06	
TOTAL Deviz faraTVA						528057,08
tva 20%						105611,41
						633668,49

Intocmit:

(functia, semnatura, numele, prenumele)

Verificat:

(functia, semnatura, numele, prenumele)