



EN 55032
EN 55024
EN 50130-4
EN 61000-3-2
EN 61000-3-3

EMC TEST REPORT

For

NETWORK VIDEO DECODER

**MODEL NUMBER: NVD0905DH, DH-NVD0905DH, NVD0905DH-4K, DH-NVD0905DH-4K,
NVD0905DH-4I-4K, DH-NVD0905DH-4I-4K**

And

**DH-NVD0905DH-4K, OEM-NVD0905DH-4K, DHI-NVD0905DH-4K, NVD0905DH-4K,
DH-NVD0905DH-4K-A, DH-NVD0905DH-4K-B, DH-NVD0905DH-4K-C, DH-NVD0905DH-4K-D,
DH-NVD0905DH-4K-E, DH-NVD0905DH-4K-F, DH-NVD0905DH-4K-G, DH-NVD0905DH-4K-H,
DH-NVD0905DH-4K-I, DH-NVD0905DH-4K-J, DH-NVD0905DH-4K-K, DH-NVD0905DH-4K-L,
DH-NVD0905DH-4K-M, DH-NVD0905DH-4K-N, DH-NVD0905DH-4K-O, DH-NVD0905DH-4K-P,
DH-NVD0905DH-4K-Q, DH-NVD0905DH-4K-R, DH-NVD0905DH-4K-S, DH-NVD0905DH-4K-T,
DH-NVD0905DH-4K-U, DH-NVD0905DH-4K-V, DH-NVD0905DH-4K-W, DH-NVD0905DH-4K-X,
DH-NVD0905DH-4K-Y, DH-NVD0905DH-4K-Z,
DH-NVD0905DH-4I-4K, OEM-NVD0905DH-4I-4K, DHI-NVD0905DH-4I-4K, NVD0905DH-4I-4K
DH-NVD0905DH-4I-4K-A, DH-NVD0905DH-4I-4K-B, DH-NVD0905DH-4I-4K-C, DH-
NVD0905DH-4I-4K-D, DH-NVD0905DH-4I-4K-E, DH-NVD0905DH-4I-4K-F, DH-NVD0905DH-
4I-4K-G, DH-NVD0905DH-4I-4K-H, DH-NVD0905DH-4I-4K-I, DH-NVD0905DH-4I-4K-J, DH-
NVD0905DH-4I-4K-K, DH-NVD0905DH-4I-4K-L, DH-NVD0905DH-4I-4K-M, DH-NVD0905DH-
4I-4K-N, DH-NVD0905DH-4I-4K-O, DH-NVD0905DH-4I-4K-P, DH-NVD0905DH-4I-4K-Q, DH-
NVD0905DH-4I-4K-R, DH-NVD0905DH-4I-4K-S, DH-NVD0905DH-4I-4K-T, DH-NVD0905DH-
4I-4K-U, DH-NVD0905DH-4I-4K-V, DH-NVD0905DH-4I-4K-W, DH-NVD0905DH-4I-4K-X, DH-
NVD0905DH-4I-4K-Y, DH-NVD0905DH-4I-4K-Z**

REPORT NUMBER: 4788991120-2

ISSUE DATE: May 27, 2019

Prepared for

**Zhejiang Dahua Vision Technology Co., Ltd.
No.1199, Bin'an road, Binjiang District, Hangzhou, P.R.China.**

The results reported herein have been performed in accordance with the laboratory's terms of accreditation. This report shall not be reproduced except in full without the written approval of the Laboratory. The results in this report apply to the test sample(s) mentioned above at the time of the testing period only and are not to be used to indicate applicability to other similar products. This report does not imply that the product(s) has met the criteria for certification.



Prepared by

**UL Verification Services (Guangzhou) Co., Ltd, Song Shan Lake Branch
Building 10, Innovation Technology Park, No. 1, Li Bin Road, Song Shan Lake Hi-Tech
Development Zone Dongguan, 523808, People's Republic of China**

Tel: +86 769 22038881

Fax: +86 769 33244054

Website: www.ul.com



Revision History

<u>Rev.</u>	<u>Issue Date</u>	<u>Revisions</u>	<u>Revised By</u>
--	05/27/2019	Initial Issue	



Test Summary

Electromagnetic Interference (EMI)

EN 55032: 2015

EN 61000-3-2:2014

EN 61000-3-3:2013

Test Items	Test Method	Reference Clause	Result
Radiated Emission	EN 55032: 2015	CISPR 16-2-1:2014	PASS
Conducted Emission	EN 55032: 2015	CISPR 16-2-3: 2010+A1:2010+A2:2 014	PASS
Harmonic Emission on AC	EN 61000-3-2:2014	EN 61000-3-2:2014	N/A
Flicker Emission on AC	EN 61000-3-3:2013	EN 61000-3-3:2013	PASS

Electromagnetic Susceptibility(EMS)

EN 50130-4:2011/A1:2014

EN 55024:2010/A1:2015

ESD	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-2:2009	PASS
Radiated Immunity	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-3:2006 +A1:2008+A2:2010	PASS
Electrical Fast Transients (EFT) on AC	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-4:2012	PASS
Surge Immunity on AC	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-5:2014	PASS
Conducted Immunity on AC	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-6:2014	PASS
Power Frequency Magnetic Field	EN 55024:2010/A1:2015	EN 61000-4-8:2010	N/A
Voltage Dips and Interruptions on AC	EN 50130-4:2011/A1:2014 EN 55024:2010/A1:2015	EN 61000-4-11:2004	PASS

Note 1, N/A is an abbreviation for Not Applicable.



Note 2,

The model, DH-NVD0905DH-4K, OEM-NVD0905DH-4K, DHI-NVD0905DH-4K, NVD0905DH-4K, DH-NVD0905DH-4K-A, DH-NVD0905DH-4K-B, DH-NVD0905DH-4K-C, DH-NVD0905DH-4K-D, DH-NVD0905DH-4K-E, DH-NVD0905DH-4K-F, DH-NVD0905DH-4K-G, DH-NVD0905DH-4K-H, DH-NVD0905DH-4K-I, DH-NVD0905DH-4K-J, DH-NVD0905DH-4K-K, DH-NVD0905DH-4K-L, DH-NVD0905DH-4K-M, DH-NVD0905DH-4K-N, DH-NVD0905DH-4K-O, DH-NVD0905DH-4K-P, DH-NVD0905DH-4K-Q, DH-NVD0905DH-4K-R, DH-NVD0905DH-4K-S, DH-NVD0905DH-4K-T, DH-NVD0905DH-4K-U, DH-NVD0905DH-4K-V, DH-NVD0905DH-4K-W, DH-NVD0905DH-4K-X, DH-NVD0905DH-4K-Y, DH-NVD0905DH-4K-Z, DH-NVD0905DH-4I-4K, OEM-NVD0905DH-4I-4K, DHI-NVD0905DH-4I-4K, NVD0905DH-4I-4K, DH-NVD0905DH-4I-4K-A, DH-NVD0905DH-4I-4K-B, DH-NVD0905DH-4I-4K-C, DH-NVD0905DH-4I-4K-D, DH-NVD0905DH-4I-4K-E, DH-NVD0905DH-4I-4K-F, DH-NVD0905DH-4I-4K-G, DH-NVD0905DH-4I-4K-H, DH-NVD0905DH-4I-4K-I, DH-NVD0905DH-4I-4K-J, DH-NVD0905DH-4I-4K-K, DH-NVD0905DH-4I-4K-L, DH-NVD0905DH-4I-4K-M, DH-NVD0905DH-4I-4K-N, DH-NVD0905DH-4I-4K-O, DH-NVD0905DH-4I-4K-P, DH-NVD0905DH-4I-4K-Q, DH-NVD0905DH-4I-4K-R, DH-NVD0905DH-4I-4K-S, DH-NVD0905DH-4I-4K-T, DH-NVD0905DH-4I-4K-U, DH-NVD0905DH-4I-4K-V, DH-NVD0905DH-4I-4K-W, DH-NVD0905DH-4I-4K-X, DH-NVD0905DH-4I-4K-Y, DH-NVD0905DH-4I-4K-Z, are the same as the original model number, only difference being the item numbers, the detail test status, please refer the test report (report no.: 4788746763-141), which was issued on November 13, 2018.



CONTENTS

1	ATTESTATION OF TEST RESULTS	7
2	TEST METHODOLOGY	9
3	ACCREDITATION	9
4	MEASURING EQUIPMENT AND SOFTWARE USED	9
5	ELECTROMAGNETIC COMPATIBILITY (EMC)	10
5.1	<i>ELECTROMAGNETIC INTERFERENCE (EMI)</i>	<i>10</i>
5.1.1	CONDUCTED EMISSION	10
5.1.2	RADIATED EMISSION	20
5.1.3	FLICKER TEST	29
5.2	<i>ELECTROMAGNETIC SUSCEPTIBILITY (IMMUNITY).....</i>	<i>31</i>
5.2.1	ELECTROSTATIC DISCHARGE (ESD)	32
5.2.2	RADIATED IMMUNITY	36
5.2.3	ELECTRICAL FAST TRANSIENTS (EFT)	40
5.2.4	SURGE IMMUNITY	44
5.2.5	CONDUCTED IMMUNITY	49
5.2.6	Voltage Dips and Interruptions.....	52
6	PHOTOGRAPHS OF EMC TEST CONFIGURATION	55
6.1	<i>CONDUCTED EMISSION TEST SETUP.....</i>	<i>55</i>
6.2	<i>RADIATED EMISSION TEST SETUP</i>	<i>57</i>
6.3	<i>VOLTAGE FLUCTUATION AND FLICK MEASUREMENT</i>	<i>59</i>
6.4	<i>ESD.....</i>	<i>60</i>
6.5	<i>RADIO FREQUENCY ELECTROMAGNETIC FIELD IMMUNITY</i>	<i>61</i>
6.6	<i>ELECTRICAL FAST TRANSIENT/BURST / SURGE IMMUNITY / VOLTAGE DIPS AND SHORT INTERRUPTIONS IMMUNITY</i>	<i>62</i>
6.7	<i>CONDUCTED IMMUNITY</i>	<i>64</i>
7	Photographs of the EUT	65



1 ATTESTATION OF TEST RESULTS

Applicant Information

Company Name: Zhejiang Dahua Vision Technology Co., Ltd.
Address: No.1199, Bin'an road, Binjiang District, Hangzhou, P.R.China.

Manufacturer Information

Company Name: Zhejiang Dahua Vision Technology Co., Ltd.
Address: No.1199, Bin'an road, Binjiang District, Hangzhou, P.R.China.

EUT Information

EUT Name: NETWORK VIDEO RECORDER
Model: NVD0905DH-4I-4K
Series Model: NVD0905DH, DH-NVD0905DH, NVD0905DH-4K, DH-NVD0905DH-4K, DH-NVD0905DH-4I-4K and DH-NVD0905DH-4K, OEM-NVD0905DH-4K, DHI-NVD0905DH-4K, NVD0905DH-4K, DH-NVD0905DH-4K-A, DH-NVD0905DH-4K-B, DH-NVD0905DH-4K-C, DH-NVD0905DH-4K-D, DH-NVD0905DH-4K-E, DH-NVD0905DH-4K-F, DH-NVD0905DH-4K-G, DH-NVD0905DH-4K-H, DH-NVD0905DH-4K-I, DH-NVD0905DH-4K-J, DH-NVD0905DH-4K-K, DH-NVD0905DH-4K-L, DH-NVD0905DH-4K-M, DH-NVD0905DH-4K-N, DH-NVD0905DH-4K-O, DH-NVD0905DH-4K-P, DH-NVD0905DH-4K-Q, DH-NVD0905DH-4K-R, DH-NVD0905DH-4K-S, DH-NVD0905DH-4K-T, DH-NVD0905DH-4K-U, DH-NVD0905DH-4K-V, DH-NVD0905DH-4K-W, DH-NVD0905DH-4K-X, DH-NVD0905DH-4K-Y, DH-NVD0905DH-4K-Z, DH-NVD0905DH-4I-4K, OEM-NVD0905DH-4I-4K, DHI-NVD0905DH-4I-4K, NVD0905DH-4I-4K, DH-NVD0905DH-4I-4K-A, DH-NVD0905DH-4I-4K-B, DH-NVD0905DH-4I-4K-C, DH-NVD0905DH-4I-4K-D, DH-NVD0905DH-4I-4K-E, DH-NVD0905DH-4I-4K-F, DH-NVD0905DH-4I-4K-G, DH-NVD0905DH-4I-4K-H, DH-NVD0905DH-4I-4K-I, DH-NVD0905DH-4I-4K-J, DH-NVD0905DH-4I-4K-K, DH-NVD0905DH-4I-4K-L, DH-NVD0905DH-4I-4K-M, DH-NVD0905DH-4I-4K-N, DH-NVD0905DH-4I-4K-O, DH-NVD0905DH-4I-4K-P, DH-NVD0905DH-4I-4K-Q, DH-NVD0905DH-4I-4K-R, DH-NVD0905DH-4I-4K-S, DH-NVD0905DH-4I-4K-T, DH-NVD0905DH-4I-4K-U, DH-NVD0905DH-4I-4K-V, DH-NVD0905DH-4I-4K-W, DH-NVD0905DH-4I-4K-X, DH-NVD0905DH-4I-4K-Y, DH-NVD0905DH-4I-4K-Z♣

♣ Please refer to Page 5 of this report which indicates which item was actually tested and which were electrically identical



APPLICABLE STANDARDS	
STANDARD	TEST RESULTS
EN 55032:2015 EN 61000-3-2:2014 EN 61000-3-3:2013 EN 50130-4:2011+A1:2014 EN 55024:2010+A1:2015	PASS

Prepared By:

Gary Zhang
Engineer Project Associate

Checked By:

Shawn Wen
Laboratory Leader

Approved By:

Stephen Guo
Laboratory Manager



2 TEST METHODOLOGY

All tests were performed in accordance with the standard EN 55032, EN 55024, EN 61000-3-2, EN 61000-3-3 and EN 50130-4.

3 ACCREDITATION

Accreditation Certificate	<p>A2LA (Certificate No.: 4102.01) UL Verification Services (Guangzhou) Co., Ltd. Song Shan Lake Branch. has been assessed and proved to be in compliance with A2LA.</p> <p>FCC (FCC Recognized No.: CN1187) UL Verification Services (Guangzhou) Co., Ltd. Song Shan Lake Branch. Has been recognized to perform compliance testing on equipment subject to the Commission's Declaration of Conformity (DoC) and Certification rules</p> <p>IC(Company No.: 21320) UL Verification Services (Guangzhou) Co., Ltd. Song Shan Lake Branch. has been registered and fully described in a report filed with Industry Canada. The Company Number is 21320.</p>
---------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

4 MEASURING EQUIPMENT AND SOFTWARE USED

All measuring equipment and software used are referred to the original report (report no.: 4788746763-141).




5 ELECTROMAGNETIC COMPATIBILITY (EMC)

5.1 ELECTROMAGNETIC INTERFERENCE (EMI)

5.1.1 CONDUCTED EMISSION


Test Method:	EN 55032																										
Detector:	Peak for pre-scan (9kHz Resolution Bandwidth)																										
	Quasi-Peak if maximized peak within 6dB of Quasi-Peak limit																										
Limit:	<p>Limits for conducted disturbance at the mains ports of class B</p> <table border="1"> <thead> <tr> <th rowspan="2">Frequency Range (MHz)</th> <th colspan="2">Class B Limit (dBuV)</th> </tr> <tr> <th>Quasi-peak</th> <th>Average</th> </tr> </thead> <tbody> <tr> <td>0.15 to 0.50</td> <td>66 to 56</td> <td>56 to 46</td> </tr> <tr> <td>0.50 to 5</td> <td>56</td> <td>46</td> </tr> <tr> <td>5 to 30</td> <td>60</td> <td>50</td> </tr> </tbody> </table> <p>NOTE 1: The limit decreases linearly with the logarithm of the frequency in the range 0.15 MHz to 0.50 MHz. NOTE 2: The lower limit is applicable at the transition frequency.</p> <p>Limits for conducted disturbance at the wired network ports of class B</p> <table border="1"> <thead> <tr> <th rowspan="2">Frequency Range (MHz)</th> <th colspan="2">Class B Limit (dBuV)</th> </tr> <tr> <th>Quasi-peak</th> <th>Average</th> </tr> </thead> <tbody> <tr> <td>0.15 to 0.50</td> <td>84 to 74</td> <td>74 to 64</td> </tr> <tr> <td>0.50 to 30</td> <td>74</td> <td>64</td> </tr> </tbody> </table>		Frequency Range (MHz)	Class B Limit (dBuV)		Quasi-peak	Average	0.15 to 0.50	66 to 56	56 to 46	0.50 to 5	56	46	5 to 30	60	50	Frequency Range (MHz)	Class B Limit (dBuV)		Quasi-peak	Average	0.15 to 0.50	84 to 74	74 to 64	0.50 to 30	74	64
Frequency Range (MHz)	Class B Limit (dBuV)																										
	Quasi-peak	Average																									
0.15 to 0.50	66 to 56	56 to 46																									
0.50 to 5	56	46																									
5 to 30	60	50																									
Frequency Range (MHz)	Class B Limit (dBuV)																										
	Quasi-peak	Average																									
0.15 to 0.50	84 to 74	74 to 64																									
0.50 to 30	74	64																									

<p>Test Setup:</p>	
<p>Test Procedure:</p>	<ol style="list-style-type: none"> 1) The mains terminal disturbance voltage test was conducted in a shielded room. 2) The EUT was connected to AC power source through a LISN 1 (Line Impedance Stabilization Network) which provides a $50\Omega/50\mu\text{H} + 5\Omega$ linear impedance. The power cables of all other units of the EUT were connected to a second LISN 2, which was bonded to the ground reference plane in the same way as the LISN 1 for the unit being measured. A multiple socket outlet strip was used to connect multiple power cables to a single LISN provided the rating of the LISN was not exceeded. 3) The tabletop EUT was placed upon a non-metallic table 0.8m above the ground reference plane. And for floor-standing arrangement, the EUT was placed on the horizontal ground reference plane. 4) The test was performed with a vertical ground reference plane. The rear of the EUT shall be 0.4 m from the vertical ground reference plane. The vertical ground reference plane was bonded to the horizontal ground reference plane. The LISN 1 was placed 0.8 m from the boundary of the unit under test and bonded to a ground reference plane for LISNs mounted on top of the ground reference plane. This distance was between the closest points of the LISN 1 and the EUT. All other units of the EUT and associated equipment was at least 0.8 m from the LISN 2.

Measurement Data

Conducted Emission for Power Port Test Data

Test Mode :	Mode 1: Full system with vision signal of HDMI 1(110V/60Hz)		
AC Power :	AC 110V/60Hz	Phase :	LINE
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.2540	10.13	35.63	45.76	79.00	-33.24	QP
2	0.2540	10.13	33.91	44.04	66.00	-21.96	AVG
3	0.3780	10.15	32.65	42.80	79.00	-36.20	QP
4	0.3780	10.15	27.21	37.36	66.00	-28.64	AVG
5	0.5700	10.16	31.34	41.50	73.00	-31.50	QP
6	0.5700	10.16	24.67	34.83	60.00	-25.17	AVG
7	0.6940	10.15	31.61	41.76	73.00	-31.24	QP
8	0.6940	10.15	27.29	37.44	60.00	-22.56	AVG
9	14.1500	10.48	31.33	41.81	73.00	-31.19	QP
10	14.1500	10.48	28.25	38.73	60.00	-21.27	AVG
11	21.3460	10.37	30.11	40.48	73.00	-32.52	QP
12	21.3460	10.37	26.27	36.64	60.00	-23.36	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 1: Full system with vision signal of HDMI 1(110V/60Hz)		
AC Power :	AC 110V/60Hz	Phase :	NEUTRAL
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	58%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.1900	10.13	33.23	43.36	79.00	-35.64	QP
2	0.1900	10.13	28.84	38.97	66.00	-27.03	AVG
3	0.5700	10.15	29.39	39.54	73.00	-33.46	QP
4	0.5700	10.15	22.69	32.84	60.00	-27.16	AVG
5	0.6940	10.16	29.92	40.08	73.00	-32.92	QP
6	0.6940	10.16	25.71	35.87	60.00	-24.13	AVG
7	1.3900	10.18	25.37	35.55	73.00	-37.45	QP
8	1.3900	10.18	21.51	31.69	60.00	-28.31	AVG
9	14.2140	10.49	32.75	43.24	73.00	-29.76	QP
10	14.2140	10.49	29.46	39.95	60.00	-20.05	AVG
11	24.5780	10.36	31.47	41.83	73.00	-31.17	QP
12	24.5780	10.36	31.39	41.75	60.00	-18.25	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1(230V/50Hz)		
AC Power :	AC 230V/50Hz	Phase :	LINE
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.2540	10.13	34.50	44.63	79.00	-34.37	QP
2	0.2540	10.13	33.64	43.77	66.00	-22.23	AVG
3	0.4420	10.15	31.59	41.74	79.00	-37.26	QP
4	0.4420	10.15	23.88	34.03	66.00	-31.97	AVG
5	0.6300	10.15	31.39	41.54	73.00	-31.46	QP
6	0.6300	10.15	23.18	33.33	60.00	-26.67	AVG
7	0.7580	10.14	33.00	43.14	73.00	-29.86	QP
8	0.7580	10.14	26.13	36.27	60.00	-23.73	AVG
9	7.7500	10.25	8.96	19.21	73.00	-53.79	QP
10	7.7500	10.25	0.34	10.59	60.00	-49.41	AVG
11	14.0260	10.48	35.03	45.51	73.00	-27.49	QP
12	14.0260	10.48	29.95	40.43	60.00	-19.57	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1(230V/50Hz)		
AC Power :	AC 230V/50Hz	Phase :	NEUTRAL
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.1860	10.13	30.13	40.26	79.00	-38.74	QP
2	0.1860	10.13	25.81	35.94	66.00	-30.06	AVG
3	0.3780	10.15	29.37	39.52	79.00	-39.48	QP
4	0.3780	10.15	21.71	31.86	66.00	-34.14	AVG
5	0.6300	10.16	30.32	40.48	73.00	-32.52	QP
6	0.6300	10.16	24.12	34.28	60.00	-25.72	AVG
7	0.7580	10.16	31.63	41.79	73.00	-31.21	QP
8	0.7580	10.16	25.03	35.19	60.00	-24.81	AVG
9	1.0100	10.18	29.31	39.49	73.00	-33.51	QP
10	1.0100	10.18	23.35	33.53	60.00	-26.47	AVG
11	14.1500	10.49	36.60	47.09	73.00	-25.91	QP
12	14.1500	10.49	30.25	40.74	60.00	-19.26	AVG

Note: Measurement Level = Reading Level + Correct Factor



Conducted Emission for Telecommunication Port Test Data

Test Mode :	Mode 1: Full system with vision signal of HDMI 1(110V/60Hz)		
AC Power :	AC 110V/60Hz	Phase :	LAN 1 1000Mbps
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.3500	19.62	26.21	45.83	91.28	-45.45	QP
2	0.3500	19.62	25.90	45.52	78.28	-32.76	AVG
3	1.0220	19.30	28.14	47.44	87.00	-39.56	QP
4	1.0220	19.30	26.85	46.15	74.00	-27.85	AVG
5	7.9220	19.46	40.49	59.95	87.00	-27.05	QP
6	7.9220	19.46	38.02	57.48	74.00	-16.52	AVG
7	13.3580	19.37	47.16	66.53	87.00	-20.47	QP
8	13.3580	19.37	46.50	65.87	74.00	-8.13	AVG
9	23.1299	19.73	48.94	68.67	87.00	-18.33	QP
10	23.1299	19.73	46.53	66.26	74.00	-7.74	AVG
11	26.6100	19.79	46.90	66.69	87.00	-20.31	QP
12	26.6100	19.79	44.49	64.28	74.00	-9.72	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 1: Full system with vision signal of HDMI 1(110V/60Hz)		
AC Power :	AC 110V/60Hz	Phase :	LAN 2 1000Mbps
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.3500	19.62	26.03	45.65	91.28	-45.63	QP
2	0.3500	19.62	25.61	45.23	78.28	-33.05	AVG
3	1.0220	19.30	28.09	47.39	87.00	-39.61	QP
4	1.0220	19.30	26.44	45.74	74.00	-28.26	AVG
5	7.9260	19.46	38.82	58.28	87.00	-28.72	QP
6	7.9260	19.46	36.31	55.77	74.00	-18.23	AVG
7	13.3580	19.37	47.19	66.56	87.00	-20.44	QP
8	13.3580	19.37	46.50	65.87	74.00	-8.13	AVG
9	14.2140	19.32	47.07	66.39	87.00	-20.61	QP
10	14.2140	19.32	45.38	64.70	74.00	-9.30	AVG
11	23.1299	19.73	48.94	68.67	87.00	-18.33	QP
12	23.1299	19.73	46.52	66.25	74.00	-7.75	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1(230V/50Hz)		
AC Power :	AC 230V/50Hz	Phase :	LAN 1 1000Mbps
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28




No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.1980	19.61	25.85	45.46	95.63	-50.17	QP
2	0.1980	19.61	26.05	45.66	82.63	-36.97	AVG
3	0.3500	19.62	26.89	46.51	91.28	-44.77	QP
4	0.3500	19.62	26.76	46.38	78.28	-31.90	AVG
5	1.2700	19.27	25.50	44.77	87.00	-42.23	QP
6	1.2700	19.27	23.17	42.44	74.00	-31.56	AVG
7	8.7180	19.54	40.21	59.75	87.00	-27.25	QP
8	8.7180	19.54	37.71	57.25	74.00	-16.75	AVG
9	13.3580	19.37	47.19	66.56	87.00	-20.44	QP
10	13.3580	19.37	46.52	65.89	74.00	-8.11	AVG
11	23.1299	19.73	48.92	68.65	87.00	-18.35	QP
12	23.1299	19.73	46.51	66.24	74.00	-7.76	AVG

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1(230V/50Hz)		
AC Power :	AC 230V/50Hz	Phase :	LAN 2 1000Mbps
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temperature :	25°C	Humidity :	56%
Pressure(mbar) :	1002	Date :	2016/10/28



No.	Frequency (MHz)	Factor (dB)	Reading (dBuV)	Level (dBuV)	Limit (dBuV)	Margin (dB)	Detector
1	0.3220	19.62	26.60	46.22	92.08	-45.86	QP
2	0.3220	19.62	26.31	45.93	79.08	-33.15	AVG
3	0.3500	19.62	26.46	46.08	91.28	-45.20	QP
4	0.3500	19.62	26.29	45.91	78.28	-32.37	AVG
5	7.9220	19.46	40.51	59.97	87.00	-27.03	QP
6	7.9220	19.46	38.05	57.51	74.00	-16.49	AVG
7	13.3580	19.37	47.11	66.48	87.00	-20.52	QP
8	13.3580	19.37	46.42	65.79	74.00	-8.21	AVG
9	23.1299	19.73	48.91	68.64	87.00	-18.36	QP
10	23.1299	19.73	46.49	66.22	74.00	-7.78	AVG
11	26.6100	19.79	46.87	66.66	87.00	-20.34	QP
12	26.6100	19.79	44.44	64.23	74.00	-9.77	AVG

Note: Measurement Level = Reading Level + Correct Factor

5.1.2 RADIATED EMISSION

Test Method:	EN 55032		
Limit:	Frequency	Limit(@3m)	Remark
	30MHz-230MHz	40dBuV/m	QP value
	230MHz-1GHz	47dBuV/m	QP value
	1GHz-3GHz	50dBuV/m	Average value
		70dBuV/m	PK value
	3GHz-6GHz	54dBuV/m	Average value
74dBuV/m		PK value	

Test Setup:




Figure 1. 30MHz to 1GHz




Figure 2. Above 1 GHz

Test Procedure:

1. From 30 MHz to 1GHz test procedure as below:
 - 1) The radiated emissions were tested in a semi-anechoic chamber.
 - 2) The EUT is placed on a turntable, which is 0.8m above ground plane.
 - 3) The turntable shall be rotated for 360 degrees to determine the position of maximum emission level.
 - 4) EUT is set 3m away from the receiving antenna, which is moved from 1m to 4m to find out the maximum emissions.
 - 5) Maximum procedure was performed on the six highest emissions to ensure EUT compliance.
 - 6) And also, each emission was to be maximized by changing the polarization of receiving antenna both horizontal and vertical.
 - 7) Repeat above procedures until the measurements for all frequencies are complete.
2. Above 1GHz test procedure as below:
 - 1) Different between above is the test site, change from Semi- Anechoic Chamber to fully Anechoic Chamber.

Measurement Data:

30MHz ~ 1000MHz

Test Mode :	Mode 1: Full system with vision signal of HDMI 1 (110V/60Hz)		
AC Power :	AC 110V/60Hz	Ant. Polarization:	Horizontal
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25℃	Humidity :	53%
Pressure(mbar) :	1002	Date :	2018/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	94.0199	-15.30	40.23	24.93	40.00	-15.07	QP	100	74
2	125.0600	-9.77	41.66	31.89	40.00	-8.11	QP	100	360
3	151.2500	-10.67	42.28	31.61	40.00	-8.39	QP	400	291
4	172.5900	-11.25	44.26	33.01	40.00	-6.99	QP	100	360
5	359.8000	-6.84	33.54	26.70	47.00	-20.30	QP	400	251
6	600.3600	-1.24	39.72	38.48	47.00	-8.52	QP	100	0

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 1: Full system with vision signal of HDMI 1 (110V/60Hz)		
AC Power :	AC 110V/60Hz	Ant. Polarization:	Vertical
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	32.9099	-5.36	34.20	28.84	40.00	-11.16	QP	100	110
2	56.1899	-16.50	42.67	26.17	40.00	-13.83	QP	100	0
3	140.5800	-10.43	45.82	35.39	40.00	-4.61	QP	400	34
4	172.5900	-11.25	40.26	29.01	40.00	-10.99	QP	100	289
5	359.8000	-6.84	31.86	25.02	47.00	-21.98	QP	100	187
6	600.3600	-1.24	41.11	39.87	47.00	-7.13	QP	100	19

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1 (230V/50Hz)		
AC Power :	AC 230V/50Hz	Ant. Polarization:	Horizontal
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24



No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	30.0000	-3.26	30.62	27.36	40.00	-12.64	QP	400	199
2	125.0600	-9.77	40.16	30.39	40.00	-9.61	QP	400	347
3	172.5900	-11.25	40.76	29.51	40.00	-10.49	QP	400	81
4	359.8000	-6.84	32.54	25.70	47.00	-21.30	QP	100	0
5	600.3600	-1.24	35.22	33.98	47.00	-13.02	QP	400	0
6	906.8799	3.58	28.21	31.79	47.00	-15.21	QP	100	162

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1 (230V/50Hz)		
AC Power :	AC 230V/50Hz	Ant. Polarization:	Vertical
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	32.9099	-5.36	33.20	27.84	40.00	-12.16	QP	400	296
2	94.0199	-15.30	40.25	24.95	40.00	-15.05	QP	100	105
3	136.6999	-10.28	43.32	33.04	40.00	-6.96	QP	100	338
4	250.1899	-10.44	32.61	22.17	47.00	-24.83	QP	100	0
5	359.8000	-6.84	30.86	24.02	47.00	-22.98	QP	100	14
6	600.3600	-1.24	38.61	37.37	47.00	-9.63	QP	400	0

Note: Measurement Level = Reading Level + Correct Factor



Above 1000MHz

Test Mode :	Mode 1: Full system with vision signal of HDMI 1 (110V/60Hz)		
AC Power :	AC 110V/60Hz	Ant. Polarization:	Horizontal
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	1038.000	-9.14	38.44	29.30	56.00	-26.70	AVG	100	174
2	1040.000	-9.12	56.92	47.80	76.00	-28.20	peak	100	174
3	1109.000	-8.70	36.28	27.58	56.00	-28.42	AVG	100	213
4	1110.000	-8.69	54.99	46.30	76.00	-29.70	peak	100	213
5	1853.000	-4.05	36.41	32.36	56.00	-23.64	AVG	100	213
6	1855.000	-4.04	55.44	51.40	76.00	-24.60	peak	100	213
7	2120.000	-2.68	50.47	47.79	76.00	-28.21	peak	100	225
8	2122.000	-2.67	31.08	28.41	56.00	-27.59	AVG	100	225
9	2437.000	-1.50	36.27	34.77	56.00	-21.23	AVG	100	238
10	2440.000	-1.49	55.74	54.25	76.00	-21.75	peak	100	238
11	2809.000	-0.49	35.96	35.47	56.00	-20.53	AVG	100	147
12	2810.000	-0.48	54.78	54.30	76.00	-21.70	peak	100	147

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 1: Full system with vision signal of HDMI 1 (110V/60Hz)		
AC Power :	AC 110V/60Hz	Ant. Polarization:	Vertical
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	1038.000	-9.14	39.77	30.63	56.00	-25.37	AVG	100	157
2	1040.000	-9.12	58.73	49.61	76.00	-26.39	peak	100	157
3	1485.000	-6.37	56.89	50.52	76.00	-25.48	peak	200	356
4	1486.000	-6.37	38.42	32.05	56.00	-23.95	AVG	200	356
5	2000.000	-3.12	52.70	49.58	76.00	-26.42	peak	100	37
6	2001.000	-3.12	33.09	29.97	56.00	-26.03	AVG	100	37
7	2119.000	-2.68	51.52	48.84	56.00	-7.16	AVG	100	235
8	2120.000	-2.68	32.45	29.77	76.00	-46.23	peak	100	235
9	2450.000	-1.46	52.15	50.69	76.00	-25.31	peak	100	232
10	2452.000	-1.45	33.19	31.74	56.00	-24.26	AVG	100	232
11	2810.000	-0.48	53.95	53.47	76.00	-22.53	peak	100	158
12	2811.000	-0.48	35.72	35.24	56.00	-20.76	AVG	100	158

Note: Measurement Level = Reading Level + Correct Factor



Test Mode :	Mode 5: Full system with vision signal of HDMI 1 (230V/50Hz)		
AC Power :	AC 230V/50Hz	Ant. Polarization:	Horizontal
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24




No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	1040.000	-9.12	56.88	47.76	76.00	-28.24	peak	100	216
2	1041.000	-9.12	39.86	30.74	56.00	-25.26	AVG	100	216
3	1484.000	-6.38	32.47	26.09	56.00	-29.91	AVG	200	214
4	1485.000	-6.37	51.03	44.66	76.00	-31.34	peak	200	214
5	1855.000	-4.04	54.28	50.24	76.00	-25.76	peak	100	211
6	1856.000	-4.03	35.60	31.57	56.00	-24.43	AVG	100	211
7	2485.000	-1.33	50.32	48.99	76.00	-27.01	peak	100	151
8	2487.000	-1.32	32.19	30.87	56.00	-25.13	AVG	100	151
9	2700.000	-0.76	50.87	50.11	76.00	-25.89	peak	100	146
10	2701.000	-0.76	31.43	30.67	56.00	-25.33	AVG	100	146
11	2810.000	-0.48	55.55	55.07	76.00	-20.93	peak	100	133
12	2811.000	-0.48	36.92	36.44	56.00	-19.56	AVG	100	133

Note: Measurement Level = Reading Level + Correct Factor




Test Mode :	Mode 5: Full system with vision signal of HDMI 1 (230V/50Hz)		
AC Power :	AC 230V/50Hz	Ant. Polarization:	Vertical
Equipment :	NETWORK VIDEO DECODER	Model No :	NVD0905DH-4I-4K
Temp :	25°C	Humidity :	53%
Pressure(mbar) :	1002	Date :	2016/10/24



No.	Frequency (MHz)	Factor (dB/m)	Reading (dBuV)	Level (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Det.	Height (cm)	Azimuth (deg)
1	1039.000	-9.13	39.77	30.64	56.00	-25.36	AVG	100	161
2	1040.000	-9.12	58.25	49.13	76.00	-26.87	peak	100	161
3	1185.000	-8.23	56.18	47.95	76.00	-28.05	peak	100	29
4	1186.000	-8.22	37.80	29.58	56.00	-26.42	AVG	100	29
5	1485.000	-6.37	56.63	50.26	76.00	-25.74	peak	100	214
6	1487.000	-6.36	37.46	31.10	56.00	-24.90	AVG	100	214
7	1998.000	-3.13	33.52	30.39	56.00	-25.61	AVG	100	37
8	2000.000	-3.12	52.74	49.62	76.00	-26.38	peak	100	37
9	2495.000	-1.29	50.97	49.68	76.00	-26.32	peak	100	224
10	2496.000	-1.28	31.63	30.35	56.00	-25.65	AVG	100	224
11	2810.000	-0.48	54.53	54.05	76.00	-21.95	peak	100	150
12	2812.000	-0.48	35.79	35.31	56.00	-20.69	AVG	100	150

Note: Measurement Level = Reading Level + Correct Factor


5.1.3 FLICKER TEST

Test Method:	EN 61000-3-3		
Limits:	Test items	Limits(EN61000-3-3)	Descriptions
	P_{st}	$\leq 1.0, T_p=10\text{min}$	short-term flicker indicator
	P_{lt}	$\leq 0.65, T_p=2\text{h}$	long-term flicker indicator
	d_c	$\leq 3.3\%$	relative steady-state voltage change
	d_{max}	$\leq 4\%$ (or 6% ^{Note(1)} , 7% ^{Note(2)})	maximum relative voltage change:
	d_(t)	$\leq 3.3\%$, more than 500ms	relative voltage change characteristic
Test Setup:	 <p>1. The test supply voltage (open-circuit voltage) was the rated voltage of the EUT. The Test voltage: was maintained within $\pm 2\%$ of the nominal value. The frequency was 50 Hz $\pm 0.5\%$.</p> <p>2. The voltage fluctuations and flicker were measured at the supply terminals of the EUT.</p> <p>3. The observation period, T_p, for the assessment of flicker values by flicker measurement, flicker simulation, or analytical method was: — for P_{st}, $T_p = 10\text{ min}$; — for P_{lt}, $T_p = 2\text{ h}$.</p> <p>The observation period included that part of the whole operation cycle in which the EUT produces the most unfavorable sequence of voltage changes.</p>		



Measurement Data:

Flicker Emission IEC 61000-4-15 for 230V/50Hz



Actual Flicker (F_{fl}):	0.03
Short-term Flicker (P_{st}):	0.47
Limit (P _{st}):	1.00
Long-term Flicker (P_{lt}):	0.47
Limit (P _{lt}):	0.65
Maximum Relative Volt. Change (d_{max}):	0.00%
Limit (d _{max}):	4.00%
Relative Steady-state Voltage Change (dc):	0.21%
Limit (dc):	3.30%
T_{max} 3.30% (dt):	0.00ms
Limit (dt>Lim):	500ms

Flicker Emission - IEC 61000-3-3, EN 61000-3-3

U_{rms} = 230.3 V P = 46.63 W
I_{rms} = 0.209 A pf = 0.754

MVD0050H

Test completed, Result: PASSED

2016-10-29 15:28:44

Range: 50 A
V_{nom}: 230 V
TestTime: 10 min (100%)

HAF-1000-090-Pariser

- Full Bar : Actual Values
- Empty Bar : Maximum Values
- Circles : Average Values
- Blue : Current , Green : Voltage , Red : Failed

U_{rms} = 230.3V Freq = 50.000 Range: 50 A
I_{rms} = 0.209A I_{pk} = 0.537A cf = 2.000
P = 46.63W S = 61.85VA pf = 0.754

Test - Time : 1 x 10min = 10min (100 %)

LIN (Line Impedance Network): No LIN

Limits : P_{lt} : 0.65 P_{st} : 1.00
d_{max} : 4.00 % dc : 3.30 %
dtLim: 3.30 % dt>Lim: 500ms

Test completed, Result: PASSED



5.2 ELECTROMAGNETIC SUSCEPTIBILITY (IMMUNITY)

Performance Criteria Description

Criterion A:
The apparatus shall continue to operate as intended during and after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used asintended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, either of these may be derived from the product description and documentation and what the user may reasonably expect from the apparatus if used as intended.
Criterion B:
The apparatus shall continue to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. The performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed. No change of actual operating state or stored data is allowed. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, either of these may be derived from the product description and documentation and what the user may reasonably expect from the apparatus if used as intended.
Criterion C:
Temporary loss of function is allowed, provided the function is self-recoverable or can be restored by the operation of the controls.

5.2.1 ELECTROSTATIC DISCHARGE (ESD)

Test Method:	EN61000-4-2
Criterion Required:	B
Discharge Impedance:	330 Ω / 150 pF
Polarity:	Positive & Negative
Number of Discharge:	Minimum 10 times at each test point (for EN50130-4) At least 200 discharges and 100 each for polarity (for EN55024)
Discharge Mode:	Single Discharge
Discharge Period:	1 second minimum
Equipment Used:	Refer to section 5 for details.
Test Setup:	<p style="text-align: center;">Test set-up for tabletop equipment</p>
Test Procedure:	<ol style="list-style-type: none"> 1) Contact discharges to the conductive surfaces and to coupling planes: Air discharge at slots and apertures, and insulating surfaces: On those parts of the EUT where it was not possible to perform contact discharge testing, the equipment was investigated to identify user accessible points where breakdown may occur. This investigation was restricted to those areas normally handled by the user. A minimum of 10 single air discharges were applied to the selected test point for each such area. The application of electrostatic discharges to the contacts of open connectors was not required by this standard. 2) The EUT was put on a 0.8m high wooden table for table-top equipment or 0.1m high for floor standing equipment standing on the ground reference plane (GRP). 3) A horizontal coupling plane(HCP) 1.6m by 0.8m in size was placed on the table, and the EUT with its cables were isolated from the HCP by an insulating support thick than 0.5mm. The VCP 0.5m by 0.5m in size & HCP were constructed from the same material type & think mess as that of the



	<p>GRP, and connected to the GRP via a 470kΩ resistor at each end. The distance between EUT and any of the other metallic surfaces excepted the GRP, HCP and VCP was greater than 1m.</p> <p>4) During the contact discharges, the tip of the discharge electrode was touch the EUT before the discharge switch is operated. During the air discharges, the round discharge tip of the discharge electrode was approached as fast as possible to touch the EUT.</p> <p>5) After each discharge, the ESD generator was removed from the EUT, the generator was then retrigged for a new single discharge. For ungrounded product, a discharge cable with two resistances was used after each discharge to remove remnant electrostatic voltage. 10 times of each polarity single discharge were applied to HCP and VCP.</p>
--	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



Test Results:

Test Mode 1
For EN 55024: 2010
Test Voltage: AC 230V/50Hz

	Contact Discharge								Air Discharge							
	25 times / each								10 times / each							
Voltage	2 kV		4 kV		6 kV		8 kV		2 kV		4 kV		8 kV		10 kV	
Point/Polarity	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-
HCP	A	A	A	A	---	---	---	---	---	---	---	---	---	---	---	---
VCP	A	A	A	A	---	---	---	---	---	---	---	---	---	---	---	---
1-19	A	A	A	A	---	---	---	---	---	---	---	---	---	---	---	---
20-24	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---
25-78	A	A	A	A	---	---	---	---	---	---	---	---	---	---	---	---
79-84	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---

For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz																
	Contact Discharge								Air Discharge							
	25 times / each								10 times / each							
Voltage	2 kV		4 kV		6 kV		8 kV		2 kV		4 kV		8 kV		10 kV	
Point/Polarity	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-
HCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
VCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
1-19	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
20-24	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---
25-78	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
79-84	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---



Test Voltage: AC 195.5V/50Hz																
	Contact Discharge								Air Discharge							
	25 times / each								10 times / each							
Voltage	2 kV		4 kV		6 kV		8 kV		2 kV		4 kV		8 kV		10 kV	
Point/Polarity	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-
HCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
VCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
1-19	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
20-24	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---
25-78	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
79-84	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---

Test Voltage: AC 253V/50Hz																
	Contact Discharge								Air Discharge							
	25 times / each								10 times / each							
Voltage	2 kV		4 kV		6 kV		8 kV		2 kV		4 kV		8 kV		10 kV	
Point/Polarity	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-
HCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
VCP	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
1-19	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
20-24	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---
25-78	A	A	A	A	A	A	---	---	---	---	---	---	---	---	---	---
79-84	---	---	---	---	---	---	---	---	A	A	A	A	A	A	---	---

5.2.2 RADIATED IMMUNITY

Test Method:	EN 61000-4-3
Criterion Required:	A
Test Setup:	




Figure 1. 80MHz to 1GHz ,




Figure 2 1GHz to 2.7GHz

Test Procedure:

- 1) For table-top equipment, the EUT was placed in the chamber on a non-conductive table 0.8m high. For arrangement of floor-standing equipment, the EUT was mounted on a non-conductive support 0.1m above the supporting plane. For human body-mounted equipment, the EUT may be tested in the same manner as table top items.
- 2) If possible, a minimum of 1 m of cable is exposed to the electromagnetic field. Excess length of cables interconnecting units of the EUT shall be bundled low-inductively in the approximate center of the cable to form a bundle 30 cm to 40 cm in length.
- 3) The EUT was initially placed with one face coincident with the calibration plane. The EUT face being illuminated was contained within the UFA (Uniform Field Area).
- 4) The frequency ranges to be considered were swept with the signal modulated and pausing to adjust the RF signal level or to switch oscillators and antennas as necessary. Where the frequency range was swept incrementally, the step size was not exceed 1% of the preceding frequency value.
- 5) The dwell time of the amplitude modulated carrier at each frequency was not be less than the time necessary for the EUT to be exercised and to respond, and was not less than 0.5s.
- 6) The test normally was performed with the generating antenna facing each side of the EUT.



	<p>7) The polarization of the field generated by each antenna necessitates testing each selected side twice, once with the antenna positioned vertically and again with the antenna positioned horizontally.</p> <p>8) The EUT was performed in a configuration to actual installation conditions, a video camera, test data and/or an audio monitor were used to monitor the performance of the EUT.</p>
--	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



Test Results:

Test Mode 1

For EN 55024: 2010

Test Voltage: AC 230V/50Hz

Modulation : AM 80% , 1KHz sine wave , Dwell time: 3.0 S				
Frequency Step Size : 1 % of preceding frequency value				
Frequency (MHz)	Antenna Polarization	face	Field strength (V/m)	Result
80~1000	Horizontal &Vertical	Front	3 V/m	A
80~1000	Horizontal &Vertical	Rear	3 V/m	A
80~1000	Horizontal &Vertical	Left	3 V/m	A
80~1000	Horizontal &Vertical	Right	3 V/m	A

For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz

Modulation : AM 80% , 1KHz sine wave , Dwell time: 3.0S				
Frequency Step Size : 1 % of preceding frequency value				
Frequency (MHz)	Antenna Polarization	face	Field strength (V/m)	Result
80~2700	Horizontal &Vertical	Front	10 V/m	A
80~2700	Horizontal &Vertical	Rear	10 V/m	A
80~2700	Horizontal &Vertical	Left	10 V/m	A
80~2700	Horizontal &Vertical	Right	10 V/m	A




Test Voltage: AC 195.5V/50Hz

Modulation : AM 80% , 1KHz sine wave , Dwell time: 3.0 S				
Frequency Step Size : 1 % of preceding frequency value				
Frequency (MHz)	Antenna Polarization	face	Field strength (V/m)	Result
80~2700	Horizontal &Vertical	Front	10 V/m	A
80~2700	Horizontal &Vertical	Rear	10 V/m	A
80~2700	Horizontal &Vertical	Left	10 V/m	A
80~2700	Horizontal &Vertical	Right	10 V/m	A

Test Voltage: AC 253V/50Hz

Modulation : AM 80% , 1KHz sine wave , Dwell time: 3.0 S				
Frequency Step Size : 1 % of preceding frequency value				
Frequency (MHz)	Antenna Polarization	face	Field strength (V/m)	Result
80~2700	Horizontal &Vertical	Front	10 V/m	A
80~2700	Horizontal &Vertical	Rear	10 V/m	A
80~2700	Horizontal &Vertical	Left	10 V/m	A
80~2700	Horizontal &Vertical	Right	10 V/m	A

5.2.3 ELECTRICAL FAST TRANSIENTS (EFT)

Test Method:	EN 61000-4-4
Test Level:	±2.0kV on AC port (for EN50130-4) ±1.0kV on AC port (for EN55024) ±1.0kV on Signal port (for EN50130-4) ±0.5kV on Signal port (for EN55024)
Polarity:	Positive & Negative
Repetition Frequency:	100kHz (for EN50130-4) 5kHz (for EN55024)
Burst Period:	300ms
Test Duration:	2 minute per level & polarity
Test Setup:	
Test Procedure:	<ol style="list-style-type: none"> 1) The EUT was placed on a ground reference plane (GRP) insulated by an insulating support 0.1m thick and the GRP was placed on a 0.8m high wooden table for table-top equipment. For floor standing equipment, the EUT was placed on a 0.1m high wooden support above the GRP. 2) The GRP shall project beyond the EUT and the clamp by at least 0.1m on all sides. The distance between the EUT and any other of the metallic surface except the GRP was greater than 0.5m. All cables to the EUT were placed on the insulation support 0.1m above GRP. A cable not subject to EFT was routed as far as possible from cable under test to minimize the coupling between the cables. 3) The length of signal and power cable between the EUT and EFT generator was 0.5m. If the cable is a non-detachable supply cable more than 0.5m, the excess length of this cable shall be folded to avoid a flat coil and situated at a distance of 0.1m above the GRP. 4) The EUT was conducted the below specified test voltages for line and neutral or line, neutral and earth simultaneously (for telecommunication, single, control and DC port line with capacitive coupling clamp), 120 seconds duration. If the equipment contains identical ports, only one was tested; multicomputer cables, such as a 50-pair telecommunication cable, were tested as a single cable. Cables did not be split or divided into groups of conductors for this test; interface ports, which were intended by the manufacturer to be connected to data cables not longer than 3 m, did not be tested.

Test Results:

Test Mode 1
For EN 55024: 2010
Test Voltage: AC 230V/50Hz

Pulse : 5/50 ns		Repetition Rate: <u>5 kHz</u>			
Burst : 15m/300ms					
Test time : 1 min/each condition					
Voltage/ Mode/ Polarity/ Result/ Phase		<u>0.5 kV</u>		<u>1.0 kV</u>	
		+	-	+	-
Power Line	L	---	---	A	A
	N	---	---	A	A
	L-N	---	---	A	A
	PE	---	---	A	A
	L-PE	---	---	A	A
	N-PE	---	---	A	A
	L-N-PE	---	---	A	A
Signal Line	RJ45	A	A	---	---



For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz

Pulse : 5/50 ns		Repetition Rate: <u>5/100</u> kHz			
Burst : 15m/300ms					
Test time : 1 min/each condition					
Voltage/ Mode/ Polarity/ Result/ Phase		<u>1.0</u> kV		<u>2.0</u> kV	
		+	-	+	-
Power Line	L	---	---	A	A
	N	---	---	A	A
	L-N	---	---	A	A
	PE	---	---	A	A
	L-PE	---	---	A	A
	N-PE	---	---	A	A
	L-N-PE	---	---	A	A
Signal Line	RJ45	A	A	---	---

Test Voltage: AC 195.5V/50Hz

Pulse : 5/50 ns		Repetition Rate: <u>5/100</u> kHz			
Burst : 15m/300ms					
Test time : 1 min/each condition					
Voltage/ Mode/ Polarity/ Result/ Phase		<u>1.0</u> kV		<u>2.0</u> kV	
		+	-	+	-
Power Line	L	---	---	A	A
	N	---	---	A	A
	L-N	---	---	A	A
	PE	---	---	A	A
	L-PE	---	---	A	A
	N-PE	---	---	A	A
	L-N-PE	---	---	A	A
Signal Line	RJ45	A	A	---	---



Test Voltage: AC 253V/50Hz

Pulse : 5/50 ns		Repetition Rate: <u>5/100</u> kHz			
Burst : 15m/300ms					
Test time : 1 min/each condition					
Voltage/ Mode/ Polarity/ Result/ Phase		<u>1.0 kV</u>		<u>2.0 kV</u>	
		+	-	+	-
Power Line	L	---	---	A	A
	N	---	---	A	A
	L-N	---	---	A	A
	PE	---	---	A	A
	L-PE	---	---	A	A
	N-PE	---	---	A	A
	L-N-PE	---	---	A	A
Signal Line	RJ45	A	A	---	---

5.2.4 SURGE IMMUNITY

Test Method:	EN 61000-4-5	
Test Level:	FOR EN50130-4:2011/A1:2014 ± 0.5/1.0 kV Line to Line, ± 0.5/1.0 kV Signal port	For EN55024: ±1 kV Line-to-Line ± 0.5/1.0 kV Signal port
Criterion Required:	B	
Polarity:	Positive & Negative	
Interval:	60s between each surge	
No. of Surges:	5 positive, 5 negative at 0°, 90°, 180°, 270°.	
Test Setup:	<p style="text-align: center;">For AC port</p>	
Test Procedure:	<ol style="list-style-type: none"> 1) The EUT was placed on a ground reference plane (GRP) insulated by an insulating support 0.1 m thick and the GRP was placed on a 0.8m high wooden table for table-top equipment. For floor standing equipment, the EUT was placed on a 0.1m high wooden support above the GRP. 2) The 1.2/50 μs surge was to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks were required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines and to provide sufficient decoupling impedance to the surge wave so that the specified wave may be applied on the lines under test. 3) The power cord between the EUT and the coupling/decoupling network was not exceed 2 m in length. The interconnection line between the EUT and the coupling/ decoupling network shall not exceed 2 m in length. 4) The EUT was conducted 0.5 kV and 1 kV test voltage for line to line and line to neutral and conducted 0.5 kV, 1 kV and 2 kV test voltage for line to earth and neutral to earth, five positive pulses and five negative pulses each at 0°, 90°, 180° and 270° for a.c. power ports and five positive pulses and five negative surge pulses for d.c. power ports (for telecommunication port, It was 0.5 kV for indoor cable longer than 10m line to ground and 0.5kV,1kV test voltage for outdoor cable line to ground, five positive pulses and five negative surge pulses), The test levels were applied on the EUT with a 2 Ω generator source impedance for power supply terminals and 40Ω output impedance for interconnection lines. The tests were done at repetition rate one per minute. 	



Test Results:

Test Mode 1

For EN 55024: 2010

Test Voltage: AC 230V/50Hz

Waveform : 1.2/50µs(8/20µs) Repetition rate : 60 sec Time : 20 time/each condition						
/Phase Voltage / Mode / Polarity / Result			0°	90°	180°	270°
<u>0.5/1.0 kV</u>	L-N	+	A	A	A	A
		-	A	A	A	A
<u>0.5/1.0/2.0kV</u>	L-PE	+	A	A	A	A
		-	A	A	A	A
	N-PE	+	A	A	A	A
		-	A	A	A	A

Waveform : 10/700µs Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A



For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz						
Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 20 time/each condition						
/Phase Voltage / Mode / Polarity / Result			0°	90°	180°	270°
<u>0.5/1.0 kV</u>	L-N	+	A	A	A	A
		-	A	A	A	A
<u>0.5/1.0/2.0 kV</u>	L-PE	+	A	A	A	A
		-	A	A	A	A
	N-PE	+	A	A	A	A
		-	A	A	A	A

Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

Waveform : 10/700 μ s Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

**Power Port**

Test Voltage: AC 195.5V/50Hz						
Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 20 time/each condition						
/Phase Voltage / Mode / Polarity / Result			0°	90°	180°	270°
<u>0.5/1.0 kV</u>	L-N	+	A	A	A	A
		-	A	A	A	A
<u>0.5/1.0/2.0kV</u>	L-PE	+	A	A	A	A
		-	A	A	A	A
	N-PE	+	A	A	A	A
		-	A	A	A	A

Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

Waveform : 10/700 μ s Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

**Power Port**

Test Voltage: AC 253V/50Hz						
Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 20 time/each condition						
/Phase Voltage / Mode / Polarity / Result			0°	90°	180°	270°
<u>0.5/1.0 kV</u>	L-N	+	A	A	A	A
		-	A	A	A	A
<u>0.5/1.0/2.0kV</u>	L-PE	+	A	A	A	A
		-	A	A	A	A
	N-PE	+	A	A	A	A
		-	A	A	A	A

Waveform : 1.2/50 μ s(8/20 μ s) Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

Waveform : 10/700 μ s Repetition rate : 60 sec Time : 5 time/each condition				
Voltage	<u>0.5 kV</u>		<u>1.0 kV</u>	
Mode / Polarity / Result	+	-	+	-
RJ45	A	A	A	A

5.2.5 CONDUCTED IMMUNITY

Test Method:	EN 61000-4-6
Criterion Required:	A
Test Setup:	<p style="text-align: center;">For AC port</p>
Test Procedure:	<ol style="list-style-type: none"> 1) The EUT was placed on an insulating support of 0.1m height above a ground reference Plane, arranged and connected to satisfy its functional requirement. All cables exiting the EUT was supported at a height of at least 30 mm above the ground reference plane. 2) The coupling and decoupling devices were required; they were located between 0.1m and 0.3m from the EUT. This distance was to be measured horizontally from the projection of the EUT on to the ground reference plane to the coupling and decoupling device. 3) Each AE, used with clamp injection, shall be placed on an insulating support 0.1m above the ground reference plane. A decoupling network shall be installed on each cable between the EUT and AE except the cable under test. All cables connected to each AE, other than those being connected to the EUT, shall be provided with decoupling networks. The decoupling networks connected to each AE (except those on cables between the EUT and AE) shall be applied no further than 0.3m from the AE. The cable(s) between the AE and the decoupling network (s) or in between the AE and the injection clamp shall not be bundled nor wrapped and shall be kept between 30mm and 50mm above the ground reference plane. 4) The frequency range was swept from 150 kHz to 80MHz, using the signal levels established during the setting process, and with the disturbance signal 80 % amplitude modulated with a 1 kHz sine wave, pausing to adjust the RF signal level or to change coupling devices as necessary. Where the frequency was swept incrementally, the step size does not exceed 1% of the preceding frequency value. The dwell time of the amplitude modulated carrier at each frequency was not less than the time necessary for the EUT to be exercised and to respond, and was not less than 0.5 s.

Test Results:

Test Mode 1

For EN 55024: 2010

Test Voltage: AC 230V/50Hz

Frequency : 0.15~80MHz, Modulation : AM 80%,1KHz sine wave, Dwell time: 3.0s Frequency Step Size : 1 % of preceding frequency value			
Frequency	Test mode	Voltage(V)	Result
0.15 ~ 80MHz	Power(M3)	3	A
0.15 ~ 80MHz	RJ45	3	A

For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz

Frequency : 0.15~100MHz, Modulation : AM 80%,1KHz sine wave, Dwell time: 3.0s Frequency Step Size : 1 % of preceding frequency value			
Frequency	Test mode	Voltage(V)	Result
0.15 ~ 100MHz	Power(M3)	10	A
0.15 ~ 100MHz	RJ45	10	A




Test Voltage: AC 195.5V/50Hz

Frequency : 0.15~100MHz, Modulation : AM 80%, 1KHz sine wave, Dwell time: 3.0s Frequency Step Size : 1 % of preceding frequency value			
Frequency	Test mode	Voltage(V)	Result
0.15 ~ 100MHz	Power(M3)	10	A
0.15 ~ 100MHz	RJ45	10	A

Test Voltage: AC 253V/50Hz

Frequency : 0.15~100MHz, Modulation : AM 80%, 1KHz sine wave, Dwell time: 3.0s Frequency Step Size : 1 % of preceding frequency value			
Frequency	Test mode	Voltage(V)	Result
0.15 ~ 100MHz	Power(M3)	10	A
0.15 ~ 100MHz	RJ45	10	A

5.2.6 Voltage Dips and Interruptions

Test Method:	EN 61000-4-11
Test Level:	<p>For EN50130-4: 80% for 250 Periods 70 % for 25 Periods 40 % for 10 Periods 0% for 250 Periods</p> <p>For EN55024: >95 % for 0.5 Periods 30 % for 25 Periods >95 % for 250 Periods</p>
No. of Dips / Interruptions:	3 per Level
Test Setup:	
Test Procedure:	<ol style="list-style-type: none"> 1) The EUT was placed on a ground reference plane (GRP) insulated by an insulating support 0.1 m thick and the GRP was placed on a 0.8m high wooden table for table-top equipment. For floor standing equipment, the EUT was placed on a 0.1m high wooden support above the GRP. 2) The test was performed with the EUT connected to the test generator with the shortest power supply cable as specified by the EUT manufacturer. 3) The EUT was tested for each selected combination of test level and duration with a sequence of three dips /interruptions with intervals of 10 s minimum. Each representative mode of operation was tested. 4) For EUT with more than one power cord, each power cord was tested individually.



Test Results:

Test Mode 1

For EN 55024: 2010

Voltage(UT): AC 100V/50 Hz Interval(s) : 10s Times : 3										
Test mod	Test level UT %	Durations (period / ms)	Phase / Result							
			0	45	90	135	180	225	270	315
Voltage interruptions	>95%	250	C	C	C	C	C	C	C	C
Voltage dips	30%	25	B	B	B	B	B	B	B	B
	>95%	0.5	B	B	B	B	B	B	B	B

Voltage(UT): AC 230V/240 V/50 Hz Interval(s) : 10s Times : 3										
Test mod	Test level UT %	Durations (period / ms)	Phase / Result							
			0	45	90	135	180	225	270	315
Voltage interruptions	>95%	250	C	C	C	C	C	C	C	C
Voltage dips	30%	25	A	A	A	A	A	A	A	A
	>95%	0.5	A	A	A	A	A	A	A	A



For EN 50130-4: 2011

Test Voltage: AC 230V/50Hz Interval(s) : 10s Times : 3										
Test mod	Test level UT %	Durations (period / ms)	Phase / Result							
			0	45	90	135	180	225	270	315
Voltage interruptions	100%	250	A	A	A	A	A	A	A	A
Voltage dips	20%	250	A	A	A	A	A	A	A	A
	30%	25	A	A	A	A	A	A	A	A
	60%	10	A	A	A	A	A	A	A	A

100% and 20% is permitted to UPS to meet the requirements of Result A.

Test Voltage: AC 195.5V/50Hz Interval(s) : 10s Times : 3										
Test mod	Test level UT %	Durations (period / ms)	Phase / Result							
			0	45	90	135	180	225	270	315
Voltage interruptions	100%	250	A	A	A	A	A	A	A	A
Voltage dips	20%	250	A	A	A	A	A	A	A	A
	30%	25	A	A	A	A	A	A	A	A
	60%	10	A	A	A	A	A	A	A	A

100% and 20% is permitted to UPS to meet the requirements of Result A.

Test Voltage: AC 253 V 50 Hz Interval(s) : 10s Times : 3										
Test mod	Test level UT %	Durations (period / ms)	Phase / Result							
			0	45	90	135	180	225	270	315
Voltage interruptions	100%	250	A	A	A	A	A	A	A	A
Voltage dips	20%	250	A	A	A	A	A	A	A	A
	30%	25	A	A	A	A	A	A	A	A
	60%	10	A	A	A	A	A	A	A	A

100% and 20% is permitted to UPS to meet the requirements of Result A.



6 PHOTOGRAPHS OF EMC TEST CONFIGURATION

6.1 CONDUCTED EMISSION TEST SETUP

Power Port





Telecommunication Port





6.2 RADIATED EMISSION TEST SETUP

30MHz ~ 1000MHz



Above 1000MHz



6.3 VOLTAGE FLUCTUATION AND FLICKER MEASUREMENT



Flicker



6.4 ESD



6.5 RADIO FREQUENCY ELECTROMAGNETIC FIELD IMMUNITY



6.6 ELECTRICAL FAST TRANSIENT/BURST / SURGE IMMUNITY / VOLTAGE DIPS AND SHORT INTERRUPTIONS IMMUNITY

Main



LAN



6.7 CONDUCTED IMMUNITY




7 Photographs of the EUT

1) EUT Photo



2) EUT Photo



3) EUT Photo



4) EUT Photo



END OF REPORT