

Deviz local

Valoarea de deviz 303 450,52 Lei


№ crt.	Simbol norme și Cod resurse	Denumire lucrări și cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					Pe unitate de măsură	Total
1	2	3	4	5	6	7
		Total borderou de resurse № 01-01-2009:				

Manopera :

1.	7123010010200	Betonist	h-om	45,0300	57,66	2 596,429
2.	7124010010700	Dulgher	h-om	202,1660	57,66	11 656,892
3.	7124010010730	Dulgher 3	h-om	65,4052	57,66	3 771,264
4.	7134030012200	Izolator hidrofug	h-om	79,9700	57,66	4 611,070
5.	7213050013100	Tinichigiu	h-om	477,3500	57,66	27 524,001
6.	9310060019900	Muncitor necalificat	h-om	11,2860	57,66	650,750
7.	9310060019920	Muncitor deservire CM	h-om	327,0084	57,66	18 855,304
8.	9310060019930	Muncitor	h-om	19,9080	57,66	1 147,895
		Total manopera				70 813,60

Materiale:

1.	1212121212121	apa	m3	4,9770	15,00	74,655
2.	1411122201752	Piatra sparta	m3	13,1100	280,00	3 670,800
3.	1421102200290	Pietris ciuruit spalat de mal 7-30 mm	m3	8,2901	280,00	2 321,228
4.	1421102200525	Nisip sortat nespalat de riu si lacuri 0,0-7,0 mm	m3	8,9809	240,00	2 155,416
5.	20101029010142	Lemn rotund de rasinoase pentru fabricarea lemnarei ecarisate sau pregatirea lamanelor (пластиты) б=20-24см calitatea a II a	m3	0,3000	3 340,00	1 002,000
6.	2010102903495	Scinduri de rasinoase	m3	2,7900	3 340,00	9 318,600
7.	20101029041692	Dulapuri ecarisati de rasinoase calit a Ia	m3	1,3612	3 340,00	4 546,408
8.	20101029041693	Dulapuri ecarisati de rasinoase б=19-22mm calit a III a	m3	0,3000	3 340,00	1 002,000
9.	20101029041694	Dulapuri ecarisati de rasinoase б=44mm calit a III a	m3	0,5000	3 340,00	1 670,000
10.	2010102906900	Rigle de rasinoase	m3	1,6380	3 340,00	5 470,920
11.	20101029087371	Grinzi ecarisate de rasinoase de б=100,125 mm, calit, a II a	m3	0,0984	3 340,00	328,656
12.	20101029087372	Grinzi ecarisate de rasinoase б=40-75mm calit a II a	m3	0,2624	3 340,00	876,416
13.	2020132920073	Placi PAL grosime 6 mm	m3	0,2366	3 340,00	790,244
14.	20301129470001	Pervaz de rasinoase	m	254,8000	2,00	509,600
15.	2124117000002	Fosfat de amoniu, praf, calitate superioara	kg	37,8000	18,00	680,400
16.	2413217300010	Cleme	buc	22,4400	8,00	179,520
17.	24142161094821	Pasta antiseptica	kg	3,2144	26,00	83,574
18.	2430127317192	Diamoniu fosfat	kg	34,6500	16,30	564,795
19.	2521106718272	Profil pentru etansare din spuma polimerica	m	33,0940	12,00	397,128



20.	2640122303000	Coame metalice pentru placi tip tigla	buc	66,1878	26,00	1 720,883
21.	2651122100397	Ciment metalurgic cu adaosuri M 30	kg	2 130,0900	1,76	3 748,958
22.	26821326004260	Carton gudronat (толь)	m2	5,5432	8,30	46,008
23.	2682132600465	Folie suplimentara polimerica	m2	746,5430	9,00	6 718,887
24.	2710403640000	Tabla plana protejata anticoroziv	kg	165,4696	11,00	1 820,165
25.	2710403643000	Placi din tabla amprentata tip tigla	m2	761,1597	112,00	85 249,886
26.	2710403740000	Pazie din tabla protejata anticoroziv	buc	26,4751	34,00	900,153
27.	2710406311726	Burlan rotund prefabricat tip brass	m	47,1240	55,00	2 591,820
28.	2710406311800	Jgheaburi semirotunde prefabricate tip brass	m	124,1562	56,00	6 952,747
29.	27106020001211	Otel beton laminat la cald in colaci D = 6,3 - 6,5mm (катанка горячекатанная в мотках Д=6,3 - 6,5 мм)	kg	7,1832	11,00	79,016
30.	28631463108081	Balamale (петли)	buc	20,0000	15,00	300,000
31.	28631463112701	Cremon (ручка оконная)	buc	5,0000	12,00	60,000
32.	2873145887000	Cuie cu cap conic tip A pentru constructii	kg	41,5920	15,60	648,835
33.	2874115837745	Suruburi	buc	1 182,4400	1,00	1 182,440
34.	28741458870491	Cuie de constructie	kg	15,3080	24,50	375,046
35.	2875274000050	Elemente de legatura	buc	23,0444	29,00	668,288
36.	2875274000501	Cot de jgheab	buc	23,6488	31,00	733,113
37.	2875274000502	Cot burlan	buc	22,4400	51,00	1 144,440
38.	2875274000503	Cot de capat	buc	11,2200	31,00	347,820
39.	2875276311231	Cirlige din otel zn pentru jgheaburi	buc	165,5416	29,00	4 800,706
40.	2875276312000	Accesorii metalice pentru fixare	buc	5 956,9020	0,15	893,536
41.	28752763120001	Шпильки (fise)	buc	7 790,0136	0,15	1 168,502
42.	4100116202818	Apa pentru mortare si betoane	m3	3,1088	15,00	46,632
43.	4100126202818	Apa	m3	1,1400	15,00	17,100
Total materiale de constructii						157 857,34
Total utilaje de constructii						0,00

Total	Lei	228 670,94
Asigurarea sociala	24 %	16 995,26
Transportarea materialelor	1,1 %	1 736,43
Total		247 402,63
Cheltueli de regie	1,1 %	2 721,43
Beneficiul de deviz	1,1 %	2 751,37
TVA	20 %	50 575,09

Total deviz:

303 450,52

Intocmit

Administrator Bosticeanu Piote
(funcția, semnătura, numele, prenumele)

