



RDW

Vehicle Technology Division



THE NETHERLANDS
(N E D E R L A N D)



COMMUNICATION

Concerning ⁽¹⁾ :

- ~~- approval granted~~
- approval extended
- ~~- approval refused~~
- ~~- approval withdrawn~~
- ~~- production definitely discontinued~~

of a type of tyre for motor vehicles pursuant to Regulation number 30.

Approval number: E4-30R-0247444

Extension number: 01

- | | |
|--|---|
| 1. Manufacturer's name and address | : Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover |
| 2. Tyre type designation ⁽²⁾ | |
| 2.1 Brand-name(s)/trademark(s) | : BARUM
<u>POINT S</u> |
| 2.2 Trade description(s)/Commercial name(s) | : BARUM, BRILLANTIS 2
<u>POINT S, SUMMERSTAR 3+</u> |
| 3. If applicable, name and address of the manufacturer's representative | : not applicable |
| 4. Summarized description | |
| 4.1 Tyre size designation | : 175/70 R 13 |
| 4.2 Category of use | : normal / snow / special use / temporary use ⁽¹⁾ |
| 4.3 Structure | : diagonal / bias belted / radial / run-flat tyre ⁽¹⁾ |
| 4.4 Speed category symbol | : T |
| 4.5 Load-capacity index | : 82 |
| 5. Technical Service and, where applicable, test laboratory approved for purposes of approval or of verification of conformity | : Continental Reifen Deutschland GmbH
Vahrenwalder Str. 9
30165 Hannover |
| 6. Date of report issued by that service | : 13.03.2015 |
| 7. Number of report issued by that service | : 4386729, 4386731 |
| 8. Reason(s) of extension (if applicable) | : Tyre Type Designation added |
| 9. Any remarks | : - |



Approval number: E4-30R-0247444

Extension number: 01

10. Place : Zoetermeer
11. Date : 10-MAY-2017
12. Signature :



13. The list of documents in the approval file which are deposited at the administrative service having delivered the approval and which can be obtained upon request.

- Application form relating to ECE approval for a pneumatic tyre pursuant to Regulation number 30.


-
- The drawing of the tyre's sidewalls, tread and dimensioned cross-section.
 - The test report as mentioned in item 7.

(1) Strike out what does not apply.

(2) A list of Brand name(s)/trademark(s) or Trade description(s)/ Commercial name(s) may be annexed to this communication



The drawing may contain more position numbers than required by UNECE type approval.





Position	Description	min height	Tire Side	TSL Content
1/194	Brand Name (Trade mark)		both	POINT S
2 or 3	Trade description (Commercial name)		both	POINT S SUMMERSTAR 3+
4	Tire size designation	>6 (or 9	both	175/70 R 13
6	Structure	>4 mm	both	RADIAL
7 or 8	Service description (LI / SSY)	>6 mm	both	82T
9 or 10	Additional service description	>6 mm	both	
13 or 14	"M+S" (or "M.S" or "M&S")		both	
15	Tube type / Tubeless		both	TUBELESS
17	Extra Load or Reinforced	>6 mm	both	-
19	PSI index	>2 mm	both	-
27	Regroovability		both	-
32	"TEMPORARY USE ONLY"	>12,7 mm	both	-
34	"INFLATE TO 420 kPa (60 PSI)"	>12,7 mm	both	-
78	Mark for special use tires	>4 mm	both	-
79	"TRACTION"	>4mm	both	-


Position	Description	min height	Tire Side	TSL Content
116	"Inside"/"Outside" marking		SS	OUTSIDE
117	"Inside"/"Outside" marking		OSS	INSIDE
134	Date of manufacturing	>4 mm	SS	[WWYY]
179	Alpine Symbol		both	-
184	Runflat Symbol		both	-
191	"FRT" marking	>4 mm	both	-
135	UN approval mark	>12 mm	both	E4
137	UN R30/R54/R75 approval no.		both	0247444
If Pos 78 is used	Tread depth			-
	Surface void/ fill ratio			-
If Pos 79 is used	Number of circumferential ribs			-
	Number of block-like elements			-
	Depth of lateral grooves/sipes >=50%of main groove depth?			-

Design Dimensions (calculated /Annex-5)		
Overall diameter	A (mm)	576
Section Width	B (mm)	177
Measuring rim	C (Rim Code)	5.0Jx13
Approval No.	E4-30R-0247444	
Extension:	01	
Name:	D. Schoenfelder	
Drawing No.:	1	
Date:	5/4/17 12:53 PM	
Pattern	3547.02	






1st Sidewall



2nd Sidewall



2962-03



6		5					
T	175/70 R 13	82	TT TL	576	177	5Jx13	
SS	4 Category of use	LI	Tyre type	A mm	B mm	C Rim-Code	Remarks
Brand name	1	Barum		Drawing No. /Remarks:		Checked / Date :	
Tyre type designation	2	Brillant 2		P- 0247444		30.04.2009	Fischer

