

ANTREPRENOR

**"Alpro-Construct" SRL, IDNO
1009600009470**

BENEFICIAR

**IS "MOLDELECTRICA", IDNO
1002600004580**

Coordonat:

Aprobat:

***Lucrari de protectie anticoroziva a
pilonilor metalici (20 buc.)***

(denumirea obiectivului)

Contract Nr. **14761****DEVIZ LOCAL № 2**

LEA-110 kV Edinet # Colicauti nr. 108 (tip pilon Y1M); nr. 139 (tip pilon Y110-4+5); Total 2 piloni.

Valoarea de deviz **115 610.71 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2	413.94	5.10	2 111.82
	7141020013400	Vopsitor industrial	h-om	45.533	46.38	2 111.82
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 18 buc.	m2	61.20	6.51	398.56
	7134030012200	Izolator hidrofug	h-om	3.672	46.38	170.31
	2682132602	Пленка п/э	m2	68.544	3.33	228.25
	2922140006702	Macara de fereastră	h-ut	0.918	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2	413.94	171.50	70 991.00
	7141020013300	Zugrav vopsitor	h-om	1 150.753	46.38	53 371.92
	2430116104160	Email (с алюмин. пастой)	kg	99.346	103.93	10 325.03
	2430226100981 f	Grund anticorosiv 2 in 1	kg	66.230	62.50	4 139.38
	2430226109260	Diluant 509 D.005-1 S 3123	kg	17.385	53.67	933.05
	2320166200676	White spirit	kg	41.394	53.67	2 221.62
Total			Lei			73 501.38
Asigurarea sociala			24.00 %			13 356.97
Transportarea materialelor			6.00 %			1 070.84
Cheltuieli directe						87 929.19
Cheltuieli de regie			7.00 %			6 155.05
Total						94 084.24

Beneficiu de deviz	2.40 %	2 258.02
Total		96 342.26
TVA	20.00 %	19 268.45

Total deviz: **Lei** **115 610.71**
Incluziv salariu **55 654.05**

Intocmit _____
(functia, semnatura)

Verificat _____
(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761**

Anexa Nr. 1

Catalog de preturi unitare

LEA-110 kV Edinet # Colicauti nr. 108 (tip pilon Y1M); nr. 139 (tip pilon Y110-4+5); Total 2 piloni.
(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatare cu perie de sirma	m2			5.10
	7141020013400	Vopsitor industrial	h-om	0.110	46.38	5.10
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 18 buc.	m2			6.51
	7134030012200	Izolator hidrofug	h-om	0.060	46.38	2.78
	2682132602	Пленка п/э	m2	1.120	3.33	3.73
	2922140006702	Macara de fereastră	h-ut	0.015	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2			171.50
	7141020013300	Zugrav vopsitor	h-om	2.780	46.38	128.94
	2430116104160	Email (с алюмин. пастой)	kg	0.240	103.93	24.94
	2430226100981f	Grund anticorosiv 2 in 1	kg	0.160	62.50	10.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	0.042	53.67	2.25
	2320166200676	White spirit	kg	0.100	53.67	5.37

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761****DEVIZ LOCAL № 2****LEA-110 kV Edinet # Colicauti nr. 108 (tip pilon Y1M); nr. 139 (tip pilon Y110-4+5); Total 2 piloni.****Valoarea de deviz 115 610.71 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7

Manopera:

1.	7134030012200	Izolator hidrofug	h-om	3.672	46.38	170.31
2.	7141020013300	Zugrav vopsitor	h-om	1 150.753	46.38	53 371.92
3.	7141020013400	Vopsitor industrial	h-om	45.533	46.38	2 111.82
Total manopera						55 654.05

Materiale:

1.	2320166200676	White spirit	kg	41.394	53.67	2 221.62
2.	2430116104160	Email (с алюмин. пастой)	kg	99.346	103.93	10 325.03
3.	2430226100981f	Grund anticorosiv 2 in 1	kg	66.230	62.50	4 139.38
4.	2430226109260	Diluant 509 D.005-1 S 3123	kg	17.385	53.67	933.05
5.	2682132602	Пленка п/э	m2	68.544	3.33	228.25
Total materiale de constructii						17 847.33

Utilaje de constructii:

1.	2922140006702	Macara de fereastră	h-ut	0.918	0.00	0.00
Total utilaje de constructii						0.00

Total	Lei	73 501.38
Asigurarea sociala	24.00 %	13 356.97
Transportarea materialelor	6.00 %	1 070.84
Cheltuieli directe		87 929.19
Cheltuieli de regie	7.00 %	6 155.05
Total		94 084.24
Beneficiu de deviz	2.40 %	2 258.02
Total		96 342.26
TVA	20.00 %	19 268.45

Total deviz: Lei 115 610.71
Incluziv salariu 55 654.05

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)