

1	2	3	4	5	6	7
	295227000 2719	Instalatie de foraj hidraulic cu circulatie inversa FA 50	h-ut	0,04	210,00	8,40
	291234000 2510	Motocompresor mobil de aer de joasa presiune, debit 6,0 - 9,9 mc/min	h-ut	0,04	44,00	1,76
15	FjB03E k=0,48	Foraj hidraulic cu circulatie directa executat cu instalatie FA 50 ,0-400 m adincime, in teren grupa III d=394mm k=0,48	m			355,32
	811302007 0100	Sondor	h-om	3,12	57,66	86,35
	295212734 4244	Sape foraj cu insertie widia	buc	0,015	7 800,00	58,97
	295227000 3793	Instalatie de foraj hidraulic cu circulatie directa FA 50	h-ut	0,52	210,00	210,00
16	FjF04B	Curatirea si spalarea cu apa a forajelor executate cu instalatie FA 50 hidraulica	m			34,80
	811302007 0100	Sondor	h-om	0,24	57,66	13,84
	121212121 2121	Apa	m3	0,90	12,00	10,80
	295227000 2719	Instalatie de foraj hidraulic cu circulatie inversa FA 50	h-ut	0,04	210,00	8,40
	291234000 2510	Motocompresor mobil de aer de joasa presiune, debit 6,0 - 9,9 mc/min	h-ut	0,04	44,00	1,76
17	FjD01A	Tubarea coloanelor de protectie la forajele executate hidraulic cu instalatie FA 20	m			1 122,62
	811302007 0100	Sondor	h-om	2,52	57,66	145,30
	272210330 3721	Teava sudata elicoidal	m	1,01	890,00	903,39
	295227000 2711	Instalatie de foraj hidraulic cu circulatie inversa FA 20	h-ut	0,42	176,00	73,92
18	FjF03A	Cimentarea coloanelor de exploatare pentru izolarea straturilor acvifere la forajele executate cu instalatie FA 20 hidraulica	m3			3 335,31
	811302007 0100	Sondor	h-om	15,70	57,66	905,26
	265112210 0024	Ciment portland P 40 saci S388	kg	1 049,00	1,65	1 730,85
	121212121 2121	Apa	m3	0,70	12,00	8,40
	295227000 2711	Instalatie de foraj hidraulic cu circulatie inversa FA 20	h-ut	3,14	176,00	552,64
	291234000 2510	Motocompresor mobil de aer de joasa presiune, debit 6,0 - 9,9 mc/min	h-ut	3,14	44,00	138,16
19	FjB03G	Foraj hidraulic cu circulatie	m			608,57