

1	2	3	4	5	6	7
	0237					
		3. Blocul A Tavane suspendate				
8	CK50B	Tavane suspendate executate pe santier din ghips-carton, grosime 9,5 mm pe structura din profile zincata: suprafete tavanelor plane, cu goluri pentru corpuri de iluminat	m2			191,26 133,53
	742201006 0100	Timplar	h-om	2,3000	52,57	120,91
	931006001 9920	Muncitor deservire CM	h-om	0,1900	52,57	9,99
	285210733 5349	Lucru la masina	h-om	0,0500	52,57	2,63
	266210270 0202	Placi ghips-carton 250x120x0,95 cm	buc	0,3700	56,67	20,97
	284013631 2702	Profile tabla zincata CD 60x27 mm L=4 m	buc	0,8600	23,33	20,06
	284013631 2703	Profile tabla zincata UD 27x28 mm L=4 m	buc	0,2700	15,00	4,05
	287411583 3871	Suruburi cu autofiletare 3,5x25 mm	buc	45,0000	0,06	2,70
	287411583 3874	Suruburi autofiletante 3,5x9,5 mm	buc	20,0000	0,08	1,60
	282211570 8000	Element de sustinere	buc	1,2000	2,33	2,80
	287527630 5105	Conector	buc	4,4400	1,25	5,55

Intocmit



(funcția, semnătura)