

1	2	3	4	5	6	7
		cu impanare fara innorore,h=12cm				
7	DI107	Amorsarea suprafetelor straturilor de baza in vederea aplicarii unui strat de beton asfaltic	t	0,09	68,24 0,00	6,14 0,00
8	DB19G	Imbracaminte de beton asfaltic cu agregat SKPg- SM STB 1033:2008, executata la cald, in grosime de 6,0 cm, cu asternere mecanica	m2	150,00	278,16 3,46	41 723,94 518,94
9	DI107	Amorsarea suprafetelor straturilor de baza in vederea aplicarii unui strat de beton asfaltic	t	0,04	68,25 0,00	3,07 0,00
10	DB16H	Imbracaminte de beton asfaltic cu agregate marunte SMBg- / 2.3 SM STB 1033:2008, executata la cald; in grosime de 4,0 cm, cu asternere mecanica	m2	150,00	186,55 2,88	27 982,20 432,45

**Total 2.1 Reparatia
imbracamintei rutiere**

77 471,25

Incluziv salariu

1 697,80

2.2 Consolidarea acostamentelor

11	DI115	Consolidarea acostamentelor cu un strat de piatra sparta de 10 cm	m2	450,00	31,66 1,83	14 248,72 822,52
12	DI95	Sapatura mecanizata a rigolelor in pamint de cat.II	100 m3	1,76	4 899,08 2 191,08	8 622,38 3 856,30

**Total 2.2 Consolidarea
acostamentelor**

22 871,10

Incluziv salariu

4 678,82

L 92 R 14 Drum de acces spre s. Rublenita Noua (Sectorul 3)

		Acostamente				
1	DH02B	Scarificarea usoara a impietuirii pina la 10 cm adincime cu autogreder, inclusiv reprofilarea	100m2	2,25	33,00 0,00	74,25 0,00
2	TsC21C1	Sapatura mecanica cu autogreder de pina la 175 CP, inclusiv imprastierea pamintului la 10 m, in teren catg. II (ridicarea acostamentelor cu material	100 m3	0,08	1 202,50 0,00	96,20 0,00

