

SPECIFICATII DE PRET

Catre: IMSP CRDM ,Mun.Chisinau,str.C.Virnav,13 Tel 022 888416; crdm@ms.md

or.Chisinau, 25 martie 2024

Instalare camera frigorifica cu T=0 gr.C 3250x3100x2,60(H)=27 m3 si dotare utilaj frigorific complet 2 set:

-Asamblare incapere teploizolata,materiale si servicii

1. Panou sandwich 65 m2 x1800 mdl cu instalare		=117000 mdl
2. Usa frigorifica pozitiva 900x1900 mm batanta	1 buc	=27000 mdl
3. Aluminui pentru podea 2 mm	11m2 x3000 mdl	=33000 mdl
4. Stelaj in camera	4 set x15000	=60000 mdl
5. Perdea din silicon 2 m2		=4800 mdl
Total cost incapere teploizolata fara TVA		=201500 mdl
Total cost incapere teploizolata cu TVA 20%		=241800 mdl
-Montare echipamente frigorifice		-2 set
6. Agregat frigorific cu compressor Danfoss MTZ18 ,380V,condensator racirepentru t=43 gr.C, presostat KP-5		=27000 mdlx2 =54000 mdl
7.Evaporator racire 1x300 mm Guentner	1x300 mm;	=27000 mdl x2=54000 mdl
8. Panou de comanda cu controller Dixell, protectie faza RNPP311	18A	7200 mdlx2 =14400 mdl
9.Ventil solenoid,Ventil termostatic ,filtru uscare,vizor,teava Cu,altele Servicii de montare,transport, neprevazute		24000 mdl x2=4800mdl
10.Aranjarea in panourile de comanda a contabilizarii timpului de lucru a echipamentelor frigorifice		24000mdl x2 buc. =48000 mdl
Total cost echipament frigorific fara TVA 20%	2 set.	=182000 mdl
Total cost echipament frigorific cu TVA 20%	2 set	=218400 mdl
Total cost in ansamblu camera frigorifica fara TVA 20%	1 set	=383500 mdl

Preturile includ TVA 20%

