

**Lucrari de reparatii capitale a
parcarii aferente cladirii nr.162
din bd Stefan cel Mare si Sfint.**

mun. Chisinau

(denumirea obiectivului)

DEVIZ LOCAL №

Valoarea de deviz 912 000,79 lei

Intocmit in prexouri curente

№ crt.	Simbol norme ei Cod resurse	Denumire lucrri ei cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					Pe unitate de mrsurr	Total
1	2	3	4	5	6	7
Total borderou de resurse № :						

Manopera :

1.	7129020012800	Pavator	h-om	1 189,97	57,66	68 613,64
2.	8141260100100	Fasonator	h-om	25,30	57,66	1 458,80
3.	9310060019900	Muncitor necalificat	h-om	296,53	57,66	17 097,87
4.	9310060019922	Muncitor deservire	h-om	33,34	57,66	1 922,27
5.	9310060019930	Muncitor	h-om	1,46	57,66	84,21
Total manopera						89 176,79

Materiale:

1.	1411122201752	Piatra sparta	m3	0,01	256,00	1,61
2.	1421102200513	Nisip sortat nespalat de riu si lacuri 0,0-3,0 mm	m3	0,41	198,00	80,19
3.	1421102200546	Nisip pentru constructii 0,3-0,7 mm (pentru rosturi)	m3	5,28	198,00	1 044,45
4.	1421102200547	Nisip pentru constructii 0,3-0,7 mm (pentru strat)	m3	90,41	198,00	17 901,87
5.	1421402200393	Balast pentru betoane 0-71 mm S1667	m3	345,78	282,00	97 508,92
6.	2651122100024	Ciment portland P 40 saci S388	kg	137,70	1,51	207,93
7.	2651122100027	Ciment portland M400 saci, (pentru rosturi)	kg	1 688,00	1,51	2 548,88
8.	2651122100442	Ciment portland M400 saci, (pentru strat)	kg	16 595,15	1,51	25 058,68
9.	2661112800655	Placi din beton, pentru trotuare 300*300mm, gr.80mm STST 17608-91	m2	1 070,82	232,00	248 431,40
10.	2663102100001	Beton clasa...(pt.informatie)	m3	6,48	0,00	0,00
11.	2666122800325	Bordura beton pentru trotuare тип "Бордюор" БР 100*30*15	m	135,67	136,00	18 451,80
12.	2881116002701	Disc pentru taiat placi	buc	21,10	185,33	3 910,46
13.	4100116202806	Apa industriala in cisterne pt. lucrari drumuri-terasam.	m3	61,19	10,00	611,90
14.	4100116202818	Apa pentru mortar si betoane	m3	0,41	10,00	4,05
Total materiale de constructii						415 762,14

Utilaje de constructii:

1.	2875277400000	Compresor (7 atm.) 6 m ³ /min	h-ut	0,46	196,00	91,14
2.	2922140007000	Macara	h-ut	1,50	400,00	600,00
3.	2952220003546	Autogreder pneu 175 cp	h-ut	12,76	397,00	5 063,81

4.	2952240004010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	40,35	320,00	12 913,18
5.	2952260003501	Excavator pe senile cu o cupa cu motor termic, 0,40-0,70 mc	h-ut	1,75	397,00	696,74
6.	2952260003544	Scarificator mecanic remorcat	h-ut	0,05	140,00	6,76
7.	2952260003554	Buldozer 79kw (108CP)	h-ut	1,97	397,00	783,20
8.	2952270003370	Ciocan pneumatic 4.0-5.9 m3/min	h-ut	0,46	50,00	23,25
9.	2952270004706	Motoferestraul	h-ut	5,40	127,00	685,80
10.	2952500005607	Tractor pe senile 80 cp	h-ut	0,05	156,00	7,53
11.	2955270002608	Fierastrau mecanic cu lant de 2,2 kw, 3 cp (Drujba)	h-ut	4,50	56,00	252,00
12.	3410520005701	Autoturn	h-ut	20,20	350,00	7 070,00
13.	3410540000006	Autobasculanta	h-ut	106,55	395,00	42 088,83
14.	3410540005603	Autocisterna 5-8 t cu dispozitive de stropire	h-ut	6,07	296,00	1 795,62
Total utilaje de constructii						72 077,88

Total:


Total	lei	577 016,81
Asigurarea socila si med	22,50 %	20 064,78
Transportarea materialelor	7,00 %	29 103,35
Total	100,00 +	626 184,94
Cheltuieli de regie	14,50 %	90 796,82
Total	100,00 +	716 981,75
Beneficiu	6,00 %	43 018,91
Total	100,00 +	760 000,66
TVA	20,00 %	152 000,13
Total	100,00 +	912 000,79

912 000,7

9

Total deviz:

Intocmit



(functioia, semnrtura)

Verificat

(functioia, semnrtura)