

1	2	3	4	5	6	7
57	TsG14AI	Cosirea vegetatiei	100m2	358,00	35,75 35,75	12 798,21 12 798,21
58	TsH111A	Cosirea ierbei pe acostamente mecanizat	1 km	70,00	46,38 10,38	3 246,52 726,52
59	DI139A	Profilarea partii carosabile a drumurilor impetruite K=8	1 km	44,80	275,00 0,00	12 320,00 0,00
60	DI92B	Reparatia gropilor mici si izolate la impetruiri din macadam executate manual: cu adincimea 10cm.	m2	380,00	41,90 20,18	15 920,48 7 668,78
61	DH27B	Vopsirea parapetelor din metal barei de siguranta)	m2	30,00	43,32 35,17	1 299,68 1 055,18
62	RpDA15A	Varuirea plantatiei si accesoriilor la drumuri, executata manual	m2	40,00	15,39 11,53	615,78 461,28

Total Capitolul 16. L205
G41-Mateuti-
Bosernita, km0-7.1

53 231,92

Incluziv salariu

22 709,97

		16. Capitolul 17. L206 Soldanesti-Papautii-Tareuca km 0-5.0				
63	DI93B	Plombarea gropilor la imbracaminti din beton asfaltic cu grosimea pina la: 5 cm.	m2	126,00	228,65 44,40	28 810,09 5 594,17
64	DI139A	Profilarea partii carosabile a drumurilor impetruite k=8	1 km	24,00	275,00 0,00	6 600,00 0,00
65	TsH111A	Cosirea ierbei pe acostamente mecanizat	1 km	20,00	46,38 10,38	927,58 207,58
66	DH27Bf	Vopsirea stilpilor p/u ind.rutiere	m2	15,00	43,32 35,17	649,84 527,59
67	DH27B	Vopsirea parapetelor din metal barei de siguranta)	m2	50,00	43,32 35,17	2 166,13 1 758,63
68	RpDE10C	Marcaje rutiere longitudinale, simple sau duble, transversale si diverse, cu intreruperi sau continue, executate mecanizat cu vopsea de email pe	m2	10,00	78,40 34,60	784,02 345,96



H. Birn