

1	2	3	4	5	6	7
	0000					
	271060342 0379	Otel patrat lam.cald lt = 30 mm	kg	0,0110	10,80	0,13
	295224000 4010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	0,0114	220,00	2,57
35	DB19C	Imbracaminte de beton asfaltic cu agregat mare, executata la cald, in grosime de 6,0 cm, cu asternere manuala	m2			181,07 9,22
	712904001 0110	Asfaltator	h-om	0,1600	57,66	9,22
	111100010 001310	Mixtura asfaltica preparata la cald cu agregate mari	t	0,1410	1 180,00	167,17
	142110220 0000	Nisip bitumat	t	0,0030	250,00	0,83
	271060342 0375	Otel patrat lam.cald lt = 50 mm	kg	0,0160	10,80	0,18
	295224000 4010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	0,0166	220,00	3,67
		3.3. Lucrari de demontare				
36	RpEL03 A	Demontarea conductorului aerian cu legare ordinara	1 km			922,55 922,55
	713701001 1510	Electromontor	h-om	16,0000	57,66	922,55

Intocmit

_____ ()

(funcția, semnătura)

Verificat

_____ (.)

(funcția, semnătura)

