

Устройство дорожного покрытия из асфальтобетона с крупным наполнением и ямочного ремонта асфальтобетонного покрытия с деградированной поверхностью по ул.Ленина села Казаклия

(denumirea obiectivului)

DEVIZ LOCAL №
Ремонт

Valoarea de deviz 623 600,06 Lei

Intocmit in prețuri curente

№ crt.	Simbol norme și Cod resurse	Denumire lucrări și cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					Pe unitate de măsură	Total
1	2	3	4	5	6	7
Total borderou de resurse № :						

Manopera :

1.	0003	muncitor	h-om.	0,1440	47,13	6,787
2.	7129020012800	Pavator	h-om	37,5000	47,13	1 767,375
3.	7129040010110	Asfaltator	h-om	333,4550	47,13	15 715,734
4.	9310060019930	Muncitor	h-om	10,5000	47,13	494,865
Total manopera						17 984,76

Materiale:

1.	111100010001310	Mixtura asfaltica preparata la cald cu agregate mari	t	162,1500	982,93	159 382,100
2.	111100010001311	Mixtura asfaltica preparata la cald cu agregate marunte	t	75,2000	1 222,88	91 960,576
3.	1411122201646	Piatra sparta pentru pt.drumuri r.magmatice 15-25 mm	m3	12,6875	433,17	5 495,845
4.	1411122201672	Piatra sparta pentru pt.drumuri r.magmatice 40-63 mm	m3	76,1875	433,17	33 002,139
5.	1421102200000	Nisip bitumat	t	3,4500 2,4000	982,93 1 222,88	3 391,109 2 934,912
6.	14221022055070	Beton asfaltic	t	50,5000	1 222,88	61 755,440
7.	1422102205518	Beton asfaltic preparat la cald cu granulatie fina	t	44,2750	1 222,88	54 143,012
8.	23203226000401	Bitum	t	0,4944	7 592,92	3 753,940
9.	23203226001101	Bitum	t	0,2310	7 592,92	1 753,965
10.	2710603420379	Otel patrat lam.cald lt = 30 mm	kg	27,2000	0,00	0,000
11.	4100116202806	Apa industriala in cisterne pt. lucrari drumuri-terasam.	m3	11,6850	0,00	0,000
Total materiale de construcții						417 573,04

Utilaje de construcții:

1.	0001	gudronator BA2 (utilaj de amorsarea)	h-ut	3,2240	17,57	56,646
2.	0002	Topitor de bitum	h-ut	0,1440	17,23	2,481
3.	2912340002517	Motocompresor 3 WF-3	h-ut	19,2500	16,39	315,507
4.	2940420007200	Freza cu latimea tamburului 1000 mm	h-ut	23,1000	324,64	7 499,184
5.	2952220000000	Autogudronator 3500 l - 3600 l	h-ut	0,1440	222,79	32,082
6.	2952220003546	Autogreder pina la 175 cp	h-ut	6,3165	284,69	1 798,244
7.	2952240004003	Compactor pe pneuri static autopropulsat 10,1-16 tf	h-ut	13,3250	161,55	2 152,654
8.	2952240004010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	29,4500	161,55	4 757,648
9.	29522400040101	Compactor 10 t	h-ut	6,6500	161,55	1 074,308

10.	2952240004105	Compactor 5-6 t	h-ut	1,9950	161,55	322,292
11.	2952240004127	Placa compactoare, vibro	h-ut	5,3900	161,55	870,754
12.	2952240005100	Repartizor finisor de mixturi asfaltice cu motor term. 92 cp	h-ut	14,9550	211,43	3 161,936
13.	2952270004033	Topitor de bitum	h-ut	3,0800	17,23	53,068
14.	2952500005008	Tractor pina la 80 cp	h-ut	3,0800	162,40	500,192
15.	3410540005603	Autocisterna 5-8 t cu dispozitive de stropire	h-ut	2,8625	162,40	464,870
		Total utilaje de construcții				23 061,87

Total	Lei	458 619,67
Соц мед страх	22,5 %	4 046,57
Итого		462 666,24
Наклатные расходы	8 %	37 013,30
Итого		499 679,54
Прибыль	4 %	19 987,18
Итого		519 666,72
НДС	20 %	103 933,34

Total deviz:

623 600,06

Intocmit

SA Drumuri Cahul

(funcția, semnătura)

Verificat

Primaria Cazaclia

(funcția, semnătura)