

1	2	3	4	5	6	7
	Ш=1,000	executate manual (emulsie apoasa)				
	7141020013300	Zugrav vopsitor	h-om	411,147		
	2430116103800	Vopsea pe baza de copolimeri vinilici	kg	332,240		
	2681126001472 1	Hirtie pentru slefuit uscata 23x30 gr 6	buc	415,300		
Total Capitolul 5.2. Perete					170 106,319	
Incluziv salariu					140 600,147	
8. Capitolul 5.3. Glafurile interioare						
24	CK18C п. K=3=1,000; M=1,000; Ш=1,000	Montarea baghetelor la lambriuri din aluminiu (coltarului din aluminiu)	m	77,700	16,293 <hr/> 13,668	1 265,981 <hr/> 1 062,019
	7422010060100	Timplar	h-om	20,202		
	2743123549025	Baghete din aluminiu	m	81,585		
25	CF02B п. K=3=1,000; M=1,000; Ш=1,000	Tencuieli interioare de 2 cm grosime, driscuite, executate manual, la pereti sau stilpi, pe suprafete plane cu mortar de ciment-var marca M 100-T pentru sprit, grund si stratul vizibil, pe zidarie de caramida sau blocuri mici de beton (Внутренняя штукатурка толщиной 2 см)	m2	18,500	68,925 <hr/> 52,570	1 275,113 <hr/> 972,545
	7122050013400	Zidar	h-om	14,800		
	9310060019920	Muncitor deservire CM	h-om	3,700		
	2651122100402	Ciment metalurgic cu adaosuri M 30 saci S1500	kg	146,150		
	1421102200513	Nisip sortat nespalat de riu si lacuri 0,0-3,0 mm	m3	0,444		
26	CN53A п. K=3=1,000; M=1,000; Ш=1,000	Grunduirea suprafetelor interioare a peretilor si tavanelor	m2	18,500	6,304 <hr/> 3,154	116,628 <hr/> 58,353
	7141020013300	Zugrav vopsitor	h-om	1,110		
	2652102100696	Грунтовка	kg	3,700		
27	CF50B п. K=3=1,000; M=1,000; Ш=1,000	Tencuieli interioare de 5 mm grosime, executate manual, cu amestec uscat pe baza de ipsos, la pereti si pereti despartitori, preparare manuala a mortarului.	m2	18,500	63,617 <hr/> 54,514	1 176,917 <hr/> 1 008,503

