

(denumirea obiectivului)

DEVIZ LOCAL №

Lucrari de electromontare

Valoarea de deviz 223 454,72 Lei

№ crt.	Simbol norme ei Cod resurse	Denumire lucrri ei cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					Pe unitate de mrsurr	Total
1	2	3	4	5	6	7
Total borderou de resurse № :						

Manopera :

1.	1	Muncitor	h-om	1 193,9816	31,93	38 123,834
2.	7137010011520	Electrician in constructii	h-om	56,4400	31,93	1 802,129
3.	7141020013300	Zugrav vopsitor	h-om	7,4800	31,93	238,836
Total manopera						40 164,80

Materiale:

1.	101-1714	Suruburi de constructii cu piulite si saibe	kg	3,0000	100,00	300,000
2.	1011977	Suruburi cu piulite si saibe	kg	2,0380	100,00	203,800
3.	1019852	Vopsea	kg	12,6100	55,00	693,550
4.	126	Consola p/u corp de iluminat	buc	136,0000	70,83	9 632,880
5.	2320166200676	White spirit	kg	0,6800	65,00	44,200
6.	2430226100700	Grund alchidic	kg	0,7072	65,00	45,968
7.	2430226109444	Diluant alchidic D.005-12 NI 1708-61 A1	kg	0,7480	55,00	41,140
8.	503	Corpuri de iluminat LED 50W	buc	30,0000	361,98	10 859,400
9.	504	Corpuri de iluminat LED 30W	buc	38,0000	337,50	12 825,000
10.	5555	Cablu de energie AVVG 2*2.5mm2	m	102,0000	2,50	255,000
11.	55588	Clama p/u banda	buc	140,0000	2,47	345,800
12.	66588	Coliere plastic 2.5*250	buc	160,0000	1,00	160,000
13.	777	Conductor SIP 2*25mm2	m	4 840,0000	10,32	49 948,800
14.	7778	Clema de ancora PA-1000	buc	140,0000	37,50	5 250,000
15.	7788	Banda p/u montare	m	140,0000	8,33	1 166,200
16.	8888	Automat VA 47-29 3p/C25	buc	2,0000	60,00	120,000
17.	999	Cleme de ramificare 16-95	buc	136,0000	24,75	3 366,000
Total materiale de constructii						95 257,74

Utilaje de constructii:

1.	031001	Autohidroascensoare, capacitate de ridicare 12 m	h-ut	172,5444	10,00	1 725,444
2.	031050	Turle telescopice, 25 m	h-ut	293,7800	10,00	2 937,800
3.	330206	Masini de gaurit electrice	h-ut	0,0800	28,00	2,240
4.	400001	Autocamion de bord, tonaj pina la 5 t	h-ut	7,4800	10,00	74,800
5.	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,4850	10,00	4,850
Total utilaje de constructii						4 745,13

Cheltuieli directe	Lei	175 543,39
Materiale auxiliare	5 %	4 762,89
Total		180 306,28
Cheltuieli de transport	5 %	4 762,89
Total		185 069,17
Cheltuieli de depozit	1,2 %	1 143,09
Total		186 212,26
TVA	20 %	37 242,46

Total deviz:

223 454,7

2

Intocmit


Director

A.Marta

“Moldcablu”

Verificat

Primar



DEVIZ LOCAL № Lucrari de electromontare

Valoarea de deviz 223 454,72 Lei

№ crt.	Simbol norme ei Cod resurse	Lucrri ei cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					Pe unitate de mrsurr incl. salariu	Total incl. salariu
1	2	3	4	5	6	7
1. Lucrari de constructie						
1	33-04-017-1	Suspendarea cu ajutorul mecanismelor a conductorilor izolati LEA 0,38 kV	1 km	4,8400	14 772,833 <hr/> 2 083,113	71 500,512 <hr/> 10 082,268
1		Muncitor	h-om	315,7616		
999		Cleme de ramificare 16-95	buc	136,0000		
66588		Coliere plastic 2.5*250	buc	160,0000		
55588		Clama p/u banda	buc	140,0000		
7788		Banda p/u montare	m	140,0000		
7778		Clema de ancora PA-1000	buc	140,0000		
777		Conductor SIP 2*25mm2	m	4 840,0000		
031001		Autohidroascensoare, capacitate de ridicare 12 m	h-ut	118,1444		
2	33-04-014-2	Montarea corpurilor de iluminat: cu lampi luminescente	buc	68,0000	434,931 <hr/> 73,120	29 575,340 <hr/> 4 972,140
1		Muncitor	h-om	155,7200		
101-1714		Suruburi de constructii cu piulite si saibe	kg	3,0000		
504		Corpuri de iluminat LED 30W	buc	38,0000		
503		Corpuri de iluminat LED 50W	buc	30,0000		
031001		Autohidroascensoare, capacitate de ridicare 12 m	h-ut	54,4000		
400001		Autocamion de bord, tonaj pina la 5 t	h-ut	7,4800		
Cheltuieli directe			Lei		101 075,852	
Asigurarea sociala si medicala			22,5 %		3 387,242	
Total					104 463,094	
Cheltueli de regie			10 %		10 446,309	
Total					114 909,403	
Beneficiul de deviz			5 %		5 745,470	
Total					120 654,873	
Total Lucrari de constructie					120 654,873	
Inclusiv salariu					15 054,408	
2. Lucrari de montare						
3	08-02-376-17	Noduri sectorului a liniei aeriene la pozarea CIA	buc	19,0000	125,569	2 385,811 <hr/> 2 002,011

					105,369	
	1	Muncitor	h-om	62,7000		
	1011977	Suruburi cu piulite si saibe	kg	0,3800		
	1019852	Vopsea	kg	2,4700		
	031050	Turle telescopice, 25 m	h-ut	20,9000		
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0950		
4	08-02-376-18	Noduri sectorului tip a liniei aeriene la pozarea CIA pe stilp intermediar	buc	4,0000	50,681	202,724
					36,081	144,324
	1	Muncitor	h-om	4,5200		
	1011977	Suruburi cu piulite si saibe	kg	0,0800		
	1019852	Vopsea	kg	0,5200		
	031050	Turle telescopice, 25 m	h-ut	2,1600		
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0200		
5	08-02-376-22	Noduri sectorului tip a liniei electrice aeriene la pozarea CIA pe stilp de colt	buc	4,0000	67,888	271,552
					51,088	204,352
	1	Muncitor	h-om	6,4000		
	1011977	Suruburi cu piulite si saibe	kg	0,0800		
	1019852	Vopsea	kg	0,5200		
	031050	Turle telescopice, 25 m	h-ut	3,0400		
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0200		
6	08-02-376-29	Noduri sectorului tip a liniei aeriene la pozarea CIA conectarea corpului de iluminat	buc	68,0000	104,618	7 114,024
					83,018	5 645,224
	1	Muncitor	h-om	176,8000		
	1011977	Suruburi cu piulite si saibe	kg	1,3600		
	1019852	Vopsea	kg	8,8400		
	031050	Turle telescopice, 25 m	h-ut	84,3200		
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,3400		
7	08-02-376-32	Noduri sectorului tip a liniei electrice aeriene la pozarea CIA: instalare legarii la pamint pe stilpul de capat	buc	2,0000	104,618	209,236
					83,018	166,036
	1	Muncitor	h-om	5,2000		
	1011977	Suruburi cu piulite si saibe	kg	0,0400		
	1019852	Vopsea	kg	0,2600		
	031050	Turle telescopice, 25 m	h-ut	2,4800		
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0100		
8	RpED02A	Montarea cablurilor de energie electrica, instalate aparent pe scoabe de bachelita, pe console, cu sectiunea pina la 16 mmp	m	102,0000	6,970	710,960
					4,470	455,960
	7137010011520	Electrician in constructii	h-om	14,2800		
	5555	Cablu de energie AVVG 2*2.5mm2	m	102,0000		
9	08-03-526-1	Automat mono-, bi-, tripolar, montat pe constructii pe perete sau coloana, curent pina la 25 A	buc	2,0000	115,831	231,662
					49,811	99,622
	1	Muncitor	h-om	3,1200		
	8888	Automat VA 47-29 3p/C25	buc	2,0000		
	1011977	Suruburi cu piulite si saibe	kg	0,0980		
	330206	Masini de gaurit electrice	h-ut	0,0800		
10	08-02-363-1	Console metalice, speciale, sudate, pe stilpi, pentru corpuri de iluminat, cantitate becuri: 1	buc	136,0000	193,011	26 249,537
					108,881	14 807,857
	1	Muncitor	h-om	463,7600		
	126	Consola p/u corp de iluminat	buc	136,0000		
	031050	Turle telescopice, 25 m	h-ut	180,8800		
11	CN20B	Vopsitorii interioare sau exterioare aplicate pe timplarie metalica cu	m2	6,8000	54,433	370,144
					35,123	238,836

		email alchidic in 2 straturi inclusiv grundul				
	7141020013300	Zugrav vopsitor	h-om	7,4800		
	2430226100700	Grund alchidic	kg	0,7072		
	2430226109444	Diluant alchidic D.005-12 NI 1708-61 A1	kg	0,7480		
	2320166200676	White spirit	kg	0,6800		
12	RpEJ06C	Incerari, verificari electrice si reglari la corpuri de iluminat	buc	68,0000	19,797	1 346,169
					19,797	1 346,169
	7137010011520	Electrician in constructii	h-om	42,1600		
	Cheltuieli directe		Lei			39 091,819
	Asigurarea sociala si medicala		22,5 %			5 649,838
	Total					44 741,657
	Cheltuieli de regie		30 %			7 533,117
	Total					52 274,774
	Beneficiul de deviz		5 %			2 613,739
	Total					54 888,513
	Total Lucrari de montare Inclusiv salariu					54 888,513 25 110,391
	Cheltuieli directe		Lei			175 543,39
	Materiale auxiliare		5 %			4 762,89
	Total					180 306,28
	Cheltuieli de transport		5 %			4 762,89
	Total					185 069,17
	Cheltuieli de depozit		1,2 %			1 143,09
	Total					186 212,26
	TVA		20 %			37 242,46
	Total deviz: Inclusiv salariu					223 454,72 40 164,80

Intocmit

Director

A.Marta

(functioia, semnrtura)

Verificat

Primar

(functioia, semnrtura)



Investitor Iluminarea stradala s.Isaicani r-ul Nisporeni
Obiect

Catalog de preturi unitare pentru obiectul № Lucrari de electromontare (formular desfreurat)

Nr crt.	Simbol norme ei Cod resurse	Denumire lucrri, cheltuieli ei resurse	U.M.	Consum de resurse pe unitate de mrsurr	Valoare, lei	
					Pe unitate de mrsurr	Total incl. salariu
1	2	3	4	5	6	7
		1. Lucrari de constructie				
1	33-04-017-1	Suspendarea cu ajutorul mecanismelor a conductorilor izolati LEA 0,38 kV	1 km			14 772,833
						2 083,113
	1	Muncitor	h-om	65,2400	31,93	2 083,11
	999	Cleme de ramificare 16-95	buc		24,75	695,45
	66588	Coliere plastic 2.5*250	buc		1,00	33,06
	55588	Clama p/u banda	buc		2,47	71,45
	7788	Banda p/u montare	m		8,33	240,95
	7778	Clema de ancora PA-1000	buc		37,50	1 084,71
	777	Conductor SIP 2*25mm2	m		10,32	10 320,00
	031001	Autohidroascensoare, capacitate de ridicare 12 m	h-ut	24,4100	10,00	244,10
2	33-04-014-2	Montarea corpurilor de iluminat: cu lampi luminescente	buc			434,931
						73,120
	1	Muncitor	h-om	2,2900	31,93	73,12
	101-1714	Suruburi de constructii cu piulite si saibe	kg		100,00	4,41
	504	Corpuri de iluminat LED 30W	buc		337,50	188,60
	503	Corpuri de iluminat LED 50W	buc		361,98	159,70
	031001	Autohidroascensoare, capacitate de ridicare 12 m	h-ut	0,8000	10,00	8,00
	400001	Autocamion de bord, tonaj pina la 5 t	h-ut	0,1100	10,00	1,10
		2. Lucrari de montare				
3	08-02-376- 17	Noduri sectorului la pozarea CIA	buc			125,569
						105,369
	1	Muncitor	h-om	3,3000	31,93	105,37
	1011977	Suruburi cu piulite si saibe	kg	0,0200	100,00	2,00
	1019852	Vopsea	kg	0,1300	55,00	7,15
	031050	Turle telescopice, 25 m	h-ut	1,1000	10,00	11,00
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0050	10,00	0,05
4	08-02-376- 18	Noduri pe stilp intermediar	buc			50,681
						36,081
	1	Muncitor	h-om	1,1300	31,93	36,08
	1011977	Suruburi cu piulite si saibe	kg	0,0200	100,00	2,00

1	2	3	4	5	6	7
	1019852	Vopsea	kg	0,1300	55,00	7,15
	031050	Turle telescopice, 25 m	h-ut	0,5400	10,00	5,40
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0050	10,00	0,05
5	08-02-376-22	Noduri pe stilp de colt	buc			67,888
	1	Muncitor	h-om	1,6000	31,93	51,09
	1011977	Suruburi cu piulite si saibe	kg	0,0200	100,00	2,00
	1019852	Vopsea	kg	0,1300	55,00	7,15
	031050	Turle telescopice, 25 m	h-ut	0,7600	10,00	7,60
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0050	10,00	0,05
6	08-02-376-29	Noduri conectare corpului de iluminat	buc			104,618
	1	Muncitor	h-om	2,6000	31,93	83,02
	1011977	Suruburi cu piulite si saibe	kg	0,0200	100,00	2,00
	1019852	Vopsea	kg	0,1300	55,00	7,15
	031050	Turle telescopice, 25 m	h-ut	1,2400	10,00	12,40
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0050	10,00	0,05
7	08-02-376-32	Noduri instalare legarii la pamint pe stilpul de capat	buc			104,618
	1	Muncitor	h-om	2,6000	31,93	83,02
	1011977	Suruburi cu piulite si saibe	kg	0,0200	100,00	2,00
	1019852	Vopsea	kg	0,1300	55,00	7,15
	031050	Turle telescopice, 25 m	h-ut	1,2400	10,00	12,40
	400002	Automobile cu bord, tonaj pina la 8 t	h-ut	0,0050	10,00	0,05
8	RpED02A	Montarea cablurilor de energie electrica, instalate aparent pe scoabe de bachelita, pe console, cu sectiunea pina la 16 mmp	m			6,970
	7137010011520	Electrician in constructii	h-om	0,1400	31,93	4,47
	5555	Cablu de energie AVVG 2*2.5mm2	m		2,50	2,50
9	08-03-526-1	Automat mono-, bi-, tripolar, montat pe constructii pe perete sau coloana, curent pina la 25 A	buc			115,831
	1	Muncitor	h-om	1,5600	31,93	49,81
	8888	Automat VA 47-29 3p/C25	buc		60,00	60,00
	1011977	Suruburi cu piulite si saibe	kg	0,0490	100,00	4,90
	330206	Masini de gaurit electrice	h-ut	0,0400	28,00	1,12
10	08-02-363-1	Console metalice, speciale, sudate, pe stilpi, pentru corpuri de iluminat, cantitate becuri: 1	buc			193,011
	1	Muncitor	h-om	3,4100	31,93	108,88
	126	Consola p/u corp de iluminat	buc		70,83	70,83
	031050	Turle telescopice, 25 m	h-ut	1,3300	10,00	13,30
11	CN20B	Vopsitorii interioare sau exterioare aplicate pe timplarie metalica cu email alchidic in 2 straturi inclusiv grundul	m2			54,433
	7141020013300	Zugrav vopsitor	h-om	1,1000	31,93	35,12

1	2	3	4	5	6	7
	2430226100700	Grund alchidic	kg	0,1040	65,00	6,76
	2430226109444	Diluant alchidic D.005-12 NI 1708-61 A1	kg	0,1100	55,00	6,05
	2320166200676	White spirit	kg	0,1000	65,00	6,50
12	RpEJ06C	Incerari, verificari electrice si reglari la corpuri de iluminat	buc			19,797
	7137010011520	Electrician in constructii	h-om	0,6200	31,93	19,80

Intocmit

Director A.Marta SRL "Moldcablu"

(functioia, semnrtura)

Verificat

Primar

(functioia, semnrtura)

