

# Tightness test

## General information

Subject : IZYLUM 3 - 60 LH351C - Philips SR 150W - 700mA - Lumawise - CL I

Asked by : SZÜGYI János Péter

Created on : 25/10/2019

Validated on : 06/11/2019

Test number : D190994

Reference norm : IEC/EN 60598-1 Standard

Sample(s) : E190753

Folder : P-F19086

## Test conditions

Luminaire : IZYLUM 3

Number of LED : 60

LED : Samsung LH351C

Driver current (mA) : 700

Protector Material : Glass Extra Clear

Protector Shape : Flat

External accessories :

Lumawise


Preconditioning time (minutes) : 60

Operator : Philippe Léonard



IMG\_5364

## Conclusion

 Success

Conclusion :

IP66 granted.

Validated by :  
GHYSENS Gilles

Duplicate to : SZÜGYI János Péter, HORVÁTH Csaba, BEDŐ Péter, BOS Peter  
LAB : 06/11/2019

**D190994**

1/4



## Test(s) details

---

### Test(s)

Name	Description	Result
IP6X	<ul style="list-style-type: none"><li>- Luminaire switched ON until stable T°</li><li>- Talcum in suspension (blowing ON)</li><li>- After 1', luminaire OFF</li><li>- Talcum for 3 hours</li></ul>	Success
IPX6	<ul style="list-style-type: none"><li>- Luminaire switched ON until stable T°</li><li>- Luminaire switched OFF and immediately sprayed with water jet</li><li>- Hose diam. 12,5 mm</li><li>- Water flow: 100 l/min</li><li>- Spraying distance: 3 m</li><li>- Duration of test: 3 minutes</li></ul>	Success

### IP6X

#### Result(s)



Test succeeded no dust entry in the optical and auxiliary part.

---

### IPX6

#### Result(s)



Test succeeded no water ingress in the optical and auxiliary part.

**Test room temperature (°C) : 24**

**Measurement equipment :**

**IP6X**

**Talcum chamber (A003)**

**Thermometer (A039/2)**

**Chronometer (A043/6)**

**Caliper (M054/M055)**

**IPX6**

**Rotating table (A001/2)**

**Chronometer (A043/6)**

**Thermometer (A039/1)**

**Flowmeter (A001/9)**

**IPx6 nozzle (A001/5)**

**Quantities measured:**

**Verification of water/dust ingress within a luminaire enclosure according to**

**For IP2X: PT-S-14**

**For IP3X/4X: PT-S-15**

**For IP5X/6X: PT-S-06**

**For IPX3/X4: PT-S-01**

**For IPX5/X6: PT-S-08**

**For IPX7/X8: PT-S-09**

**Uncertainties:**

**Statement of uncertainties (K=2, 95% of confidence level):**

**Time: 0,35 seconds per 10 minutes**

**Temperature: 0,6 °K**

**Calipers: 0,005 mm**

**Measuring tape: ± 1,13 mm**

**Dynamometric key :**

**From 0.5 to 2.5 Nm : 0,15 Nm**

**From 2.5 to 5 Nm : 0,22 Nm**

**From 5 to 25 Nm : 0,83 Nm**

**From 25 to 60 Nm : 2,73 Nm**

**From 60 to 100 Nm : 3,55 Nm**

**For solid ingress test:**

**IP2X:**

**Probe dimensions: ± 0,6 mm**

**Applied force: ± 0,4 N**

**IP3X:**

**Probe dimensions: ± 0,3 mm**

**Applied force: ± 0,13 N**

**IP4X:**

**Probe dimensions: ± 0,1 mm**

**Applied force: ± 0,11 N**

**IP5X/6X**

Test duration (talcum suspension time):  $\pm 3$  seconds

Talcum mass: 0,02 %

For liquid ingress test:

**IPX3/X4**

Table rotation:  $\pm 6$  sec/rotation

Arms Rotation angle:  $\pm 3^\circ$

Water flow:  $\pm 4$  %

**IPX5/X6**

Table rotation:  $\pm 6$  sec/rotation

Water flow:  $\pm 4$  %

Test Distance: +0 / -50 cm

**IPX7/X8**

Test depth: +10 cm / -0 cm

**Decision rules:**

Pass/fail criteria

For solid ingress test:

**IP2X:**

If contact possible with live parts: fail

Otherwise: pass

**IP3X/4X:**

For luminaires without draining holes, nor ventilation slots for forced cooling, penetration of the test probe in the enclosure: fail

For luminaires with draining holes, or ventilation slots for forced cooling, if contact possible with live part: fail

Otherwise: pass

**IP5X/6X**

By visual inspection:

If possible hazard due to presence of conductive dust: fail

If no possible hazard due to the presence of conductive dust: IP5X granted

No presence of talcum: IP6X granted

For liquid ingress test:

**IPX3/X4/X5/X6:**

By visual inspection:

If possible hazard due to presence of water: fail

If no possible hazard due to the presence of water and no efficient way to evacuate the water: fail

If no possible hazard due to the presence of water and an efficient way to evacuate the water: pass

No presence of water: pass

**IPX7/X8:**

By visual inspection:

Presence of water: fail

No presence of water: pass

**End of test report** -----