

Beneficiar "FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924

Antreprenor "Alpro-Construct" SRL, IDNO 1009600009470

Obiect *Устройство шлифованных бетонных полов в секции компрессоров №1*

Contract Nr. 14931

DEVIZ LOCAL № 14931-1**Устройство шлифованных бетонных полов в секции компрессоров №1**

Valoarea de deviz 129 220.39 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	RpCK42A	Desfacerea pardoselilor reci	m2	2.000	35.64	71.27
					32.64	65.27
2	TsC54C	Strat de fundatie din pietris	m3	5.000	185.40	927.01
					107.70	538.51
3	RpCE09B	Instalare pelicula	m2	129.000	9.26	1 195.08
					3.26	421.02
4	RpCD08C	Instalare plasa din armatura (129m2)	kg	421.000	24.89	10 480.02
					3.92	1 648.83
5	CG22A2	Pardoseli din beton B25, cu strat consolidat (H=150mm, k=1.5 mater.)	m2	129.000	550.90	71 066.67
					135.99	17 542.39
Total			Lei			83 740.05
Asigurarea sociala				24.00 %		4 851.84
Transportarea materialelor				5.00 %		2 975.85
Total						91 567.74
Cheltuieli de regie				12.00 %		10 988.13
Total						102 555.87
Beneficiu de deviz				5.00 %		5 127.79
Total						107 683.66
TVA				20.00 %		21 536.73

Total deviz:**Lei****129 220.39**

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **"FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect *Устройство шлифованных бетонных полов в секции компрессоров №1*Contract Nr. **14931**

Anexa Nr. 1

Catalog de preturi unitare**Устройство шлифованных бетонных полов в секции компрессоров №1**
(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	RpCK42A	Desfacerea pardoselilor reci	m2			35.64
						32.64
	7132040012700	Parchetar	h-om	0.1500	94.60	16.32
	9310060019920	Muncitor deservire CM	h-om	0.1500	94.60	16.32
	4100126202818	Apa	m3	0.0500	0.00	0.00
	2922140006703	Macara fereastră	h-ut	0.0400	75.00	3.00
2	TsC54C	Strat de fundatie din pietris	m3			185.40
						107.70
	9310060019900	Muncitor necalificat	h-om	0.9900	94.60	107.70
	1421102200068	Pietris ciuruit nespalat de riu 7-15mm	m3	1.1500	0.00	0.00
	4100126202818	Apa	m3	0.1000	0.00	0.00
	2912340002506	Compresor mobil motor ardere interna, presiunea pina la 686 kPa (7atm), 2,2 m3/min	h-ut	0.2100	0.00	0.00
	2592270004021	Compactor pe pneuri sau mecanic 150 - 200 kg	h-ut	0.4200	185.00	77.70
3	RpCE09B	Instalare pelicula	m2			9.26
						3.26
	7134030012200	Izolator hidrofug	h-om	0.0600	94.60	3.26
	2682132603	Pelicula PE	m2	1.1200	4.31	4.88
	2922140006702	Macara de fereastră	h-ut	0.0150	75.00	1.13
4	RpCD08C	Instalare plasa din armatura (129m2)	kg			24.89
						3.92
	7123020011140	Fierar beton	h-om	0.0310	94.60	3.37
	9310060019920	Muncitor deservire CM	h-om	0.0050	94.60	0.54
	28731220511	Plase arm. Bp5*100*100	kg	1.0100	20.25	20.45
	2734113803116	Sirma neagra moale d = 1 mm	kg	0.0100	21.67	0.22
	2523156719079	Distantier pt.poz. arm in beton armat tip cupa	buc	0.1500	1.75	0.26
	2922140006702	Macara de fereastră	h-ut	0.0006	75.00	0.04
5	CG22A2	Pardoseli din beton B25, cu strat consolidat (H=150mm, k=1.5 mater.)	m2			550.90
						135.99
	7123010010200	Betonist	h-om	1.1500	94.60	125.11

9310060019920	Muncitor deservire CM	h-om	0.1000	94.60	10.88
2663102100350	Beton B25 (cu pompa)	m3	0.1025	2 101.31	323.08
265112210012	Sikafloor ProSeal-12	kg	0.1500	79.17	17.81
1135444004	Cordon de etansare	m	0.66667	7.92	7.92
11354118	Toping Sintop	kg	3.0000	8.75	39.38
2952160007200	Utilaj de ridicat pentru lucrari de finisaj	h-ut	0.1000	267.33	26.73

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar "FABRICA DE STICLA DIN CHISINAU" I.S., c.f. 1002600008924

Antreprenor "Alpro-Construct" SRL, IDNO 1009600009470

Obiect *Устройство шлифованных бетонных полов в секции компрессоров №1*

Contract Nr. 14931

DEVIZ LOCAL № 14931-1**Устройство шлифованных бетонных полов в секции компрессоров №1**

Valoarea de deviz 129 220.39 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7
Manopera:						
1.	7123010010200	Betonist	h-om	170.60	94.60	16 139.00
2.	7123020011140	Fierar beton	h-om	15.01	94.60	1 419.82
3.	7132040012700	Parchetar	h-om	0.35	94.60	32.64
4.	7134030012200	Izolator hidrofug	h-om	4.45	94.60	421.02
5.	9310060019900	Muncitor necalificat	h-om	5.69	94.60	538.51
6.	9310060019920	Muncitor deservire CM	h-om	17.60	94.60	1 665.04
Total manopera						20 216.02
Materiale:						
1.	11354118	Toping Sintop	kg	580.50	8.75	5 079.38
2.	1135444004	Cordon de etansare	m	129.00	7.92	1 021.68
3.	1421102200068	Pietris ciuruit nespalat de riu 7-15mm	m3	5.75	0.00	0.00
4.	2523156719079	Distantier pt.poz. arm in beton armat tip cupa	buc	63.15	1.75	110.51
5.	265112210012	Sikafloor ProSeal-12	kg	29.02	79.17	2 297.91
6.	2663102100350	Beton B25 (cu pompa)	m3	19.83	2 101.31	41 676.75
7.	2682132603	Pellicula PE	m2	145.92	4.31	628.94
8.	2734113803116	Sirma neagra moale d = 1 mm	kg	4.21	21.67	91.23
9.	28731220511	Plase arm. Bp5*100*100	kg	425.21	20.25	8 610.50
10.	4100126202818	Apa	m3	0.60	0.00	0.00
Total materiale de constructii						59 516.90
Utilaje de constructii:						
1.	2592270004021	Compactor pe pneuri sau mecanic 150 - 200 kg	h-ut	2.10	185.00	388.50
2.	2912340002506	Compresor mobil motor ardere interna, presiunea pina la 686 kPa (7atm), 2,2 m3/min	h-ut	1.05	0.00	0.00
3.	2922140006702	Macara de fereastră	h-ut	2.19	75.00	164.07
4.	2922140006703	Macara fereastră	h-ut	0.08	75.00	6.00
5.	2952160007200	Utilaj de ridicat pentru lucrari de finisaj	h-ut	12.90	267.33	3 448.56
Total utilaje de constructii						4 007.13
Total			Lei		83 740.05	
Asigurarea sociala			24.00 %		4 851.84	
Transportarea materialelor			5.00 %		2 975.85	
Total					91 567.74	
Cheltuieli de regie			12.00 %		10 988.13	
Total					102 555.87	
Beneficiu de deviz			5.00 %		5 127.79	

