

Obiectivul: Reparatia capitala a str.A.Perciun si Patria din or.Cimislia

Obiectul: Reparatia capitala a str.A.Perciun si Patria din or.Cimislia

Devizul: Reparatia capitala a str.A.Perciun si Patria din or.Cimislia

Devizul local de resurse Nr. 17.1.1

Intocmit in preturi curente 2019-05-13

Valoarea de deviz 270 981,807 (Lei)

Nr.	Simbol norme si Cod resurse	Denumire lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz (Lei)	
					Pe unitate de masura	Total
1	2	3	4	5	6	7
Manopera						
1	7123030012500	Montator P.B	h-om	2,2800	36,0000	82,080
2	7129020012800	Pavator	h-om	544,0000	36,0000	19 584,000
3	9310060019900	Muncitor necalificat	h-om	14,0300	36,0000	505,080
Total manopera					20 171,160	
Materiale						
1	1411122201646	Piatra sparta pentru pt.drumuri r.magmatice 15-25 mm	m3	69,3600	0,0000	0,000
2	1411122201672	Piatra sparta pentru pt.drumuri r.magmatice 40-63 mm	m3	863,6000	0,0000	0,000
3	1421102200525	Nisip (savura)	m3	174,7600	200,0000	34 952,000
4	2666122800611	Element prefabricat din beton armat	buc	12,0840	520,0000	6 283,680
5	4100116202806	Apa industriala in cisterne pt. lucrari drumuri-terasam.	m3	170,0000	5,0000	850,000
Total materiale					42 085,680	
Utilaje						
1	2952220003546	Autogreder pina la 175 cp	h-ut	169,3120	20,0000	3 386,240
2	2952220003546	Autogreder pina la 175 cp	h-ut	45,4578	410,0000	18 637,698
3	2952240004010	Compactor static autopropulsat cu rulouri valturi R 8-14 de 14tf	h-ut	175,4400	320,0000	56 140,800
4	2952270007403	Incarcator frontal pe senile 0,5 - 0,99 mc	h-ut	8,5680	120,0000	1 028,160
5	2952270007403	Incarcator frontal pe senile 0,5 - 0,99 mc	h-ut	79,1112	350,0000	27 688,920
6	3410520001373	Automacara 5 tf	h-ut	0,7200	120,0000	86,400
7	3410540000006	Autobasculanta-5t	h-ut	60,5000	20,0000	1 210,000
8	3410540000006	Autobasculanta-5t	h-ut	74,0000	250,0000	18 500,000
9	3410540005603	Autocisterna 5-8 t cu dispozitive de stropire	h-ut	17,0000	120,0000	2 040,000
Total utilaje					128 718,218	
Total					190 975,058	
Asigurari sociale si medicale			22,5000%		4 538,511	
Total					195 513,569	
Cheltuieli de regie			10,0000%		19 551,357	
Total					215 064,926	
Beneficiu de deviz			5,0000%		10 753,246	
TOTAL Deviz fara TVA					225 818,172	
Total					225 818,172	
TVA			20%		45 163,634	
TOTAL Deviz					270 981,807	

Intocmit:

(functia, semnatura, numele, prenumele)

Verificat:

(functia, semnatura, numele, prenumele)

