

Obiectivul: Lucrari de constructii complete sau partiale si lucrari publice

Obiectul: Reparatia portiunii de drum L362.1 drum de acces spre s. Minzatesti (varianta alba)

Devizul local de resurse Nr. 2.1

Intocmit in preturi curente 2024-09-10

Valoarea de deviz 909 500,00 (Lei)

Deviz: Reparatia imbracamintei rutiere in varianta alba (L=1700ml, b=5m)						
Nr.	Simbol norme si Cod resurse	Denumire lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz (Lei)	
					Pe unitate de masura	Total
1	2	3	4	5	6	7
Manopera						
1	7129020012800	Pavator	h-om	38,7600	76,42	2 962,16
2	9310060019900	Muncitor necalificat	h-om	162,8600	76,42	12 446,28
3	9310060019930	Muncitor	h-om	419,9000	76,42	32 090,10
Total manopera						47 498,54
Materiale						
1	11202062010361	Savura	m3	85,0000	269,82	22 935,05
2	1411122201645	Piatra sparta 5-10 mm	m3	85,0000	287,81	24 464,06
3	1411122201661	Piatra sparta 20-70 mm	m3	1 606,5000	287,81	462 370,66
4	14111222017521	Piatra sparta 10-20	m3	127,5000	287,81	36 696,08
5	4100116202806	Apa industrială in cisterne pt. lucrari drumuri-terasam.	m3	255,0000	17,09	4 357,66
Total materiale						550 823,52
Utilaje						
1	2952220003546	Autogreder pina la 175 cp	h-ut	22,8650	449,71	10 282,55
2	29522400040101	Compactor 10 t	h-ut	230,3500	269,82	62 153,99
3	2952240004105	Compactor 5-6 t	h-ut	95,2000	224,85	21 406,05
4	2952260003552	Buldozer pe senile 79 kW	h-ut	21,9300	449,71	9 862,07
5	29522700076111	Distribuito de criblura	h-ut	9,0100	449,71	4 051,86
6	3410540005603	Autocisterna 5-8 t cu dispozitive de stropire	h-ut	35,1900	314,79	11 077,63
Total utilaje						118 834,15
Total						717 156,22
Asigurari sociale				24,0000%		11 399,65
Total						728 555,87
Cheltuieli de regie				3,0000%		21 856,68
Total						750 412,54
Beneficiu de deviz				1,0000%		7 504,13
TOTAL Deviz fara TVA						757 916,67
Total						757 916,67
TVA				20%		151 583,33
TOTAL Deviz						909 500,00

Intocmit: SRL "Balt-Cons"

(functia, semnatura, numele, prenumele)

Verificat:

(functia, semnatura, numele, prenumele)