


1	2	3	4	5	6	7
		2. Частичный ремонт здания котельной				
		2.1. Демонтажные работы				
22	RpCI42B	Demontarea elementelor de acoperis - invelitori din tabla, asbociment, PVC, carton, pinza, stuf, etc, inclusiv tunsul tablei recuperabile	m2	44,000	25,64 25,20	1 128,16 1 108,80
23	RpCH32C	Desfacerea planseelor din lemn si a elementelor de acoperis - astereala invelitorilor cu sau fara recuperarea materialelor	m2	44,000	6,96 6,30	306,24 277,20
24	RpCH32B	Desfacerea planseelor din lemn si a elementelor de acoperis - sarpanta acoperisului cu desfacerea tuturor elementelor componente, inclusiv sortarea materialelor rezultate	m2	44,000	15,19 13,65	668,36 600,60
25	RpCO56A	Demontari: timplarie din lemn (ferestre)	m2	4,140	14,71 14,71	60,90 60,90
26	RpCR29A	Curatarea vopselei pe baza de ulei, cu decapant	m2	42,000	26,55 8,05	1 115,10 338,10
27	RpCO56C	Demontari: captuseli din lemn, asbociment, PFL, PAS, tec. la pereti sau tavane suspendate, usi, etc.(Разборка потолка из жестяных листов)	m2	42,000	8,75 8,75	367,50 367,50
28	RpCB18F	Demolarea betoanelor vechi cu mijloace mecanice, beton simplu(y входа двери)	m3	0,450	248,87 119,78	111,99 53,90
29	RpCB18F	Demolarea betoanelor vechi cu mijloace mecanice, beton simplu(отмостка)	m3	1,170	249,45 119,66	291,86 140,00
Total Демонтажные работы						4 050,11
Inclusiv salariu						2 947,00
		2.2. Кровля				
30	CE41A	Montarea capriorilor cu tratament antiseptic	m3	0,600	5 238,63 843,50	3 143,18 506,10
31	CN50A	Tratament ignifug al lemnariei, ferme, arce, grinzi, capriori, cosoroabe. S.R.L.	m3	0,600	187,90 29,75	112,74 17,85



fool