

ANTREPRENOR

"Alpro-Construct" SRL, IDNO
1009600009470

BENEFICIAR

IS "MOLDELECTRICA", IDNO
1002600004580

Coordonat:

Aprobat:

**Lucrari de protectie anticoroziva a
pilonilor metalici (20 buc.)**

(denumirea obiectivului)

Contract Nr. 14761

DEVIZ LOCAL № 6

LEA 110 kV Straseni - Peresecena nr. 1, 2 (tip pilon Y110-2+9) Total 2 piloni.

Valoarea de deviz 207 581.75 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2	742.80	5.10	3 789.62
	7141020013400	Vopsitor industrial	h-om	81.708	46.38	3 789.62
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 36 buc.	m2	122.40	6.51	797.11
	7134030012200	Izolator hidrofug	h-om	7.344	46.38	340.61
	2682132602	Пленка п/э	m2	137.088	3.33	456.50
	2922140006702	Macara de fereastră	h-ut	1.836	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2	742.80	171.50	127 390.78
	7141020013300	Zugrav vopsitor	h-om	2 064.984	46.38	95 773.96
	2430116104160	Email (с алюмин. пастой)	kg	178.272	103.93	18 527.81
	2430226100981 f	Grund anticorosiv 2 in 1	kg	118.848	62.50	7 428.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	31.198	53.67	1 674.40
	2320166200676	White spirit	kg	74.280	53.67	3 986.61
Total			Lei			131 977.51
Asigurarea sociala			24.00 %			23 977.01
Transportarea materialelor			6.00 %			1 924.40
Cheltuieli directe						157 878.92
Cheltuieli de regie			7.00 %			11 051.53
Total						168 930.45

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761**

Anexa Nr. 1

Catalog de preturi unitare**LEA 110 kV Straseni - Peresecena nr. 1, 2 (tip pilon Y110-2+9) Total 2 piloni.**
(formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2			5.10
	7141020013400	Vopsitor industrial	h-om	0.110	46.38	5.10
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 36 buc.	m2			6.51
	7134030012200	Izolator hidrofug	h-om	0.060	46.38	2.78
	2682132602	Пленка п/э	m2	1.120	3.33	3.73
	2922140006702	Macara de fereastră	h-ut	0.015	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2			171.50
	7141020013300	Zugrav vopsitor	h-om	2.780	46.38	128.94
	2430116104160	Email (с алюмин. пастой)	kg	0.240	103.93	24.94
	2430226100981f	Grund anticorosiv 2 in 1	kg	0.160	62.50	10.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	0.042	53.67	2.25
	2320166200676	White spirit	kg	0.100	53.67	5.37

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761****DEVIZ LOCAL № 6****LEA 110 kV Straseni - Persecena nr. 1, 2 (tip pilon Y110-2+9) Total 2 piloni.****Valoarea de deviz 207 581.75 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7
Manopera:						
1.	7134030012200	Izolator hidrofug	h-om	7.344	46.38	340.61
2.	7141020013300	Zugrav vopsitor	h-om	2 064.984	46.38	95 773.96
3.	7141020013400	Vopsitor industrial	h-om	81.708	46.38	3 789.62
Total manopera						99 904.19
Materiale:						
1.	2320166200676	White spirit	kg	74.280	53.67	3 986.61
2.	2430116104160	Email (с алюмин. пастой)	kg	178.272	103.93	18 527.81
3.	2430226100981f	Grund anticorosiv 2 in 1	kg	118.848	62.50	7 428.00
4.	2430226109260	Diluant 509 D.005-1 S 3123	kg	31.198	53.67	1 674.40
5.	2682132602	Пленка п/э	m2	137.088	3.33	456.50
Total materiale de constructii						32 073.32
Utilaje de constructii:						
1.	2922140006702	Macara de fereastră	h-ut	1.836	0.00	0.00
Total utilaje de constructii						0.00
Total			Lei			131 977.51
Asigurarea sociala			24.00 %			23 977.01
Transportarea materialelor			6.00 %			1 924.40
Cheltuieli directe						157 878.92
Cheltuieli de regie			7.00 %			11 051.53
Total						168 930.45
Beneficiu de deviz			2.40 %			4 054.34
Total						172 984.79
TVA			20.00 %			34 596.96

Total deviz:**Lei****207 581.75****Incluziv salariu****99 904.19**

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)