

**ANTREPRENOR**

"Alpro-Construct" SRL, IDNO  
1009600009470

**BENEFICIAR**

IS "MOLDELECTRICA", IDNO  
1002600004580

**Coordonat:**

\_\_\_\_\_  
\_\_\_\_\_

**Aprobat:**

\_\_\_\_\_  
\_\_\_\_\_

**Lucrari de protectie anticoroziva a  
pilonilor metalici (20 buc.)**

\_\_\_\_\_  
(denumirea obiectivului)

Contract Nr. 14761

**DEVIZ LOCAL № 3**

**LEA-35 kV Soldanesti 110 - UBA Soldanesti nr. 18 (tip pilon Y35-2+5)  
Total 1 pilon.**

Valoarea de deviz 86 031.84 Lei

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Lucrari si cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m. incl. salariu	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2	308.20	5.10	1 572.37
	7141020013400	Vopsitor industrial	h-om	33.902	46.38	1 572.37
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 12 buc.	m2	40.80	6.51	265.71
	7134030012200	Izolator hidrofug	h-om	2.448	46.38	113.54
	2682132602	Пленка п/э	m2	45.696	3.33	152.17
	2922140006702	Macara de fereastră	h-ut	0.612	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2	308.20	171.50	52 856.50
	7141020013300	Zugrav vopsitor	h-om	856.796	46.38	39 738.20
	2430116104160	Email (с алюмин. пастой)	kg	73.968	103.93	7 687.49
	2430226100981 f	Grund anticorosiv 2 in 1	kg	49.312	62.50	3 082.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	12.944	53.67	694.70
	2320166200676	White spirit	kg	30.820	53.67	1 654.11
Total			Lei			54 694.58
Asigurarea sociala			24.00 %			9 941.79
Transportarea materialelor			6.00 %			796.23
Cheltuieli directe						65 432.60
Cheltuieli de regie			7.00 %			4 580.29
Total						70 012.89



Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761**

Anexa Nr. 1

**Catalog de preturi unitare**  
**LEA-35 kV Soldanesti 110 - UBA Soldanesti nr. 18 (tip pilon Y35-2+5)**  
**Total 1 pilon.**  
 (formular desfasurat)

nr. crt.	Simbol norme si Cod resurse	Denumire lucrari, cheltuieli si resurse	U.M.	Consum resurse pe u.m.	Valoare, lei	
					pe u.m.	total incl. salariu
1	2	3	4	5	6	7
1	IzA04A	Pregatirea suprafetelor de metal in vederea aplicarii protectiei anticorozive prin curatire cu perie de sirma	m2			5.10
	7141020013400	Vopsitor industrial	h-om	0.110	46.38	5.10
2	RpCE09B	Straturi suplimentare de separare (Защита изоляторов п/э пленкой) - 12 buc.	m2			6.51
	7134030012200	Izolator hidrofug	h-om	0.060	46.38	2.78
	2682132602	Пленка п/э	m2	1.120	3.33	3.73
	2922140006702	Macara de fereastră	h-ut	0.015	0.00	0.00
3	IzA11A	Vopsirea constructiilor metalice, executata manual, de pe scari de fringhie	m2			171.50
	7141020013300	Zugrav vopsitor	h-om	2.780	46.38	128.94
	2430116104160	Email (с алюмин. пастой)	kg	0.240	103.93	24.94
	2430226100981F	Grund anticorosiv 2 in 1	kg	0.160	62.50	10.00
	2430226109260	Diluant 509 D.005-1 S 3123	kg	0.042	53.67	2.25
	2320166200676	White spirit	kg	0.100	53.67	5.37

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)

Beneficiar **IS "MOLDELECTRICA", IDNO 1002600004580**Antreprenor **"Alpro-Construct" SRL, IDNO 1009600009470**Obiect **Lucrari de protectie anticoroziva a pilonilor metalici (20 buc.)**Contract Nr. **14761****DEVIZ LOCAL № 3****LEA-35 kV Soldanesti 110 - UBA Soldanesti nr. 18 (tip pilon Y35-2+5)****Total 1 pilon.****Valoarea de deviz 86 031.84 Lei**

Intocmit in preturi curente

nr. crt.	Simbol norme si Cod resurse	Denumire resurse	U.M.	Cantitate conform datelor din proiect	Valoarea de deviz, lei	
					pe u.m.	total
1	2	3	4	5	6	7
<b>Manopera:</b>						
1.	7134030012200	Izolator hidrofug	h-om	2.448	46.38	113.54
2.	7141020013300	Zugrav vopsitor	h-om	856.796	46.38	39 738.20
3.	7141020013400	Vopsitor industrial	h-om	33.902	46.38	1 572.37
<b>Total manopera</b>						<b>41 424.11</b>
<b>Materiale:</b>						
1.	2320166200676	White spirit	kg	30.820	53.67	1 654.11
2.	2430116104160	Email (с алюмин. пастой)	kg	73.968	103.93	7 687.49
3.	2430226100981f	Grund anticorosiv 2 in 1	kg	49.312	62.50	3 082.00
4.	2430226109260	Diluant 509 D.005-1 S 3123	kg	12.944	53.67	694.70
5.	2682132602	Пленка п/э	m2	45.696	3.33	152.17
<b>Total materiale de constructii</b>						<b>13 270.47</b>
<b>Utilaje de constructii:</b>						
1.	2922140006702	Macara de fereastră	h-ut	0.612	0.00	0.00
<b>Total utilaje de constructii</b>						<b>0.00</b>
<b>Total</b>			<b>Lei</b>	<b>54 694.58</b>		
Asigurarea sociala			24.00 %	9 941.79		
Transportarea materialelor			6.00 %	796.23		
Cheltuieli directe				65 432.60		
Cheltuieli de regie			7.00 %	4 580.29		
<b>Total</b>				<b>70 012.89</b>		
Beneficiu de deviz			2.40 %	1 680.31		
<b>Total</b>				<b>71 693.20</b>		
TVA			20.00 %	14 338.64		

**Total deviz: Lei 86 031.84****Incluziv salariu 41 424.11**

Intocmit

(functia, semnatura)

Verificat

(functia, semnatura)