SPECIFICATION			SPECIFICATIA			
Marca Positie	Symbol Insemnare	Name	Denumire	Unit U.M.	Quantity Cant.	Note Nota
1		Ductile iron flanged nonrising stem	Vana-pana din fonta maleabila cu tija			
		wedge gate valve PN10 ø80	neascendenta cu flanse PN10 ø80	pcs buc	2	L=180mm
2		—11— ø100	—11— ø100	pcs buc	6	
3		—11— ø150	—11— ø150	pcs buc	3	
4		—11— ø200	—11— ø200	pcs buc	1	
5		—11— ø300	—11— ø300	pcs buc	9	
6		Ductile iron valve with PE reducing	Ventil din fonta maleabila cu reductie			
		pipes PN10 ø25	PE PN10 ø25	pcs buc	1	
7		ø50	ø50	pcs buc	1	
8		Combination flanged air valve, cast	Ventuza combinata din fonta cu flanse			
		iron PN16 ø80	PN16 ø80	pcs buc	2	
9		Cast iron flanged flap valve PN10	Supapa de retinere cu flanse din			
		ø100	fonta PN10 ø100	pcs buc	2	
10		Ductile iron fire hidrant for	Hidrant de incendiu subteran din			
		undeground installation PN16	fonta maleabila PN16			
		ø100 h=980 mm	ø100 h=980 mm	pcs buc	4	
11		—11— ø100 h=1230 mm	—11— ø100 h=1230 mm	pcs buc	2	
12		Handwhell for gate valve ø25	Mansa pentru ventile, vane ø25	pcs buc	1	
13		—11— ø50	—11— ø50	pcs buc	1	
14		—11— ø80	—11— ø80	pcs buc	2	
15		—11— ø100	—11— ø100	pcs buc	6	
16		—11— ø150	—11— ø150	pcs buc	3	
17		—11— ø200	—11— ø200	pcs buc	1	
18		—11— ø300	—11— ø300	pcs buc	9	
19a		Ductile iron all flanged tee PN10	Teu cu flanse din fonta maleabila			
		ø100x80	PN10 ø100x80	pcs buc	1	
19		—11— ø300x80	—11— ø300x80	pcs buc	1	
20		—11— ø300x100	—11— ø300x100	pcs buc	11	
21		—11— ø300x150	—11— ø300x150	pcs buc	1	
22		—11— ø300x200	—11— ø300x200	pcs buc	1	
23		—11— ø300x300	—11— ø300x300	pcs buc	4	
24		Ductile iron all flanged taper PN10	Reductie cu flanse din fonta maleabila			
		ø300x150	PN10 ø300x150	pcs buc	1	
24.1		Steel transition PN10 ø350x300	Tranzitia otelului PN10 ø350x300	pcs buc	1	
25		HDPE/Steel adaptor PE100 PN10	Reductie polietilen/otel PE100 PN10			
		ø32x25	ø32x25	pcs buc	1	
26		—11— ø63x50	—11— ø63x50	pcs buc	1	
27		—11— ø110x100	—11— ø110x100	pcs buc	3	
28			Not used position			
29		—11— ø200x200	—11— ø200x200	pcs buc	1	
30		—11— ø315x300	—11— ø315x300	pcs buc	2	
31		Electrofusion coupling PE100 SDR11 ø32	Mufa electrosudabila PE100 SDR11 ø32	pcs buc	3	
32		—11— ø63	—11— ø63	pcs buc	4	
33		Electrofusion reducing coupling	Mufa electrosudabila de reductie			
		PE100 SDR11 ø63x32	PE100 SDR11 ø63x32	pcs buc	1	
34		Pipe PE80 SDR13.6 PN10 ø32	Teava PE80 SDR13.6 PN10 ø32	m	9	
35		Pipe PE80 SDR13.6 PN10 ø63	Teava PE80 SDR13.6 PN10 ø63	m	8	

Инв. № подл. | Подпись и дата | Взам. инв. №

SPECIFICATION			SPECIFICATIA			
Marca Positie	Symbol Insemnare	Name	Denumire	Unit U.M.	Quantity Cant.	Note Nota
36		Pipe PE100 SDR17 PN10 ø110	Teava PE100 SDR17 PN10 ø110	m	42	
37		—11— ø160	—11— ø160	m	10	
38		—11— ø200	—11— ø200	m	11	
39		—11— ø315	—11— ø315	m	1160	
40		PE welded tee PE100 SDR17	Teu sudat din polietilena PE100 SDR17			
		ø315x110	ø315x110	pcs buc	3	
41		—11— ø315x160	—11— ø315x160	pcs buc	1	
42		HPPE welded bend 30° PE100 SDR17	Cot sudat 30° PE100 SDR17			
		ø110	ø110	pcs buc	1	
43		HPPE welded bend 45° PE100 SDR17	Cot sudat 45° PE100 SDR17			
		—11— ø200	ø200	pcs buc	2	
44		—11— ø315	—11— ø315	pcs buc	7	
44.1		Welded elbow PE 90 ° section 90 ° PE100 SDR17 ø315	Cot sudat PE 90° sectiune 90° PE100 SDR17 ø315	pcs buc	2	
44.2		Welded bend ПНД 315/10 °, PE100, SDR-13.6	Cot sudat ПНД 315/10 °, PE100, SDR-13.6	pcs buc	1	
44.3		Welded bend ПНД 315/15 °, PE100, SDR-11	Cot sudat ПНД 315/15 °, PE100, SDR-11	pcs buc	1	
45		HPPE welded taper PE100 SDR17	Reductie sudata PE100 SDR17 ø315	pcs buc	2	
		ø110x63	ø110x63	pcs buc	2	
46		Sleeve under flange PE100 PN10	Manson sub flansa PE100 PN10	pcs buc		
		ø110x100	ø110x100	pcs buc	4	
47		—11— ø160x150	—11— ø160x150	pcs buc	1	
48		—11— ø200x200	—11— ø200x200	pcs buc	1	
49		—11— ø315x300	—11— ø315x300	pcs buc	31	
50		Loose flange PN10 ø100	Flansa libera ø100	pcs buc	4	
51		—11— ø150	—11— ø150	pcs buc	1	
52		—11— ø200	—11— ø200	pcs buc	1	
53		—11— ø300	—11— ø300		31	
54			Not used position			
55		Casing for pipe passing through well walls PE100, PN6, L=0.20m	Carcasa pentru trecerea tevilor din polietilena prin peretii caminelor			
		ø63	PE100, PN6, L=0.20m ø63	pcs buc	2	
56		—11— ø110	—11— ø110	pcs buc	1	
57		—11— ø200	—11— ø200	pcs buc	7	
58		—11— ø250	—11— ø250	pcs buc	3	
59		—11— ø315	—11— ø315	pcs buc	1	
60	GOST 10704-91	Item, steel pipe L=0.20m ø426x6	Idem, teava de otel L=0.20m ø426x6	pcs buc	31	
61	GOST 10704-91	Steel welded pipe ø32x2.2	Teava de otel sudata electric ø32x2.2	m	2	
62	—11—	—11— ø60x2.5	—11— ø60x2.5	m	2	
63	—11—	—11— ø108x3	—11— ø108x3	m	9	
64	—11—	—11— ø159x4	—11— ø159x4	m	21	
65	GOST 10704-91	Steel welded pipe ø219x6	Teava de otel sudata electric ø219x6	m	1	
66	—11—	—11— ø325x6	—11— ø325x6	m	2	
67	GOST 17375-01	Steel bend 45° ø159x4.5	Cot din otel 45° ø159x4.5	pcs buc	6	

SPECIFICATION			SPECIFICATIA			
Marca Positie	Symbol Insemnare	Name	Denumire	Unit U.M.	Quantity Cant.	Note Nota
68	—11—	—11— ø325x8	—11— ø325x8	pcs buc	2	
68.1	GOST 17375-01	Steel bend 60° ø325x8	Cot din otel 60° ø325x8	pcs buc	1	
69	GOST 17375-01	Steel bend 90° ø159x4	Cot din otel 90° ø159x4	pcs buc	2	
69.1	GOST 17375-01	Steel bend 60° ø108x4	Cot din otel 60° ø108x4	pcs buc	2	
69.2	GOST 17375-01	Steel bend 45° ø108x4	Cot din otel 45° ø108x4	pcs buc	1	
69.3	Изготовить на месте	Steel bend 55° ø108x4	Cot din otel 55° ø108x4	pcs buc	1	
69.4	Изготовить на месте	Steel bend 50° ø108x4	Cot din otel 50° ø108x4	pcs buc	1	
69.5	GOST 17375-01	Steel bend 45° ø57x3	Cot din otel 45° ø57x3	pcs buc	3	
69.6	GOST 17375-01	Steel bend 90° ø426x6	Cot din otel 90° ø426x6	pcs buc	2	
69.7	GOST 17375-01	Steel bend 45° ø426x6	Cot din otel 45° ø426x6	pcs buc	1	
70	GOST 17378-01	Steel taper ø325x10 – 108x4	Reductie din otel ø325x10 – 108x4	pcs buc	1	
71	se executa la fata locului	Steel sochet ø159x4	Mufa de otel ø159x4	pcs buc	1	
72	—11—	—11— ø219x6	—11— ø219x6	pcs buc	2	
73	GOST 12820-80	Welded flange 1-100-16	Flansa 1-100-16	pcs buc	1	
74	—11—	—11— 1-150-16	—11— 1-150-16	pcs buc	3	
75	GOST 10704-91	Steel casing ø426x6 L=3.00	Carcasa de otel ø426x6 L=3.00	pcs buc	2	
76	—11—	—11— L=8.45	—11— L=8.45	pcs buc	1	
77	—11—	—11— L=9.00	—11— L=9.00	pcs buc	1	
78	—11—	—11— L=10.00	—11— L=10.00	pcs buc	4	
79	—11—	—11— L=10.50	—11— L=10.50	pcs buc	2	
80	—11—	—11— L=11.60	—11— L=11.60	pcs buc	1	
81	—11—	—11— ø273x6 L=6.50	—11— ø273x6 L=6.50	pcs buc	1	
82	—11—	—11— ø219x6 L=12.40	—11— ø219x6 L=9.00	pcs buc	1	
83	—11—	—11— L=14.00	—11— L=12.40	pcs buc	1	
84	—11—	—11— ø159x6 L=5.00	—11— ø159x6 L=5.00	pcs buc	1	
85	GOST 10704-91	Steel casing ø108x3 L=3.50	Carcasa de otel ø108x3 L=3.50	pcs buc	1	
86	GOST 10704-91	Steel casing ø426x6 L=3.00	Carcasa de otel ø426x6 L=1.50	pcs buc	1	
87	GOST 10704-91	Steel casing ø426x6 L=3.00	Carcasa de otel ø426x6 L=1.80	pcs buc	1	
88	GOST 10704-91	Steel casing ø426x6 L=3.00	Carcasa de otel ø426x6 L=4.30	pcs buc	1	
89	GOST 10704-91	Steel casing ø426x6 L=3.00	Carcasa de otel ø426x6 L=4.50	pcs buc	1	
90	GOST 1839-80	Asbestos-cement pipe (power cables	Teava din azbestociment (carcasa			
		casing) L=2.00m ø100	pentru cabluri electrice) L=2.00m ø100	m	16	
		Warning tape	Banda de avertizare cu inscriptia			
91		"Mind pipe-line!"	"Atentie apeduct!"	m	1250	
92		Indicator HI (ПГ)	Indicator HI (ПГ)	pcs buc	6	
	GOST 10704-91	Steel pipe (water pipe-line casings	Teava de otel (manta pentru apeduct			
		at the crossing points with cables)	in locurile de intersectie cu cablurile)			
93		L=1.00m ø219x6	L=1.00m ø219x6	pcs buc	9	
94		—11— ø273x6	—11— ø273x6	pcs buc	7	
95		—11— ø426x6	—11— ø426x6	pcs buc	10	

Change	No.part	Page	No.doc	Signature	Date
Project manager		Gubareva			09.20
Chief spec.		Gubareva			09.20
Designed		Vainer			09.20
Checked		Gubareva			09.20

3660-6-WSS

Rehabilitation of the land supply system in Balti municipality.
Aqueduct from Fyodor Dostoevsky Street to Independentei Street, Sportiva Street to str. N. Gluhovski (stage I from str. Alexandr Puskin to str. N. Gluhovski).

External water supply network

Specification

Stage	Page	Total
WP	10	

INTEXNAUCA S.A.
Chisinau 2020

Schim	Nr.sect.	Foaia	Nr.doc	Semnet.	Data
Ingener-sef					
de proiect		Gubareva			09.20
Sp. prin.		Gubareva			09.20
Elabor		Vainer			09.20
N. contr.		Gubareva			09.20

3660-6-AE

Reabilitarea sistemului de alimentare cu apa in mun. Balti.
Apeduct de pe str. Fiodor Dostoievski pe str.Independentei, str. Sportiva pina la str. N. Gluhovski (etapa I de la str. Alexandr Puskin pina la str. N. Gluhovski).

Retea exterioară de alimentare cu apă

Specificatia

Faza	Foaia	Foi
PE	10	

INTEXNAUCA S.A.
Chisinau 2020

format A3x3